### **GENERAL NOTES**

- 1. THE LOCATIONS OF EXISTING UTILITIES, AS SHOWN ON THE PLANS, ARE BASED UPON FIELD INVESTIGATIONS AND THE BEST INFORMATION AVAILABLE. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO ASCERTAIN THE EXACT LOCATIONS FROM THE UTILITY COMPANIES PRIOR TO BEGINNING ANY EXCAVATION.
- WHERE SECTION OR SUB-SECTION MONUMENTS ARE ENCOUNTERED, THE ENGINEER SHALL BE NOTIFIED BEFORE SUCH MONUMENTS ARE REMOVED. THE CONTRACTOR SHALL PROTECT AND PRESERVE PROPERTY MARKERS AND MONUMENTS UNTIL THE OWNER, AN AUTHORIZED SURVEYOR, OR AGENT HAS WITNESSED OR OTHERWISE REFERENCED THEIR LOCATIONS
- 3. ALL EXISTING PUBLICLY AND PRIVATELY OWNED UTILITIES REQUIRING ADJUSTMENT WILL BE MADE BY THE UTILITY COMPANY INVOLVED UNLESS OTHERWISE NOTED. WHERE NO PROVISIONS HAVE BEEN MADE FOR ADJUSTMENTS ON THE PLANS, NO ADDITIONAL COMPENSATION WILL BE ALLOWED DUE TO DELAYS OR INCONVENIENCE CAUSED BY SAID UTILITY ADJUSTMENTS.
- 4. EXISTING PAVEMENT, SIDEWALK, AND CURB & GUTTER THAT ARE INTENDED TO REMAIN BUT ARE DAMAGED DUE TO THE CONTRACTOR'S NEGLIGENCE SHALL BE REPLACED AT THE EXPENSE OF THE CONTRACTOR TO THE SATISFACTION OF THE ENGINEER.
- 5. DISABLED ACCESSIBILITY FEATURES (SIDEWALK SLOPES, CURB RAMPS, ETC) SHALL NOT DEVIATE FROM THE PLANS AND STANDARDS INCLUDED. CONSTRUCT RAMPS AT ALL SIDEWALK -ROADWAY INTERSECTIONS AS SHOWN ON THE PLANS.
- 6. TEMPORARY AGGREGATE SURFACE SHALL BE USED FOR DRIVEWAYS AND ROADWAY CROSSINGS AFTER STORM SEWER INSTALLATION AND DURING DRIVEWAY CURB AND PAVEMENT CONSTRUCTION OPERATIONS AND AT LOCATIONS AT THE DIRECTION OF THE ENGINEER. THE COST OF TEMPORARY AGGREGATE SHALL BE INCLUDED IN THE CONTRACT UNIT PRICES FOR AGGREGATE FOR TEMPORARY
- 7. MAILBOXES WHICH INTERFERE WITH THE PROPOSED IMPROVEMENTS SHALL BE CAREFULLY REMOVED BY THE CONTRACTOR, INSTALLED AT A TEMPORARY LOCATION AND REINSTALLED AT A PERMANENT LOCATION WHEN ALL ROADWAY WORK IS DONE AS DIRECTED BY THE ENGINEER AND APPROVED BY PROPERTY OWNER. RELOCATING MAILBOXES SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR EARTH EXCAVATION
- 8. WATER MAIN CONSTRUCTION SHALL BE IN ACCORDANCE WITH APPLICABLE SECTIONS OF THE LATEST EDITION OF THE STANDARD SPECIFICATIONS FOR WATER AND SEWER CONSTRUCTION IN ILLINOIS AND THE SPECIAL PROVISIONS.
- 9. WHEREVER IT IS NECESSARY TO REMOVE EXISTING GRAVEL OR CRUSHED STONE BASE COURSE. IT SHALL BE REMOVED AT THE CONTRACT UNIT PRICE PER CUBIC YARD FOR EARTH EXCAVATION AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED FOR ADDITIONAL LABOR OR EQUIPMENT REQUIRED.
- 10. THE CONTRACTOR MAY BE REQUIRED TO CONDUCT SOME OF HIS GRADING OPERATIONS AROUND TRANSMISSION POLES AND UNDER TRANSMISSION LINES. THE ADDED COST OF SO DOING SHALL BE CONSIDERED INCLUDED IN THE COST OF THE VARIOUS BID ITEMS BEING CONSTRUCTED.
- 11. TRENCH BACKFILL SHALL BE PROVIDED UNDER ALL ROADWAY SURFACES, DRIVEWAYS, AND
- 12. EXISTING DRAINAGE PIPES CONNECTED TO NEW STRUCTURES: IN ACCORDANCE WITH SECTION 602 OF THE STANDARD SPECIFICATIONS, THE CONNECTING OF EXISTING DRAIN TILES. PIPE CULVERTS OR STORM SEWER TO THE PROPOSED DRAINAGE SYSTEM STRUCTURES WILL NOT BE PAID FOR SEPARATELY BUT SHALL BE CONSIDERED AS INCLUDED IN THE PAY ITEMS PROVIDED.

#### **ENVIRONMENTAL REVIEWS**

PRIOR TO THE USE OF ANY PROPOSED BORROW AREAS, USE AREAS (TEMPORARY ACCESS ROADS, DETOURS, RUN-AROUNDS, ETC.) AND/OR WASTE AREAS, THE CONTRACTOR SHALL FILE THE REQUIRED ENVIRONMENTAL RESOURCE REQUEST SURVEYS ACCORDING TO SECTION 107.22 OF THE STANDARD SPECIFICATIONS. THESE SURVEYS ARE REQUIRED IN ORDER FOR THE DEPARTMENT TO CONDUCT CULTURAL AND BIOLOGICAL RESOURCE SURVEYS FOR THE PROPOSED SITE.

PRIOR TO ANY WASTE MATERIALS BEING REMOVED FROM THE CONSTRUCTION SITE THE REQUIRED ENVIRONMENTAL RESOURCE SURVEYS WILL NEED TO BE OBTAINED AND FILED BY THE CONTRACTOR. EXCESS WASTE PRODUCTS REMOVED FROM THE CONSTRUCTION SITE SHALL BE DISPOSED OF AS REQUIRED IN SECTION 202.03 OF THE STANDARD SPECIFICATIONS.

ANY PROTRUDING METAL BARS SHALL BE REMOVED PRIOR TO THE DISPOSAL OF BROKEN CONCRETE AT APPROVED DISPOSAL SITES.

THE REQUIRED ENVIRONMENTAL RESOURCE DOCUMENTATION SHALL INCLUDE THE FOLLOWING:

- BDE FORM 2289 (ENVIRONMENTAL SURVEY REQUEST)
- A LOCATION MAP SHOWING THE SIZE LIMITS AND LOCATION OF THE USE AREA
- SIGNED PROPERTY OWNER AGREEMENT FORM -D4 PI0100 - COLOR PHOTOGRAPHS DEPICTING THE USE AREA
- BORROW AREA ENTRY AGREEMENT FORM -D4 PIO101

PLEASE NOTE THAT A MINIMUM OF TWO WEEKS SHALL BE ALLOWED FOR THE DISTRICT TO OBTAIN THE REQUIRED ENVIRONMENTAL CLEARANCES.

#### SOIL REPORT AVAILABILITY

ALL SOILS DATA COLLECTED AND PROCESSED FOR THE SOILS REPORT MADE IN CONJUNCTION WITH THE DESIGN OF THIS IMPROVEMENT IS ON FILE AT THE CITY OF MACOMB WHERE IT IS AVAILABLE FOR INSPECTION BY CONTRACTORS OR PROSPECTIVE BIDDERS. BY SUBMITTING A BID, THE CONTRACTOR ACKNOWLEDGES THAT THE SOILS REPORT HAS BEEN MADE AVAILABLE AND IS AWARE OF THE REPORT CONTENTS AND APPENDICES.

# LEGEND

		£	
	PROPERTY LINE	⊗ <sup>GV</sup>	GAS VALVE
	EXISTING RIGHT OF WAY	☐ PED	UTILITY PEDESTAL
	PROPOSED RIGHT OF WAY	<b>\$</b>	LIGHT POLE
	PROPOSED TEMP CONSTR. EASEMENT	₽>	POWER POLE AND GUY WIRE
0	FOUND IRON MARKER	0	EXISTING MANHOLE
$\bigcirc$	TREE LINE	<b>\(\theta\)</b>	BUSH
	EDGE OF FIELD	Elens.	EVICTIVIO TORE WITH CITE
	EDGE OF ROAD	E. S	EXISTING TREE WITH SIZE
	CONCRETE CURB	<b>*</b> 12"	EXISTING PINE TREE W/ SIZE
	EDGE OF GRAVEL	 A	EXISTING FIRE HYDRANT
	EXISTING WATER MAIN		
	EXISTING SANITARY SEWER	⊗ <sup>w∨</sup>	EXISTING WATER VALVE
	EXISTING STORM SEWER	Д	EXISTING DOMESTIC WATER METER VAULT
	PROPOSED STORM SEWER	*ở*	EXISTING DOMESTIC WATER SERVICE BOX
	PROPOSED WATER SERVICE	⊜ <sup>INL</sup> (OR) <b>=</b>	EXISTING STORM INLET
INL-2 → OR ◆	PROPOSED STORM INLET W/ DESIGNATION		SATELLITE DISH
MH-B	PROPOSED STORM MANHOLE W/ DESIGNATION	TOP	TOP OF MANHOLE ELEVATION
STM-55	PROPOSED STORM PIPE DESIGNATION	ΙE	INVERT ELEVATION
— <b>Q</b> ⊗—	RELOCATED DOMESTIC SERVICE BOX AND METER	EP	EDGE OF PAVEMENT ELEVATION

RATE OF APPLICATION TABLE						
AGGREGATE (SURFACE, BASE OR BACKFILL)	2.05 TONS/CU YD					
BITUMINOUS MATERIALS (PRIME COAT)	0.08 GAL/SQ.YD.					
BITUMINOUS SURFACE AND BINDER	0.056 TONS/SQ.YD./INCH					
SEEDING AREAS NITROGEN FERTILIZER NUTRIENT PHOSPHORUS FERTILIZER NUTRIENT POTASSIUM FERTILIZER NUTRIENT MULCH	90 LBS/ACRE 90 LBS/ACRE 90 LBS/ACRE 2 TONS/ACRE					

### LIST OF BENCH MARKS

BM #7 - CAP BOLT IN WORD "MUELLER" ON FIRE HYDRANT NE CORNER OF WARD AND JEFFERSON ELEVATION 700.85

BM #8 - CAP BOLT IN WORD "MUELLER" ON FIRE HYDRANT SE CORNER OF WARD AND WASHINGTON ELEVATION 702.41

# LIST OF UTILITIES

J.U.L.I.E. ———	180	0-8	392-012
WATER	CITY	OF	масоме
SANITARY SEWER	CITY	OF	масоме
STORM SEWER	CITY	OF	МАСОМВ
TELEPHONE	VERIZ	ZON	
GAS	AMER	REN	CIPS
ELECTRIC -	AMER	REN	CIPS
CABLE TELEVISION	СОМО	CAS	Т

CITY OF MACOMB-WARD STREET

SEC 09-00139-01-PV FAIL 6919 PROJ. ARA-5040 (010) CONTRACT No. 89527 SHT 2 OF 32

SHEET NO of 32

MCCLURE Engineering Associates. Inc



		1	٠.	-	1
		DATE			
	REVISIONS	ITEM			
		Ŏ.			

IMPROVEMENTS - PHASE 2, LEGEND AND BENCH MARKS Y OF MACOMB

WARD STREET II GENERAL NOTES, CITY