



LEGEND:

TEMPORARY LIGHTING UNIT

50 FT. MOUNTING HEIGHT, 15 FT. MAST ARM 400 WATT, 120 VOLT LUMINAIRE WITH PHOTOCELL

ON EACH LUMINAIRE

AERIAL CABLE, 3-1/C NO. 4, ALUMINUM, WITH MESSENGER WIRE

 \square

GROUND ROD, 5/8" DIAMETER X 10 FT.

ELECTRIC SERVICE DISCONNECT, LIGHTING AND TRAFFIC SIGNAL

EXISTING UTILITY POLE

TEMPORARY WOOD POLE, 45 FT, CLASS 5

ENGINEER

DATE: 7/8/2008 SEAL EXPIRES: 11/30/2009

NOTES

- 1. TEMPORARY LIGHTING SHALL BE INSTALLED AND OPERATIONAL BEFORE THE START OF
- POLE SHALL BE SET BACK 18 FT. FROM THE EDGE OF THE TRAVELLED PAVEMENT, UNLESS OTHERWISE REQUIRED BY THE FIELD CONDITIONS.
- 3. TEMPORARY LIGHTING SHALL REMAIN OPERATIONAL FOR BOTH STAGE I AND STAGE II. STAGE I SHOWN.
- 4. ALL POLES SHOWN ON THIS PLAN SHALL BE INSTALLED BY THE LIGHTING CONTRACTOR.

G O	Ciorba Gi	roup, Ir
بال	CONSULTING ENGIN 5507 North Cumberlas Chicago, Illinois 6065	nd Avenue, Suite
)	Tel. 773.775.4009	Fax 773.775.

IC.	USER NAME = jcoleman	DESIGNED	-	JMV	REVISED	m.
		DRAWN	-	МВ	REVISED	-
402	PLOT SCALE = 50.0000 '/ IN.	CHECKED	-	VMU	REVISED	-
4014	PLOT DATE = 7/8/2008	DATE	-	07/09/2008	REVISED	-
	·				·	

STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION**

FAS 1317 / ILLINOIS ROUTE 113 OVER TERRY CREEK TEMPORARY LIGHTING PLAN									
SCALE: 1"=50"	SHEET N	0. 1 0	OF 4 :	SHEETS	STA.	TO			

F.A.S. SECTION				COUNTY	TOTAL	SHEE NO.
1317 111 B-2				WILL	32	12
				CONTRACT	NO. 6	D86
FED. RO	DAD DIST. NO.	ILLINOIS	FED. Al	ID PROJECT		