# INDEX OF SHEETS

- COVER SHEET
- INDEX OF SHEETS, LIST OF STATE STANDARDS, SCOPE OF WORK AND GENERAL NOTES
- SUMMARY OF QUANTITIES
- SUGGESTED STAGES OF CONSTRUCTION AND TRAFFIC CONTROL NOTES
- EXISTING STRUCTURAL DRAWINGS FOR INFORMATION ONLY 5 - 9
- TRAFFIC CONTROL DETAILS FOR FREEWAY SHOULDER CLOSURES, PARTIAL RAMP CLOSURES (TC-17)

## LIST OF STATE STANDARDS

## STANDARD NO. DESCRIPTION

000001 - 05 STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS

664001 -- 01 CHAIN LINK FENCE

701400 - 02 APPROACH LANE CLOSURE, FREEWAY/EXPRESSWAY

701401 - 04 LANE CLOSURE FREEWAY/EXPRESSWAY

701446 TWO LANE CLOSURE FREEWAY/EXPRESSWAY

701801 - 03 LANE CLOSURE MULTILANE...

701901 TRAFFIC CONTROL DEVICES

704001 - 04 TEMPORARY CONCRETE BARRIER

701411 - 04 LANE CLOSURE, MULTILANE AT ENTRANCE OR EXIT RAMP.

LANE CLOSURE, MULTILANE, INTERMITTANT OR MOVING

OPERATIONS.

# SCOPE OF WORK

- INSTALL 150' TEMPORARY FENCE AT SITE, PROVIDE ACCESS CONTROL FOR I-90 AND SECURE THE CONSTRUCTION SITE.
- INSTALL 78 SQ. YD. OF PROTECTIVE SHIELDING IN THE SPAN OVER I-90 AND CTA.
- REMOVE ENTIRE SUPERSTRUCTURE INCLUDING THREE BRIDGE SPANS AND CONCRETE STAIRCASE.
- PARTIAL REMOVAL OF THE CONCRETE SUB STRUCTURE:

REMOVE PIERS 1 AND 2 FLUSH WITH THE ADJACENT RETAINING WALL AND MEDIAN BARRIER WALL.

REMOVE STAIR PIER AND LANDING FOOTING TO 2 FEET BELOW THE EXISTING GRADE.

- INSTALL ACCESS CONTROL FENCE AND METRA STATION PLATFORM FENCE:

INSTALL 140'± - CHAIN LINK FENCE 4' TO COMPLETE ACCESS CONTROL FENCE ALONG ARGYLE ST.

INSTALL 28'± - CHAIN LINK FENCE 4', ATTACHED TO STRUCTURE ON TOP OF THE ABUTMENT ALONG THE CTA TRACKS

AND RETAINING WALL ALONG THE OUTSIDE SHOULDER.

INSTALL 12'± - CHAIN LINK FENCE 4'. ATTACHED TO STRUCTURE ALONG METRA STATION PLATFORM.

- REMOVE THREE CITY OF CHICAGO LIGHT POLES, TWO MOUNTED ON THE STRUCTURE AND ONE ON CONCRETE FOUNDATION AT STAIRCASE LANDING.
- REMOVE 538 SQ. FT. OF SIDEWALK IN THE PARKWAY AND SPUR TO THE STAIR CASE.
- RESTORE DISTURBED AREAS WITH TOPSOIL, SODDING AND WOOD MULCH.

#### GENERAL NOTES

- 1. THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH RESPECTIVE UTILITIES OR THE CITY OF CHICAGO INCLUDING THE CTA AND METRA. BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "CUAN" CHICAGO UTILITY ALERT NETWORK AT (312) 744-7000 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS FACILITIES. (48 HOUR NOTIFICATION IS REQUIRED). CONTACT THE CTA AT (312) 922-4080 FOR ELECTRIC SERVICE LOCATIONS. CTA IS NOT PART OF CUAN OR JULIE.
- 2. THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.
- 3. WHEN ARTIFICIAL LIGHTING IS USED IN NIGHT OPERATIONS, THE CONTRACTOR SHALL EXERCISE THE UTMOST PRECAUTIONS IN PREVENTING ADVERSE VISIBILITY TO THE MOTORING PUBLIC AND ADJOINING RESIDENTIAL AREAS.
- 4. THIS WORK IS IN THE CHICAGO GATEWAY GREEN PARTNERSHIP AREA. THE CONTRACTOR WILL NOT BE ALLOWED TO STORE MATERIALS OR EQUIPMENT ON THE KENNEDY EXPRESSWAY RIGHT-OF-WAY.
- 5. THE CONTRACTOR SHALL COORDINATE THE EXPRESSWAY LANE CLOSURES WITH THE LAWRENCE AVENUE OVER I-90 PROJECT, WHICH WILL BE CONSTRUCTED IN 2009.
- 6. THE 12 FOOT LENGTH OF FENCE ATTACHED TO THE METRA STATION PLATFORM SHALL HAVE A BLACK VINYL COATING ON ALL POSTS, POLES, HARDWARE AND FENCE FABRIC. THE COST OF FOR THIS MATERIAL SHALL BE INCLUDED IN THE UNIT PRICE FOR "CHAIN LINK FENCE 4', ATTACHED TO STRUCTURE".

## CTA NOTES

- 1. WHEN THE CONTRACTOR IS DISMANTLING THE PEDESTRIAN OVERPASS BRIDGE HE SHALL AVOID ANY DAMAGE TO THE CTA STRUCTURES AND MAINTAIN THE EXISTING CLEARANCES.
- 2. THE CONTRACTOR SHALL FOLLOW ALL THE SPECIAL REQUIREMENTS OF THE CTA WHEN WORKING OVER AND NEXT TO CTA TRACKS. SEE SPECIAL PROVISION "CTA COORDINATION."

# METRA NOTES

1. WHEN THE CONTRACTOR IS DISMANTLING THE PEDESTRIAN OVERPASS BRIDGE, HE SHALL AVOID ANY DAMAGE TO THE METRA STATION PLATFORM.

# UNION PACIFIC RAILROAD NOTES

WHEN WORKING ON UNION PACIFIC PROPERTY:

- 1. WORK WINDOWS WILL BE FROM 9:00 AM 3:30 PM, MONDAY THRU FRIDAY. EXTENDED WORK WINDOWS MAY BE AVAILABLE ON WEEKENDS.
- NIGHT WORK WINDOWS ARE AVAILABLE FROM 8:00 PM TO 4:00 AM. PLEASE PROVIDE AT LEAST 2-3 BUSINESS DAYS OF ADDITIONAL NOTICE WHEN REQUESTING TO WORK AT NIGHT TO ENSURE APPROPRIATE FLAGGING COVERAGE. ALSO, THERE CAN BE NO WORK EQUIPMENT ON THE COMMUTER PLATFORM.
- 2. A CONTRACTOR'S RIGHT OF ENTRY PERMIT IS REQUIRED BEFORE ANY WORK CAN COMMENCE ON UNION PACIFIC PROPERTY.
- 3. FLAGGING PROTECTION WILL BE REQUIRED FOR ALL WORK WITHIN 25 FEET OF THE NEAREST TRACK, OR AS DETERMINED BY THE UNION PACIFIC.
- 4. DEMOLITION PLANS MUST BE REVIEWED AND APPROVED BY THE UNION PACIFIC.

NOTE: BOXED ITEMS ARE INCIDENTAL.

SCALE: 1'

FILE NAME = D16ØE58-sht-gennote.dgn PLOT DATE = 7/15/2008

CHRISTIAN-ROGE & ASSOCIATES, INC.	DESIGNED	-	M.P.	REVISED	
CHRISTIAN-ROGE & ASSOCIATES, INC. ENGINEERS-PLANNERS-SURVEYORS 211 WEST WACKER DRIVE	DRAWN	-	A.C.S.	REVISED	-
CHICAGO, ILLINOIS 60606	CHECKED	-	S.J.P	REVISED	be-
PHONE: (312)372-2023 FAX: (312)372-5274	DATE	-	JULY 15, 2008	REVISED	-

STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION** 

INDEX OF SHEETS, LIST OF STATE STANDARDS, SCOPE OF WORK AND		F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
GENERAL NOTES LONG AVENUE PEDESTRIAN		90	2008-027 DM	COOK	10	2
				CONTRACT NO. 60E58		
SCALE: 1" = 50'   SHEET NO. 1 OF 1 SHEETS   STA.	TO STA.	FED. RO	AD DIST, NO. 1 ILLINOIS FED. AL	D PROJECT		