## COMMITMENTS

1. CONSTRUCTION EQUIPMENT IS NOT TO BE HOUSED OUTSIDE OF THE ROADWAY ON THE SOUTHBOUND I-57 EXIT RAMP ON THE NORTHWEST OUADRANT OF THE DIAMOND INTERCHANGE FROM THE BEGINNING OF THE EXISTING DEPARTURE CURVE (RAMP B STA. 224+80.78) TO THE CENTER OF THE EXISTING TRANSITION CURVE (RAMP B STA. 233+60.20). THIS IS EQUIVALENT TO STA. 1352+61.09 TO STA. 1360+18.16 ON I-57. THIS AREA OF THE RAMP WILL ONLY BE RESURFACED, WITH NO CONSTRUCTION WORK OUTSIDE OF THE EXISTING ROADWAY, TO ENSURE NO IMPACTS WILL OCCUR TO A NEARBY WETLAND THAT IS OUTSIDE OF THE EXISTING ROADWAY. IDOT RIGHT-OF-WAY. WETLAND BOUNDARIES ARE LOCATED OUTSIDE OF THE SCOPE OF WORK FOR THIS PROJECT.

CROSS SECTIONS - 1-57 HIGHWAY STANDARDS

## LIST OF APPLICABLE HIGHWAY STANDARDS

000001-05

		STA.	J SIA.
		FED. ROAD DIST. NO. ILLINO	IS FED. AID PROJECT
STD NO.	TITLE	•99(1&2) R-3&9-1HB-1-BR-2	CONTRACT: 62253
202001-01	EARTH MEDIAN DITCH CHECK	*33(102) N 303 IND 1 DN 2	CONTINACT: 02255
280001 - 04	TEMPORARY EROSION CONTROL SYSTEMS		
420001-07	PAVEMENT JOINTS		
420101 - <b>04</b>	7.2 M (24') JOINTED PCC PAVEMENT		
420106 - <i>04</i>	10.8 M (36') JOINTED PCC PAVEMENT		
420111 - <i>0</i> <b>2</b>	PCC PAVEMENT ROUNDOUTS		
420701- <i>02</i>	PAVEMENT FABRIC		
421101 - 07	7.2 M (24') CRC PAVEMENT		
421106 - 07	10.8 M (36') CRC PAVEMENT		
424001-05	CURB RAMPS FOR SIDEWALKS		
442201 - <b>03</b>	CLASS C AND D PATCHES		
482001-0Z	HMA SHOULDER - ADJACENT TO FLEXIBLE PAVEMENT		
482011 - 03	HMA SHOULDER STRIPS/SHOULDERS WITH RESURFACING OR WIDENING AND RESURFACING PROJECTS		
483001-04	PCC SHOULDER		
515001 - 02	NAME PLATE FOR BRIDGE		
542301-01	PRECAST REINFORCED CONCRETE FLARED END SECTION		
601001-02	SUB-SURFACE DRAINS		
601101	CONCRETE HEADWALL FOR PIPE DRAIN		
	CATCH BASIN, TYPE A		
602001	CATCH BASIN, TIPE A		
602011	CATCH BASIN, TYPE C		
602301-0/	INLET, TYPE A		
602401-0/	MANHOLE, TYPE A		
602601 - <i>01</i>	PRECAST REINFORCED CONCRETE FLAT SLAB TOP		
602701-01	CAST IRON STEPS		
604001-02	FRAME AND LIDS, TYPE 1		
604006- <i>03</i>	FRAME AND GRATE, TYPE 3		
604036-01	GRATE, TYPE 8		
604086-01	FRAME AND GRATE, TYPE 23		
604091 701	FRAME AND GRATE, TYPE 24		
606001-43	CONCRETE CURB AND COMBINATION CONCRETE CURB AND GUTTER		
606301 <i>-03</i>	PC CONCRETE ISLAND AND MEDIANS		
606306-02.	CORRUGATED_PC_CONCRETE_MEDIANS		
630001-07	STEEL PLATE BEAM GUARDRAIL		
630301-04	SHOULDER WIDENING FOR TYPE 1 (SPECIAL) GUARDRAIL TERMINALS		
631011 - 04	TRAFFIC BARRIER TERMINAL TYPE 2		
631026-04	TRAFFIC BARRIER TERMINAL TYPE 5 & 5A		
631031 -00	TRAFFIC BARRIER TERMINAL TYPE 6		
635001	DELINEATORS		
635006 - 02	REFLECTOR AND TERMINAL MARKER PLACEMENT		
635011 - <i>OI</i>	REFLECTOR MARKER AND MOUNTING DETAILS		
664001 - <i>01</i>	CHAIN LINK FENCE		
667101	PERMANENT SURVEY MARKERS		
701001-01	OFF-ROAD OPERATION 2L, 2W, 4.5 M (15') MIN. AWAY		
701006 <i>-02</i>	OFF-ROAD OPERATION 2L, 2W, 4.5 M (15') TO PAVEMENT EDGE		
701101 - <i>01</i>	OFF-ROAD OPERATIONS, MULTILANE LESS THAN 4.5 M (15') TO PAVEMENT EDGE		
701106 - <i>al</i>	OFF-ROAD OPERATIONS, MULTILANE MORE THAN 4.5 M (15') AWAY		
701201 ~ <i>0</i> <b>Z</b>	LANE CLOSURE, 2L, 2W, DAY ONLY ON-ROAD TO 600 MM (24") OFF-ROAD FOR SPEEDS > 45 MPH LANE CLOSURE, 2L, 2W, NIGHT ONLY ON-ROAD TO 600 MM (24") OFF-ROAD FOR SPEEDS > 45 MPH		
701206 - <i>01</i>	LANE CLOSURE, 2L, 2W, NIGHT ONLY ON-ROAD TO 600 MM (24") OFF-ROAD FOR SPEEDS > 45 MPH	*	
701301 - <i>02</i>	TANE CLOSURE 2L. 2W SHORT TIME OPERATIONS		
701306 <i>-01</i>	LANE CLOSURE 2L, 2W SLOW MOVING OPERATIONS - DAY ONLY FOR SPEEDS > 45 MPH		
701311 - <i>02</i>	LANE CLOSURE 2L, 2W MOVING OPERATIONS - DAY ONLY _		
701326 <i>-02</i>	LANE CLOSURE 2L, 2W PAVEMENT WIDENING FOR SPEEDS > 45 MPH		
701400 <i>~02</i>	APPROACH TO LANE CLOSURE FREEWAY/EXPRESSWAY LANE CLOSURE, FREEWAY/EXPRESSWAY		
701401 <i>-04</i>	LANE CLOSURE, FREEWAY/EXPRESSWAY		
701402 - <i>06</i>	LANE CLOSURE, FREEWAY/EXPRESSWAY, W/ BARRIER _		
701411 - 04	LANE CLOSURE MULTILANE AT ENTRANCE OR EXIT RAMP FOR SPEEDS > 45 MPH		
701426 <i>-02</i>	LANE CLOSURE MULTILANE INTERMITTENT OR MOVING OPERATION FOR SPEEDS > 45 MPH		
701501 <i>-04</i>	URBAN LANE CLOSURE 2L, 2W UNDIVIDED		
701606 <i>-05</i>	URBAN LANE CLOSURE, MULTILANE, 2W WITH MOUNTABLE MEDIAN		
701701 - <i>05</i>	URBAN LANE CLOSURE, MULTILANE INTERSECTION		
701901	TRAFFIC CONTROL DEVICES		
704001 <i>-04</i>	TEMPORARY CONCRETE BARRIER		
720001	SIGN PANEL MOUNTING DETAILS		
720006-01	SIGN PANEL ERECTION DETAILS		
720011	METAL POSTS (SIGNS, MARKERS AND DELINEATORS)		
720016- <i>01</i>	MAST ARM MOUNTED STREET NAME		
720021- <i>01</i>	SIGN PANELS, EXTRUDED ALUMINUM TYPE		
729001	APPLICATION OF TYPE A AND B METAL POSTS		
780001- <i>01</i>	TYPICAL PAVEMENT MARKINGS		
781001 - 02	TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS		
805001	ELECTRICAL SERVICE INSTALLATION DETAILS		
	The state of the s		
814001-44	CONCRETE HANDHOLES		
814001-01	CONCRETE HANDHOLES		
814006-01	DOUBLE HANDHOLES		
877001 - <i>03</i>	STEEL MAST ARM ASSEMBLY AND POLE		
878001-06	CONCRETE FOUNDATION DETAILS		
880006	TRAFFIC SIGNAL MOUNTING DETAILS		
886001	DETECTOR LOOP INSTALLATIONS		
886006	TYPICAL LAYOUT FOR DETECTION LOOPS		
000001-05	STANDARD SYMBOLS, ABBREVIATIONS, AND PATTERNS		

Clark Ure	tz
ENGINEERS	

STANDARD SYMBOLS, ABBREVIATIONS, AND PATTERNS

DESIGN FIRM REGISTRATION No. 184-000450 118 SOUTH CLINTON STREE SUITE 600

ILLINOIS DEPARTMENT OF TRANSPORTATION I-57 AT MANHATTAN - MONEE ROAD INDEX OF SHEETS, LIST OF APPLICABLE HIGHWAY STANDARDS, GENERAL NOTES, COMMITMENTS

SCALE: VERT. NTS DATE 9/19/2008

DRAWN BY KLM CHECKED BY TMW

TOTAL SHEE NO.

303 2

COUNTY

TO STA.

WILL

SECTION

57