
STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

SHEET NO. 6 OF 124BR-DEWITT 64 43 760

CONTRACT NO. 70014



Detail I - With Bar Splicer or Couplers: Connect one (1) 1''x7''x10'' steel f_c^p to the top layer of couplers with $2^{-5}8''$ ϕ bolts screwed to coupler at approximate © of

Connect one (1) 1"x7"x10" steel \mathbb{P} to the concrete slab with 2- 58 " ϕ Expansion Anchors or cast in place inserts spaced between the top layer of reinforcement at approximate Q of

Cost of anchorage is included with Temporary Concrete Barrier.

NOTES

each barrier panel.


Detail II - With Extended Reinforcement Bars:

each barrier panel.

SECTIONS THRU SLAB

NEW SLAB

*** Dimension shown is minimum required embedment into concrete. If hot-mix asphalt wearing surface is present, minimum embedment shall be in addition to wearing surface depth.



DETAIL I

when "A" is greater than 3'-6".


The 1"x7"x10" Plate shall not be removed until Stage II Construction forms and reinforcement bars are in place.

BWB

MAA

RMR

BSC



The 1"x7"x10" Plate shall not be removed until Stage II Construction forms and all reinforcement bars are in place and the concrete is ready to be placed.

EXISTING SLAB


op bars spacing → @ ⁷8'' ¢ Holes * @ 1"x12" Notch

P 1"x7"x10"

* Required only with Detail II

** Wood blocks may be omitted when required to provide minimum. stage traffic lane width. When the wood blocks are omitted, the concrete barrier shall be in direct contact with the steel retainer plate.

PLANS PREPARED BY:



WOOLPERT LLP 343 Fountains Parkway, Suite A Fairview Heights, IL 62208-2044 618.632.7004

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION IL ROUTE 48 OVER TRIBUTARY TO FRIENDS CREEK DITCH FAP 760 - SECTION 124BR-1 DEWITT COUNTY STATION 73+02.00 STRUCTURE No. 020-2011 TEMPORARY CONC. BARRIER FOR STAGE CONST.

CHECKED R-27

DRAWN

DESIGNED