



LIGHTING CONTROLLER SPECIAL WIRING DIAGRAM NOT TO SCALE

## SCHEDULE OF DEVICES

MAIN BREAKER 2P, 100A

CONTACTOR 2P, 100A, 120V

BRANCH BREAKERS, 2P, 30A, 240V

CONTROL BREAKER 1P, 20A, 120V

4. CONTROL BREAKER IP, 20A, 120V
5. CONTROL RELAY 20A, 120V, ON-DELAY
6. H-O-A SWITCH, 120V
7. LIGHT SWITCH
8. LIGHT FIXTURE
9. DUPLEX RECEPTACLE, 20A, GFCI
10. TERMINAL BLOCK
11. THERMOSTAT

12. HEATER STRIP, 150W 13. SURGE SUPPRESSOR
14. TERMINAL BLOCK
15. NEUTRAL BUS

16. GROUND BUS 17. CECHA APPROVED METER HOUSING. CONTRACTOR SHALL COORDINATE WITH COMED FOR PROPER LOCATION AND SIZING.

Ciorba Group, Inc.

507 North Cumberland Avenue, Suite 402 Chicago, Illinois 60656 el. 773.775.4009 Fax 773.775.4014 Email chicago@ciorba.com

CITY OF NORTH CHICAGO MARTIN LUTHER KING JR. DRIVE IMPROVEMENTS

MARTIN LUTHER KING JR. DRIVE LIGHTING IMPROVEMENTS LIGHTING DETAILS

SCALE: NTS

DRAWN BY: KDM DATE: APRIL, 2008 CHECKED BY: JMV