


CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE					
				90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE
				ROADWAY 0004 URBAN	S.N. 016-1510 0011 URBAN	S.N. 016-1512 0011 URBAN	SAFETY 0021 URBAN	SIGN STRUCTURES 0040 URBAN	DRAINAGE 0044 URBAN
51204650	PILE SHOES	EACH	134		72	62			
51500100	NAME PLATES	EACH	2		1	1			
52000110	PREFORMED JOINT STRIP SEAL	FOOT	201		118	83			
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	21		21				
52100510	ANCHOR BOLTS, 3/4"	EACH	48			48			
52100520	ANCHOR BOLTS, 1"	EACH	16			16			
52100530	ANCHOR BOLTS, 1 1/4"	EACH	42		42				
52100540	ANCHOR BOLTS, 1 1/2"	EACH	14		14				
54215547	METAL END SECTIONS 12"	EACH	8						8
58700300	CONCRETE SEALER	SO FT	11359		5,894	5,465			
59100100	GEOCOMPOSITE WALL DRAIN	SO YD	122		60	62			
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	8						8
60105000	PIPE DRAINS, CORRUGATED STEEL OR ALUMINUM ALLOY 12"	FOOT	320						320
60107700	PIPE UNDERDRAINS 6"	FOOT	383						383

* SPECIALTY ITEM

FILE NAME =	DESIGNED - AAA	REVISED -		STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
USER NAME = tblank	DRAWN - TMB	REVISED -							373	10707-608 & 611HB-8	COOK	177	7
PLOT DATE = 6/27/2014	CHECKED - JMM	REVISED -			SCALE: N.T.S. SHEET 4 OF 10 SHEETS STA. TO STA.				CONTRACT NO. 60W77				
DATE - 6/23/2014	REVISOR -	REVISED -			ILLINOIS FED. AID PROJECT								