

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE						
				90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	
				ROADWAY	S.N. 016-1510	S.N. 016-1512	SAFETY	SIGN STRUCTURES	DRAINAGE	
				0005 URBAN	0014 URBAN	0014 URBAN	0021 URBAN	0040 URBAN	0044 URBAN	
X7030040	WET REFLECTIVE TEMPORARY TAPE TYPE III, 6 INCH	FOOT	2398	2398						
X8040310	ELECTRIC SERVICE DISCONNECT	EACH	2				2			
X8710027	FIBER OPTIC CABLE, 4 FIBERS, SINGLE MODE	FOOT	300				300			
X8710030	FIBER OPTIC CABLE 48 FIBERS, SINGLE MODE	FOOT	5000				5000			
X8730249	ELECTRIC CABLE IN CONDUIT, NO. 19 6/C	FOOT	750				750			
X8730312	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO.18 4/C, TWISTED, SHIELDED	FOOT	1100				1100			
X8850102	INDUCTION LOOP	FOOT	40				40			
XX006821	CONCRETE TRUCK WASHOUT	L SUM	1				1			
X0328502	CLOSED CIRCUIT TELEVISION CAMERA STRUCTURE, GALVANIZED STEEL, 50' MOUNTING HEIGHT	EACH	2				2			
X0325500	STAINLESS STEEL JUNCTION BOX TYPE "J" INSTALL ONLY	EACH	4				4			
87000785	ELECTRIC CABLE ASSEMBLY IN CONDUIT, 600V(XLP-TYPE TC) 2/C NO. 2 AND NO.6 GRND	FOOT	1500				1500			
X0327965	ELECTRIC CABLE NO. 19, 50 PAIR	FOOT	5500				5500			
X0329965	TEMPORARY WOOD POLE, 50 FT, CLASS 4	L SUM	1				1			

* SPECIALTY ITEM

FILE NAME	DESIGNED -	REVISED -
...\\Gene...\\0180W77-sht-500-12.dgn	DRAWN -	REVISED -
USER NAME - jmojwskl	CHECKED -	REVISED -
PLOT DATE - 6/7/2014	DATE - 6/23/2014	REVISED -



STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES			
SCALE: N.T.S.	SHEET 106 OF 10	SHEETS	STA. TO STA.

F.A.P. FILE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
373	10707-608 & 611HB-B	COOK	177	136
ILLINOIS FED. AID PROJECT			CONTRACT NO. 60W77	

Rev.

12