

**PAVEMENT SCHEDULE**

LOCATION			30300112	40603085	40603340	42000501	42001300	42001420	42001430	48101202	48203057	Z0005216	X4060110
AGGREGATE SUBGRADE IMPROVEMENT 12"			HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	PROTECTIVE COAT	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	AGGREGATE SHOULDERS, TYPE B	HOT-MIX ASPHALT SHOULDERS, 15"	HOT-MIX ASPHALT STABILIZATION 6" AT SPBGR	BITUMINOUS MATERIALS (PRIME COAT)	
ROAD	START STRCT	END STRCT	SQ YD	TON	TON	SQ YD	SQ YD	SQ YD	SQ YD	CU YD	SQ YD	SQ YD	POUND
IL 171	016-0486	016-1510				625	625.03					34	
IL 171	016-1510	016-0483				356	655.58			11.213		67	
RAMP E	016-1026	016-1512							402.93	2.51			
RAMP E	016-1512	END PROJ							340.25				
I-55	016-1510	016-1512	3037	15	10	89					2693		140
TOTAL			3037	15	10	89	981	1281	744	14	2693	101	140

**DRAINAGE SCHEDULE**

LOCATION		60100060	60107700	60200305	60218300	60235610	60500040	60500050	60500060	61000225
CONCRETE HEADWALLS FOR PIPE DRAINS		PIPE UNDERDRAIN S 6"	CATCH BASINS, TYPE A, 4'- DIAMETER, TYPE 3	MANHOLES, TYPE A, 4'- DIAMETER, TYPE 1 FRAME, OPEN LID	INLETS, TYPE A, TYPE 2 FRAME AND GRATE	REMOVING MANHOLES	REMOVING CATCH BASINS	REMOVING INLETS	TYPE F INLET BOX, STANDARD 610001	
ROAD	STRUCTURE	EACH	FOOT	EACH	EACH	EACH	EACH	EACH	EACH	EACH
I-55	016-1512	4	195			10			10	
I-55	016-1510	4	188	2	2	6	2	2.00	6	
IL-171	016-1512									4
IL-171	016-1510									4
TOTAL		8	383	2	2	16	2	2	16	8

**MOT SCHEDULE**

LOCATION	SIDE	FROM STA	TO STA	70301000	70400100	70600330	78100200	78200530	78300100	78300200	X7030040
				WORK ZONE PAVEMENT MARKING REMOVAL	TEMPORARY CONCRETE BARRIER	IMPACT ATTENUATORS, TEMPORARY (FULLY- REDIRECTIVE, NARROW), TEST LEVEL 3	TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER	BARRIER WALL MARKERS, TYPE C	PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	WET REFLECTIVE TEMPORARY TAPE TYPE III, 6 INCH
				(SQ FT)	(FOOT)	(EACH)	(EACH)	(EACH)	(SQ FT)	(EACH)	(FOOT)
I-55	CD ROAD/SB	310+11.95	320+50.65	791	2825	4	14	113	1920	11	2398
I-55	SB/NB	310+48.39	319+95.55		2775	3		111			
TOTAL				791	5600	7	14	224	1920	11	2398

**CONCRETE BARRIER SCHEDULE**

LOCATION	FROM STA	TO STA	42001300	63700275	63700805	63700900	64300260	78200530	X0325349
			PROTECTIVE COAT	CONCRETE BARRIER, DOUBLE FACE, 42 INCH HEIGHT	CONCRETE BARRIER TRANSITION	CONCRETE BARRIER BASE	IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	BARRIER WALL MARKERS, TYPE C	TEMPORARY CONCRETE BARRIER (TO REMAIN PERMANENTLY)
			SQ YD	FOOT	FOOT	FOOT	EACH	(EACH)	FOOT
I-55 (CD ROAD/SB)	310+04.62	312+94.22	520.48	223	30	223			
I-55 (SB/NB)	311+08.28	313+03.36	291.75	125	30	125			
I-55 (CD ROAD/SB)	316+28.08	317+99.90	183.71	78.71	15	78.71	1	6	150
I-55 (SB/NB)	316+24.66	318+12.75	220.68	94.55	15	94.55	2	11	275
TOTAL			1217	522	90	522	3	17	425

**REMOVAL SCHEDULE**

LOCATION			44000100	44001980	44004250
PAVEMENT REMOVAL			CONCRETE BARRIER REMOVAL	PAVED SHOULDER REMOVAL	
ROAD	START STRCT	END STRCT	SQ YD	FOOT	SQ YD
IL 171	016-0486	016-1510	0		0
IL 171	016-1510	016-0483	0		0
RAMP E	016-1026	016-1512	183		254
RAMP E	016-1512	END PROJ	35		118
I-55	016-1512	016-1510	89	677	2730
TOTAL			307	677	3103

**EROSION CONTROL SCHEDULE**

LOCATION			20101000	28000250	28000315	28000400	28001100
			TEMPORARY FENCE	TEMPORARY EROSION CONTROL SEEDING	AGGREGATE DITCH CHECKS	PERIMETER EROSION BARRIER	TEMPORARY EROSION CONTROL BLANKET
ROAD	START STRCT	END STRCT	FOOT	POUND	TON	FOOT	SQ YD
IL 171	016-0486	016-1510		26.1	0	321	1265
IL 171	016-1510	016-0483	542	16.3	0	321	789
RAMP E	016-1026	016-1512		107.9	44	480	2733
RAMP E	016-1512	END PROJECT		42.1	44	480	2037
TOTAL			542	193	88	1602	6824

**PAVEMENT MARKING SCHEDULE**

LOCATION			78000200			78000400	78005110			78005140	78005150	78100100			
			THERMOPLASTIC PAVEMENT MARKING - LINE 4"			THERMOPLASTIC PAVEMENT MARKING - LINE 6"	EPOXY PAVEMENT MARKING - LINE 4"			EPOXY PAVEMENT MARKING - LINE 8"	EPOXY PAVEMENT MARKING - LINE 12"	RAISED REFLECTIVE PAVEMENT MARKER			
			YELLOW LINE	WHITE LINE	WHITE 2' DASH 6' SKIP	WHITE 2' DASH 6' SKIP	YELLOW LINE	WHITE 2' DASH 6' SKIP	WHITE 10' DASH 30' SKIP	FOOT	FOOT	EACH			
SB IL 171	39+05.06	44+23.80								439	42	110	977	34	
RAMP E	212+63.41	218+05.70	540	540											
I-55	310+04	318+12.75	911		150	150									4
TOTAL			1451	540	150	150	439	42	110	977	34	4			

**EARTHWORK SCHEDULE**

LOCATION	20200100	20201200	20201200	20201200	20201200	
EARTH EXCAVATION		EXCAVATION VOLUME TO BE USED IN EMBANKMENT, ADJUSTED FOR 15% SHRINKAGE	EMBANKMENT VOLUME	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) VOLUME	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	
		(CU YD)	(CU YD)	(CU YD)	(CU YD)	
SN 016-1510	767	652	2302	-1,650		
RAMP E/SN 016-1512	551	468	22,915	-22,447	654	
TOTAL		1,318	1,120	25,217	-24,097	654

Pay Item 20400800 - Furnished Excavation = 24,097 CU YD

**GUARDRAIL SCHEDULE**

LOCATION		63000001	63100070	63100085	63200310
		STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	TRAFFIC BARRIER TERMINAL, TYPE 5	TRAFFIC BARRIER TERMINAL, TYPE 6	GUARDRAIL REMOVAL
STRUCTURE NUMBER	QUADRANT	FOOT	EACH	EACH	FOOT
SN 016-1510	SW	0	0	1	24
	NE	87.5	0	1	127
	NW	87.5	0	1	118
SN 016-1512	NW	75	0	1	245
	NE	0	0	0	245
	SE	75	1	0	258
	SW	112.5	0	1	258
TOTAL		437.5	1	5	1274