



NOTES:

1. INSTALL CONDUIT NEAR LANE 1.
2. THE 1/4" INNERDUCT IS TO BE INSTALLED INSIDE THE 4" PVC @ THE SAME TIME AS THE 50 PAIR #19 CABLE.
3. MAINLINE AND LATERAL SPLICE OF 48 SM FIBER.
4. INSTALL J BOX USING ONE FROM STATE STOCK.
5. NO MAINLINE SPLICE OF 50 PAIR #19 OR 48 SM FIBERS.
6. MAINLINE SPLICE OF 50 PAIR #19.
7. REMOVE TEMPORARY POLES AND CABLES AFTER NEW CABLES HAVE BEEN INSTALLED AND TESTED TO THE SATISFACTION OF THE ENGINEER.
8. INSTALLATION OF BARRIER WALL SHALL BE INCLUDED IN THE INSTALLATION OF THE BRIDGE.
9. 2C #2 WITH #6 GROUND SHALL BE ACCORDING TO ARTICLE B16.
10. FIBER OPTIC TESTING SHALL BE DONE FROM WILLOW SPRINGS RD. TO DAN RAYN.
11. TO MINIMIZE OUTAGES, WORK THAT WILL AFFECT DATA TRANSFER SHALL BE DONE ON WEEK DAYS BETWEEN 10:00 PM AND 5:00 AM, AND WEEKENDS.

FILE NAME *	DESIGNED - J.G.	REVISED - REVISION 2, J.G., 6-10-14	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PERMANENT TSC PLAN		F.A.P. RITE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
USER NAME * mearag	CHECKED - J.G.	REVISED -		373	10707-608 & 611WB-B	COOK	177	46		
DATE * 7/23/2014	DATE - 6/16/2014	REVISED -		SHEET OF SHEETS STA. TO STA.		CONTRACT NO. 60777				
ILLINOIS TSC PLAN PROJECT										