

URBAN

URBAN

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		100% STATE 0005					
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	356	356					
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	103	103					
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	5	5					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	101	101					
25200110	SODDING, SALT TOLERANT	SO YD	101	101					
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SO YD	2	2					
40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUND	22799	22799					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	51	51					
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1394	1394					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL-BUTT JOINT	SO YD	1013	1013					
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	1	1					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2843	2843					
42001300	PROTECTIVE COAT	SO YD	369	369					
* SPECIALTY ITEMS									

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		100% STATE 0005					
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	4	4					
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SO YD	4	4					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	1160	1160					
42400800	DETECTABLE WARNINGS	SO FT	132	132					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	33774	33774					
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	10	10					
44000300	CURB REMOVAL	FOOT	457	457					
44000600	SIDEWALK REMOVAL	SO FT	960	960					
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SO YD	407	407					
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SO YD	50	50					
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SO YD	100	100					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	82	82					
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	4	4					
60608300	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.12	FOOT	457	457					
* SPECIALTY ITEMS									

FILE NAME: c:\pwwork\p\dot\pancepl\0402371\014314-sht-plan.dgn	USER NAME: PancePL	DESIGNED - PLP	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>IL 68(DUNDEE ROAD) ( IL 72(MAIN STREET) TO PRAIRIE LAKE ROAD) SUMMARY OF QUANTITIES</b>	F.A.P. RTE. 343	SECTION 631RS-4	COUNTY KANE	TOTAL SHEETS 24	SHEET NO. 3	<i>Rev.</i> CONTRACT NO. 60Y61 ILLINOIS FED. AID PROJECT
PLOT SCALE: 1/8" = 1'-0"	CHECKED -	REVISOR -	SCALE:			SHEET OF	SHEETS STA. TO STA.				
PLOT DATE: 7/11/2014	DATE -	REVISED -									
Default											