



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

September 3, 2014

SUBJECT: Ohio Street
Project BRM-9003(165)
Section 08-00278-00-BR (Aurora)
Kane County
Contract No. 63859
Item 78
September 19, 2014 Letting
Addendum (A)

NOTICE TO PROSPECTIVE BIDDERS:

Due to clarify information necessary to revise the following:

1. **Pages 3 thru 13 of the Schedule of Prices.**
2. **Page 3 of the Local Agency Special Provisions Index.**
3. **Added pages 167a & 167b to the Local Agency Special Provisions.**
4. **Revised Plan Sheets 2, 3, 5A, 46, 47, 48 and 49.**
5. **Added Plan Sheets 49A & 49B.**

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

John Baranzelli, P.E.
Acting Engineer of Design and Environment

A handwritten signature in black ink, reading "Ted B. Walschleger P.E." with a stylized flourish at the end.

By: Ted B. Walschleger, P.E.
Engineer of Project Management

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 63859

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
X6026632	VALVE BOX REMOVED	EACH	2.000	X	=	=	=
X6330705	RUB RAIL	FOOT	119.000	X	=	=	=
X7010216	TRAF CONT & PROT SPL	L SUM	1.000	X	=	=	=
Z0013797	STAB CONSTR ENTRANCE	SQ YD	1,600.000	X	=	=	=
Z0013798	CONSTRUCTION LAYOUT	L SUM	1.000	X	=	=	=
Z0018500	DRAINAGE STR CLEANED	EACH	1.000	X	=	=	=
Z0022800	FENCE REMOVAL	FOOT	308.000	X	=	=	=
Z0026407	TEMP SHT PILING	SQ FT	2,055.000	X	=	=	=
Z0034210	MECH ST EARTH RET WL	SQ FT	8,890.000	X	=	=	=
Z0046304	P UNDR FOR STRUCT 4	FOOT	937.000	X	=	=	=
Z0048665	RR PROT LIABILITY INS	L SUM	1.000	X	=	=	=
Z0050600	REM RESET ORN FENCE	FOOT	682.000	X	=	=	=
Z0056668	SS 2 WAT MN 12	FOOT	275.000	X	=	=	=
Z0056669	SS 2 WAT MN 15	FOOT	32.000	X	=	=	=
Z0057000	SAN SEW 10	FOOT	10.000	X	=	=	=

Revised 9/3/14

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 63859

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
Z0057300	SAN SEW 18	FOOT	351.000 X	=	=	=	=
Z0065704	BIT CT AG SLOPEWALL 6	SQ YD	730.000 X	=	=	=	=
Z0076600	TRAINEES	HOUR	1,000.000 X	0.80	=	800.00	=
Z0076604	TRAINEES TPG	HOUR	1,000.000 X	15.00	=	15,000.00	=
20100110	TREE REMOV 6-15	UNIT	653.000 X	=	=	=	=
20100210	TREE REMOV OVER 15	UNIT	123.000 X	=	=	=	=
20101000	TEMPORARY FENCE	FOOT	675.000 X	=	=	=	=
20101200	TREE ROOT PRUNING	EACH	75.000 X	=	=	=	=
20101300	TREE PRUN 1-10	EACH	50.000 X	=	=	=	=
20101350	TREE PRUN OVER 10	EACH	25.000 X	=	=	=	=
20200100	EARTH EXCAVATION	CU YD	2,791.000 X	=	=	=	=
20201200	REM & DISP UNS MATL	CU YD	452.000 X	=	=	=	=
20400800	FURNISHED EXCAVATION	CU YD	5,394.000 X	=	=	=	=
20800150	TRENCH BACKFILL	CU YD	1,945.000 X	=	=	=	=
21101615	TOPSOIL F & P 4	SQ YD	5,508.000 X	=	=	=	=

Revised 9/3/14

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 63859

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
21301072	EXPLOR TRENCH 72	FOOT	100.000 X	=	=	=	=
25000400	NITROGEN FERT NUTR	POUND	75.000 X	=	=	=	=
25000600	POTASSIUM FERT NUTR	POUND	75.000 X	=	=	=	=
25000750	MOWING	ACRE	17.500 X	=	=	=	=
25100630	EROSION CONTR BLANKET	SQ YD	4,845.000 X	=	=	=	=
25100635	HD EROS CONTR BLANKET	SQ YD	2,050.000 X	=	=	=	=
25200110	SODDING SALT TOLERANT	SQ YD	6,358.000 X	=	=	=	=
25200200	SUPPLE WATERING	UNIT	314.000 X	=	=	=	=
28000250	TEMP EROS CONTR SEED	POUND	750.000 X	=	=	=	=
28000305	TEMP DITCH CHECKS	FOOT	24.000 X	=	=	=	=
28000400	PERIMETER EROS BAR	FOOT	3,210.000 X	=	=	=	=
28000500	INLET & PIPE PROTECT	EACH	6.000 X	=	=	=	=
28000510	INLET FILTERS	EACH	29.000 X	=	=	=	=
28100111	STONE RIPRAP CL A6	SQ YD	232.000 X	=	=	=	=
28200200	FILTER FABRIC	SQ YD	257.000 X	=	=	=	=

Revised 9/3/14

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
30300001	AGG SUBGRADE IMPROVE	CU YD	50.000 X				
30300112	AGG SUBGRADE IMPR 12	SQ YD	6,223.000 X				
35101600	AGG BASE CSE B 4	SQ YD	1,390.000 X				
35101800	AGG BASE CSE B 6	SQ YD	970.000 X				
40600982	HMA SURF REM BUTT JT	SQ YD	209.000 X				
40603080	HMA BC IL-19.0 N50	TON	2,765.000 X				
40603335	HMA SC "D" N50	TON	623.000 X				
42001165	BR APPR PAVT	SQ YD	200.000 X				
42001300	PROTECTIVE COAT	SQ YD	1,122.000 X				
42300200	PCC DRIVEWAY PAVT 6	SQ YD	562.000 X				
42300400	PCC DRIVEWAY PAVT 8	SQ YD	128.000 X				
42400200	PC CONC SIDEWALK 5	SQ FT	2,924.000 X				
42400300	PC CONC SIDEWALK 6	SQ FT	3,358.000 X				
42400800	DETECTABLE WARNINGS	SQ FT	180.000 X				
44000100	PAVEMENT REM	SQ YD	5,269.000 X				

Revised 9/3/14

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
44000200	DRIVE PAVEMENT REM	SQ YD	700.000	X	=	=	=
44000500	COMB CURB GUTTER REM	FOOT	1,501.000	X	=	=	=
44000600	SIDEWALK REM	SQ FT	10,048.000	X	=	=	=
48101500	AGGREGATE SHLDS B 6	SQ YD	79.000	X	=	=	=
48203021	HMA SHOULDERS 6	SQ YD	60.000	X	=	=	=
50100100	REM EXIST STRUCT	EACH	1.000	X	=	=	=
50105220	PIPE CULVERT REMOV	FOOT	62.000	X	=	=	=
50200100	STRUCTURE EXCAVATION	CU YD	2,937.000	X	=	=	=
50300225	CONC STRUCT	CU YD	429.000	X	=	=	=
50300255	CONC SUP-STR	CU YD	1,054.000	X	=	=	=
50300260	BR DECK GROOVING	SQ YD	1,348.000	X	=	=	=
50300285	FORM LINER TEX SURF	SQ FT	6,476.000	X	=	=	=
50300300	PROTECTIVE COAT	SQ YD	2,944.000	X	=	=	=
50500105	F & E STRUCT STEEL	L SUM	1.000	X	=	=	=
50500505	STUD SHEAR CONNECTORS	EACH	11,340.000	X	=	=	=

Revised 9/3/14

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF PRICES
CONTRACT NUMBER - 63859

ECMS002 DTGECM03 ECMR003 PAGE 8
RUN DATE - 09/02/14
RUN TIME - 184401

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
50800205	REINF BARS, EPOXY CTD	POUND	272,800.000 X				
50800515	BAR SPLICERS	EACH	80.000 X				
50901720	BICYCLE RAILING	FOOT	430.000 X				
50901730	BRIDGE FENCE RAILING	FOOT	689.000 X				
50901750	PARAPET RAILING	FOOT	738.000 X				
51201800	FUR STL PILE HP14X73	FOOT	3,028.000 X				
51202305	DRIVING PILES	FOOT	3,028.000 X				
51203800	TEST PILE ST HP14X73	EACH	4.000 X				
51500100	NAME PLATES	EACH	1.000 X				
52100010	ELAST BEARING ASSY T1	EACH	10.000 X				
52100020	ELAST BEARING ASSY T2	EACH	10.000 X				
52100505	ANCHOR BOLTS 5/8	EACH	20.000 X				
52100510	ANCHOR BOLTS 3/4	EACH	40.000 X				
52100520	ANCHOR BOLTS 1	EACH	20.000 X				
54215472	CIP RC END SEC 72	EACH	1.000 X				

Revised 9/3/14

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 63859

ECMS002 DTGECM03 ECMR003 PAGE 9
 RUN DATE - 09/02/14
 RUN TIME - 184401

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
54260311	TRAVERS PIPE GRATE	FOOT	84.000 X	=	=	=	=
54261278	CONC ES 542001 78 1:2	EACH	1.000 X	=	=	=	=
550A0340	STORM SEW CL A 2 12	FOOT	283.000 X	=	=	=	=
550A0360	STORM SEW CL A 2 15	FOOT	53.000 X	=	=	=	=
550A0380	STORM SEW CL A 2 18	FOOT	106.000 X	=	=	=	=
550A0410	STORM SEW CL A 2 24	FOOT	405.000 X	=	=	=	=
550A0500	STORM SEW CL A 2 60	FOOT	48.000 X	=	=	=	=
550A0520	STORM SEW CL A 2 72	FOOT	259.000 X	=	=	=	=
550A0530	STORM SEW CL A 2 78	FOOT	313.000 X	=	=	=	=
55100300	STORM SEWER REM 8	FOOT	16.000 X	=	=	=	=
55100500	STORM SEWER REM 12	FOOT	235.000 X	=	=	=	=
55100900	STORM SEWER REM 18	FOOT	90.000 X	=	=	=	=
55101200	STORM SEWER REM 24	FOOT	348.000 X	=	=	=	=
55101800	STORM SEWER REM 42	FOOT	33.000 X	=	=	=	=
56103300	D I WATER MAIN 12	FOOT	166.000 X	=	=	=	=

Revised 9/3/14

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
56103350	D I WATER MAIN 14	FOOT	240.000 X				
56103400	D I WATER MAIN 16	FOOT	430.000 X				
56400300	FIRE HYDNTS TO BE ADJ	EACH	3.000 X				
56400600	FIRE HYDRANTS	EACH	1.000 X				
59100100	GEOCOMPOSITE WALL DR	SQ YD	81.000 X				
60104500	PIPE DRAINS CS 48	FOOT	5.000 X				
60200805	CB TA 4 DIA T8G	EACH	5.000 X				
60201110	CB TA 4 DIA T11V F&G	EACH	15.000 X				
60218400	MAN TA 4 DIA T1F CL	EACH	4.000 X				
60221100	MAN TA 5 DIA T1F CL	EACH	4.000 X				
60223800	MAN TA 6 DIA T1F CL	EACH	1.000 X				
60224459	MAN TA 8 DIA T1F CL	EACH	1.000 X				
60224469	MAN TA 9 DIA T1F CL	EACH	3.000 X				
60224470	MAN TA 9 DIA T1F OL	EACH	3.000 X				
60236825	INLETS TA T11V F&G	EACH	11.000 X				

Revised 9/3/14

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
60248900	VV TA 5 DIA T1F CL	EACH	5.000 X	=	=	=	=
60266600	VALVE BOX ADJ	EACH	8.000 X	=	=	=	=
60500040	REMOV MANHOLES	EACH	3.000 X	=	=	=	=
60500050	REMOV CATCH BAS	EACH	4.000 X	=	=	=	=
60500060	REMOV INLETS	EACH	7.000 X	=	=	=	=
60603800	COMB CC&G TB6.12	FOOT	2,577.000 X	=	=	=	=
63000005	SPBGR TY B	FOOT	112.500 X	=	=	=	=
63100045	TRAF BAR TERM T2	EACH	1.000 X	=	=	=	=
63100070	TRAF BAR TERM T5	EACH	1.000 X	=	=	=	=
63100085	TRAF BAR TERM T6	EACH	1.000 X	=	=	=	=
63100167	TR BAR TRM T1 SPL TAN	EACH	3.000 X	=	=	=	=
63200310	GUARDRAIL REMOV	FOOT	803.000 X	=	=	=	=
66400305	CH LK FENCE 6	FOOT	207.000 X	=	=	=	=
66900200	NON SPL WASTE DISPOSL	CU YD	536.000 X	=	=	=	=
67000400	ENGR FIELD OFFICE A	CAL MO	12.000 X	=	=	=	=

Revised 9/3/14

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
67100100	MOBILIZATION	L SUM	1.000 X	=	=	=	=
70106800	CHANGEABLE MESSAGE SN	CAL MO	8.000 X	=	=	=	=
70300100	SHORT TERM PAVT MKING	FOOT	634.000 X	=	=	=	=
72000100	SIGN PANEL T1	SQ FT	113.000 X	=	=	=	=
72400310	REMOV SIGN PANEL T1	SQ FT	116.000 X	=	=	=	=
72900200	METAL POST TY B	FOOT	122.000 X	=	=	=	=
78000200	THPL PVT MK LINE 4	FOOT	4,095.000 X	=	=	=	=
78000400	THPL PVT MK LINE 6	FOOT	1,221.000 X	=	=	=	=
78000600	THPL PVT MK LINE 12	FOOT	125.000 X	=	=	=	=
78000650	THPL PVT MK LINE 24	FOOT	95.000 X	=	=	=	=
78006110	PREF THPL PM LINE 4	FOOT	808.000 X	=	=	=	=
78200410	GUARDRAIL MKR TYPE A	EACH	12.000 X	=	=	=	=
78201000	TERMINAL MARKER - DA	EACH	3.000 X	=	=	=	=
81028240	UNDRGRD C GALVS 4	FOOT	280.000 X	=	=	=	=
81101000	CON AT ST 4 GALVS	FOOT	730.000 X	=	=	=	=

Revised 9/3/14

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
81400200	HD HANDHOLE	EACH	2.000 X				
				TOTAL \$			

- NOTE:
1. EACH PAY ITEM SHOULD HAVE A UNIT PRICE AND A TOTAL PRICE.
 2. THE UNIT PRICE SHALL GOVERN IF NO TOTAL PRICE IS SHOWN OR IF THERE IS A DISCREPANCY BETWEEN THE PRODUCT OF THE UNIT PRICE MULTIPLIED BY THE QUANTITY.
 3. IF A UNIT PRICE IS OMITTED, THE TOTAL PRICE WILL BE DIVIDED BY THE QUANTITY IN ORDER TO ESTABLISH A UNIT PRICE.
 4. A BID MAY BE DECLARED UNACCEPTABLE IF NEITHER A UNIT PRICE NOR A TOTAL PRICE IS SHOWN.

Revised 9/3/14

CONDUIT ATTACHED TO STRUCTURE, 4" DIA., GALVANIZED STEEL..... 62

IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING (TPG)..... 62

GUIDELINES FOR PREPARATION OF DEMOLITION PLANS FOR STRUCTURES OVER BURLINGTON
NORTHERN SANTA FE RAILROAD..... 65

STORMWATER POLLUTION PREVENTION PLAN, NOI, ION AND NOT FORMS..... 72

SOILS REPORT..... 93

IEPA – WATER MAIN..... 166

KANE COUNTY STORMWATER MANAGEMENT..... 167

STABALIZED CONSTRUCTION ENTRANCE..... 167a

STABILIZED CONSTRUCTION ENTRANCE

Description: The stabilized construction entrance is a temporary stone-stabilized pad with a non-woven geotextile fabric underlining located at defined points of vehicular ingress and egress on construction sites to reduce the amount of mud, dirt, and rocks transported onto public roads by motor vehicles, equipment, and runoff. The edges of the entrance shall be tapered out towards the road to prevent tracking of mud at the edge of the entrance and so that long vehicles do not leave the stabilized area when turning onto or off of the paved roadway.

Materials: A stabilized construction entrance is composed of the following

Non-woven geotextile fabric and
CA-1, CA-2, CA-3, or CA-4

Use a non-woven geotextile fabric that meets the requirements of Section 804.11 of the *Standard Specifications for Highway Construction* "Geotextile Fabric for Slope Protection."

Construction Requirements: A stabilized construction entrance shall be installed at all points where traffic will be leaving the construction site and moving directly onto a public road. Use construction entrances in conjunction with the stabilization of construction roads to reduce the amount of mud picked up by vehicles.

The stabilized construction entrance shall be a minimum of 14 feet wide by 100 feet long, and may be modified as necessary to accommodate site constraints. Taper the edges of the entrance out towards the road to prevent tracking of mud at the edge of the entrance.

If washing is used, make provisions to intercept the wash water and trap the sediment before it is carried offsite. Require washdown facilities as needed. In general, establish washdown facilities with crushed gravel and drain into a sediment trap or sediment basin.

Remove all vegetation and any objectionable material from the foundation area. Divert all surface runoff and drainage from the stones to a sediment trap or basin. Install a non-woven geotextile fabric prior to placing any stone. If necessary, install a culvert pipe across the entrance to provide positive drainage. Place #1 aggregate at a minimum depth of 6-inches uniform on top of the geotextile fabric.

Maintenance: Each stabilized construction entrance shall be inspected every seven (7) days. Check for mud and sediment buildup and pad integrity. Wash, replace, or add stone whenever the entrance fails to perform effectively or as directed by the inspector. The stone in the entrance should be washed or replaced whenever the entrance fails to reduce mud being carried offsite by vehicles. Frequent washing will extend the useful life of the stone.

Reshape stone pad as needed for drainage and runoff control. Brush or sweep up soil that has been tracked offsite immediately for proper disposal. Flushing should only be used when the water can be discharged to a sediment trap or basin. Maintain the stabilized construction entrance until the remainder of the construction site has been fully stabilized. Repair any broken pavement immediately.

For sites with wash racks at each site entrance, sediment traps will have to be constructed and maintained for the life of the project.

If the aggregate material is being tracked offsite, limit larger vehicles from the construction site or use a larger diameter stone. If excessive sediment is being tracked onto the roadway, increase the length of the stabilized construction entrance.

Added 9/3/14

167a

Method of Measurement: The installation of STABILIZED CONSTRUCTION ENTRANCE shall be measured per square yard. Replacement material shall not be measured separately but considered included in the cost of the unit price.

Basis of Payment: STABILIZED CONSTRUCTION ENTRANCE shall be paid for per square yard. The installation must be accepted and certified by the Resident Engineer prior to payment. The price shall include full compensation for all labor, materials, tools, equipment, and incidentals, necessary for constructing and maintaining a STABILIZED CONSTRUCTION ENTRANCE as herein described in a workmanlike and acceptable manner. Replacement material shall be considered included in the cost of the item.

Added 9/3/14

1676