

EROSION CONTROL NOTES

41. ALL SEDIMENT AND EROSION CONTROL MEASURES WILL BE INSTALLED PER IDOT STANDARD 208881 OR AS SPECIFIED HEREIN AND PAID FOR IN ACCORDANCE WITH SECTION 280 OF THE STANDARD SPECIFICATIONS.
42. EROSION CONTROL SHALL BE PROVIDED IN ACCORDANCE WITH THE SEQUENCE OF STAGE CONSTRUCTION. THE CONTRACTOR SHALL SUBMIT A DETAILED SCHEDULE FOR APPROVAL.
43. SEDIMENT AND EROSION CONTROL DEVICES SHALL BE FUNCTIONAL BEFORE THE PROJECT SITE IS OTHERWISE DISTURBED.
44. STABILIZATION OF DISTURBED AREAS MUST BE INITIATED WITHIN 1 WORKING DAY OF PERMANENT OR TEMPORARY CESSATION OF EARTH DISTURBING ACTIVITIES AND SHALL BE COMPLETED AS SOON AS POSSIBLE BUT NOT LATER THAN 14 DAYS FROM THE INITIATION OF THE STABILIZATION WORK IN AN AREA.
45. WATER PUMPED OR OTHERWISE DISCHARGE FROM THE SITE DURING CONSTRUCTION DEWATERING SHALL BE FILTERED WITH FILTER BAGS, OR OTHER METHOD APPROVED BY THE ENGINEER.
46. GRAVEL ROADS, ACCESS DRIVES, PARKING AREA OF SUFFICIENT WIDTH AND LENGTH, AND VEHICLE WASH DOWN FACILITIES IF NECESSARY, SHALL BE PROVIDED TO PREVENT THE DEPOSIT OF SOIL FROM BEING TRACKED ONTO PUBLIC OR PRIVATE ROADWAYS. ANY SOIL REACHING A PUBLIC OR PRIVATE ROADWAY SHALL BE REMOVED BEFORE THE END OF EACH WORKDAY OR AS NEEDED.
47. ALL EROSION CONTROL MEASURES SHALL BE INSPECTED BY THE CONTRACTOR WEEKLY AND WITHIN 24 HOURS OF ANY STORM EXCEEDING 1/2 INCH PRECIPITATION. DAMAGED AND INEFFECTIVE EROSION CONTROL MEASURES SHALL BE REPAIRED OR REPLACED BY THE CONTRACTOR WITHIN 72 HOURS OF NOTIFICATION BY THE ENGINEER OR THE CITY OF AURORA.
48. THE CONTROL MEASURES SHALL BE KEPT OPERATIONAL AND MAINTAINED CONTINUOUSLY THROUGHOUT THE PERIOD OF LAND DISTURBANCE UNTIL PERMANENT SEDIMENT AND EROSION CONTROL MEASURES ARE OPERATIONAL.
49. THE CONDITION OF THE CONSTRUCTION SITE FOR WINTER SHUTDOWN SHALL BE ADDRESSED EARLY IN THE FALL GROWING SEASON SO THAT SLOPES AND OTHER BARE EARTH AREAS MAY BE STABILIZED WITH TEMPORARY AND / OR PERMANENT VEGETATIVE COVER FOR PROPER EROSION AND SEDIMENT CONTROL. ALL OPEN AREAS THAT ARE TO REMAIN IDLE THROUGHOUT THE WINTER SHALL RECEIVE TEMPORARY EROSION CONTROL MEASURES INCLUDING TEMPORARY SEEDING, MULCHING AND / OR EROSION CONTROL BLANKET PRIOR TO THE END OF THE FALL GROWING SEASON. THE AREA TO BE WORKED BEYOND THE END OF THE GROWING SEASON MUST INCORPORATE SOIL STABILIZATION MEASURES THAT DO NOT RELY ON VEGETATIVE COVER SUCH AS EROSION CONTROL BLANKET AND HEAVY MULCHING.
50. STOCKPILES OF SOIL AND OTHER BUILDING MATERIALS TO REMAIN IN PLACE MORE THAN THREE (3) DAYS SHALL BE FURNISHED WITH EROSION AND SEDIMENT CONTROL MEASURES (I.E. PERIMETER SILT FENCE). STOCKPILES, NOT BEING ACTIVELY WORKED AND TO REMAIN IN PLACE FOR 14 DAYS OR MORE SHALL RECEIVE TEMPORARY SEEDING. STOCKPILES SHOULD NOT BE LOCATED IN AREAS THAT HAVE HIGH POTENTIAL FOR CONTRIBUTING SEDIMENTS TO WETLANDS OR STORMWATER FACILITIES.
51. CONCRETE WASHOUT SHOULD BE CONTAINED AT ALL TIMES. WASHOUT MATERIAL SHOULD NOT BE ALLOWED TO ENTER STORM SEWERS OR LEACH INTO THE SOIL UNDER ANY CIRCUMSTANCES. ANY WASTE SHOULD BE DISPOSED OF PROPERLY AND THE LOCATION OF THE WASHOUT SHOULD BE DESIGNATED WITH PROPER SIGNAGE.
52. CRITICAL AREAS SUCH AS AREAS NEAR THE CREEK SHOULD BE STABILIZED IMMEDIATELY UPON FINAL GRADING.
53. UNLESS OTHERWISE INDICATED, ALL VEGETATIVE AND STRUCTURAL EROSION AND SEDIMENT CONTROL PRACTICES WILL BE CONSTRUCTED ACCORDING TO MINIMUM STANDARDS AND SPECIFICATIONS IN THE ILLINOIS URBAN MANUAL LATEST EDITION.
54. THE KANE-DUPAGE SOIL AND WATER CONSERVATION DISTRICT (KDSWCD) MUST BE NOTIFIED ONE WEEK PRIOR TO THE PRE-CONSTRUCTION CONFERENCE, ONE WEEK PRIOR TO THE COMMENCEMENT OF LAND DISTURBING ACTIVITIES, AND ONE WEEK PRIOR TO THE FINAL INSPECTION.
55. A COPY OF THE APPROVED EROSION AND SEDIMENT CONTROL PLAN SHALL BE MAINTAINED ON THE SITE AT ALL TIMES.
56. PRIOR TO COMMENCING LAND-DISTURBING ACTIVITIES IN AREAS OTHER THAN INDICATED ON THESE PLANS (INCLUDING BUT NOT LIMITED TO, ADDITIONAL PHASES OF DEVELOPMENT AND OFF-SITE BORROW OR WASTE AREAS) A SUPPLEMENTARY EROSION CONTROL PLAN SHALL BE SUBMITTED FOR REVIEW BY THE KDSWCD.
57. THE CONTRACTOR IS RESPONSIBLE FOR INSTALLATION OF ANY ADDITIONAL EROSION CONTROL MEASURES NECESSARY TO PREVENT EROSION AND SEDIMENTATION AS DETERMINED BY THE KDSWCD.
58. DURING DEWATERING OPERATIONS, WATER WILL BE FILTERED OR PUMPED INTO SEDIMENT BASINS OR SILT TRAPS. DEWATERING DIRECTLY INTO STREAMS, WETLANDS, FIELD TILES, OR STORMWATER STRUCTURES IS PROHIBITED.
59. IT IS THE RESPONSIBILITY OF THE LANDOWNER AND/OR GENERAL CONTRACTOR TO INFORM ANY SUB-CONTRACTOR(S) WHO MAY PERFORM WORK ON THIS PROJECT, OF THE REQUIREMENTS IN IMPLEMENTING AND MAINTAINING THESE EROSION CONTROL PLANS AND ASSURE COMPLIANCE WITH ALL APPLICABLE LOCAL, STATE, AND FEDERAL REGULATIONS.

NOTE: BOXED ITEMS ARE INCLUDED IN THE COST OF THE CONTRACT.

| | | |
|---------------|-----------|------|
| PLAN | SURVEYED | DATE |
| NOTE BOOK NO. | PLOTTED | BY |
| | CHECKED | |
| | BY | |
| | FILE NAME | |

| | | |
|---------------|----------------|------|
| PROFILE | SURVEYED | DATE |
| NOTE BOOK NO. | PLOTTED | BY |
| | CHECKED | |
| | BY | |
| | NOTATIONS CHKD | |

CONTACTS

AURORA TOWNSHIP HIGHWAY COMMISSIONER
JOHN SHOEMAKER
630-892-0266
200 BUTTERFIELD ROAD
NORTH AURORA, IL 60542-1316

CITY OF AURORA
630-256-5636
44 E. DOWNER PLACE
AURORA, IL 60505

NICOR GAS
CONSTANCE LANE
630-388-3830
1844 FERRY ROAD
NAPERVILLE, IL 60563

EAST AURORA SCHOOL DISTRICT 131
630-299-5550
417 FIFTH STREET
AURORA, IL 60505

AT&T OSP ENGINEER
LEGAL MANDATE GROUP
BOB ELSINGA
630-573-5452
1000 COMMERCE DRIVE
OAK BROOK, IL 60523

SIMMONS MIDDLE SCHOOL
630-299-4150
1130 SHEFFER RD.
AURORA, IL 60505

COMED
ANA KUNZE
630-437-2129
2 LINCOLN CENTER-6TH FL
OAK BROOK TERRACE, IL 60181

HERMES ELEMENTARY SCHOOL
630-299-8200
1000 JUNGLES AVE.
AURORA, IL 60505

FOX METRO WATER RECLAMATION DISTRICT
ZACHERY BONESZ
630-301-6805
682 STATE ROUTE 31
OSWEGO, IL 60543

ROLLINS ELEMENTARY SCHOOL
630-299-5480
950 KANE STREET
AURORA, IL 60505

COMCAST CABLE
MARTHA GIERAS
630-600-6352
688 INDUSTRIAL DRIVE
ELMHURST, IL 60126

OAK PARK ELEMENTARY SCHOOL
630-299-8250
1200 FRONT STREET
AURORA, IL 60505

AURORA POLICE DEPARTMENT
MAIN HEADQUARTERS
630-256-5000
1200 EAST INDIAN TRAIL ROAD
AURORA, IL 60505

COWHERD MIDDLE SCHOOL
630-299-5900
411 N. FARNSWORTH
AURORA, IL 60505

PACE SUBURBAN BUS SERVICE
(Specify Relevant Department)
847-364-7223
550 W. Algonquin Rd.
Arlington Heights, IL 60005

AURORA FIRE DEPARTMENT
CENTRAL STATION
630-256-4000
75 N. BROADWAY
AURORA, IL 60505

| STABILIZATION TYPE | JAN. | FEB. | MAR. | APR. | MAY. | JUNE | JULY | AUG. | SEPT. | OCT. | NOV. | DEC. |
|--------------------|------|------|------|------|------|------|------|------|-------|------|------|------|
| PERMANENT SEEDING | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A |
| DORMANT SEEDING | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A |
| TEMPORARY SEEDING | A | | | | | | | | | | | |
| SODDING | | | | | | | | | | | | |
| MULCHING | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A |

A. TEMPORARY SEEDING (SEE IDOT STD. SPEC. ART. 280.04 f.)

| | | | |
|---|-------------|------------|-----------|
| FILE NAME = | USER NAME = | DESIGNED - | REVISED - |
| G:\CH11\0130\Road\Sheets\10130-SHT-GenNotes.dgn | ajpondexter | MLB | 8-22-14 |
| PLOT SCALE = | CHECKED - | REVISIONS | |
| N/A | MWS | | |
| PLOT DATE = | DATE - | | |
| 8/22/2014 | 8/22/14 | | |

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**GENERAL NOTES, INDEX OF SHEETS
AND LIST OF STANDARDS**

SCALE: N.T.S. SHEET NO. 3 OF 136 SHEETS STA. TO STA.

| | | | | |
|---------------------------|----------------|--------|--------------------|-----------|
| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 4087 | 08-00278-00-BR | KANE | 136 | 3 |
| ILLINOIS FED. AID PROJECT | | | CONTRACT NO. 63859 | |