

(1) (2)

CONSTRUCTION CODE	
100% STATE	
PPS NO.	PPS NO.
6-00173-0200	6-00173-0300
	6-00173-0400
	6-00173-0500

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				ROADWAY	ROADWAY
				0005 RURAL	0005 RURAL
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	66	0	66
20400800	FURNISHED EXCAVATION	CU YD	19	2	17
21400100	GRADING AND SHAPING DITCHES	FOOT	1,950	350	1,600
25000200	SEEDING, CLASS 2	ACRE	0.54	0.06	0.48
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	48	5	43
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	48	5	43
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	48	5	43
25000700	AGRICULTURAL GROUND LIMESTONE	TON	1.08	0.12	0.96
25100115	MULCH, METHOD 2	ACRE	0.54	0.06	0.48
28000500	INLET AND PIPE PROTECTION	EACH	5	1	4
28001000	AGGREGATE (EROSION CONTROL)	TON	140	35	105
28100207	STONE RIPRAP, CLASS A4	TON	139	0	139
28100807	STONE DUMPED RIPRAP, CLASS A4	TON	13	10	3
28200200	FILTER FABRIC	SO YD	174	0	174

(1) (2)

CONSTRUCTION CODE	
100% STATE	
PPS NO.	PPS NO.
6-00173-0200	6-00173-0300
	6-00173-0400
	6-00173-0500

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				ROADWAY	ROADWAY
				0005 RURAL	0005 RURAL
31101900	SUBBASE GRANULAR MATERIAL, TYPE C	TON	20	0	20
40600285	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	POUND	453,038	90,438	362,600
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	3,738	1,062	2,676
40600990	TEMPORARY RAMP	SO YD	1,146	312	834
40603243	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, FG, N90	TON	63,053	12,296	50,757
40603570	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N90	TON	39,663	8,197	31,466
44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SO YD	19,798	0	19,798
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	236,942	54,595	182,347
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	41,743	0	41,743
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	34,475	0	34,475
44000162	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4"	SO YD	370,891	96,911	273,980
44000168	HOT-MIX ASPHALT SURFACE REMOVAL, 4 3/4"	SO YD	63,076	0	63,076
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	127	0	127
44004000	PAVED DITCH REMOVAL	FOOT	10	0	10