

SUMMARY OF QUANTITIES				CONSTRUCTION CODE		
				100% STATE	100% STATE	100% STATE
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	ROADWAY	ROADWAY
				0005	0021	0004
				6-00706-0000	6-00706-0000	6-00743-0000
20100110	TREE REMOVAL ( 6 TO 15 UNITS DIAMETER)	UNIT	230	230		
20200100	EARTH EXCAVATION	CU YD	499			499
20400800	FURNISHED EXCAVATION	CU YD	321			321
25000200	SEEDING, CLASS 2	ACRE	0.8			0.8
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	68			68
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	68			68
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	68			68
25000700	AGRICULTURAL GROUND LIMESTONE	TON	1.5			1.5
25100125	MULCH, METHOD 3	ACRE	0.8			0.8
28000315	AGGREGATE DITCH CHECKS	TON	56			56
31100700	SUBBASE GRANULAR MATERIAL, TYPE A 8"	SO YD	1984			1984
31101000	SUBBASE GRANULAR MATERIAL, TYPE B	TON	189	189		
35300400	PORTLAND CEMENT CONCRETE BASE COURSE 9"	SO YD	1699			1699
40600275	BITUMINOUS MATERIALS ( PRIME COAT)	POUND	58631	58631		

14