

SUMMARY OF QUANTITIES				CONSTRUCTION CODE		
				100% STATE	100% STATE	100% STATE
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	ROADWAY	ROADWAY
				0005	0021	0004
				6-00706-0000	6-00706-0000	6-00743-0000
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	8596	8596		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6		
67100100	MOBILIZATION	L SUM	1	1		
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1		
70100320	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	L SUM	1	1		
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	10		
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	18	18		
70200100	NIGHT TIME WORK ZONE LIGHTING	L SUM	1	1		
70300100	SHORT TERM PAVEMENT MARKING	FOOT	4036	4036		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	672	672		
* 78004220	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 5"	FOOT	5060	5060		
* 78004230	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 6"	FOOT	2381	2381		
* 78004240	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 8"	FOOT	4410	4410		
* 78004250	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 12"	FOOT	1020	1020		

\* SPECIALTY ITEMS

FILE NAME :	USER NAME : sparkgn	DESIGNED - JWC	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>			F.A.P. RATE:	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\ps_work\pvidot\sparkgn\1033062\067	SPRS-141-500.dgn	DRAWN - JWC	REVISED -					662	(1-2) RS-1,N	SANGAMON	89	6
Default	PLOT SCALE = 100.0000' / 1"	CHECKED - JWC	REVISED -		SCALE:	SHEET	OF	SHEETS	STA.	TO STA.	CONTRACT NO. 72F96 ILLINOIS FED. AID PROJECT	
	PLOT DATE = Jul-14-2014 01:55:00PM	DATE -	REVISED -									