

CURB SCHEDULE												
LOCATION STATION TO STATION	LENGTH (FT)	COMB. CURB & GUT REM (FT)	COMB. CURB & GUTTER TYP. M 4.06 (FT)	COMB. CURB & GUTTER TYP. M 4.24 (FT)	COMB. CURB & GUTTER TYP. M 6.06 (FT)	COMB. CURB & GUTTER TYP. M 6.24 (FT)	INLET ADJ. (EACH)	MEDIAN REMOVAL (SQ FT)	CONC MEDIAN SURF, 4" (SQ FT)	CONC MEDIAN TY SM (SPECIAL) (SQ FT)	SUB BASE GRAN MAT TY B (TON)	
FAP 662(IL 4)												
IL 4 (Veterans Pkwy)												
STA. 141+31.18 TO STA. 142+36.97	105.79	106.2		106.2			1.0	514.8	514.8		11.3	
STA. 141+52.68 TO STA. 142+36.97	84.29	84.3	84.3									
STA. 142+36.97 TO STA. 143+02.09	65.12						1.0	390.6		390.6		
STA. 141+54.10 TO STA. 142+24.63	70.53							407.6		407.6		
STA. 142+24.63 TO STA. 143+18.50	93.87	102.2		102.2			1.0	644.6	644.6		14.2	
STA. 142+24.63 TO STA. 143+18.50	93.87	106.8	106.8				1.0					
STA. 143+70.87 TO STA. 144+74.83	103.96	103.0		103.0			1.0	653.9	653.9		14.4	
STA. 143+79.33 TO STA. 144+74.83	95.50	108.3	108.3									
STA. 144+74.83 TO STA. 145+46.10	71.27						2.0	416.5		416.5		
STA. 143+90.57 TO STA. 144+62.16	71.59							413.7		413.7		
STA. 144+62.16 TO STA. 145+47.26	85.10	84.8	84.8				1.0	516.8	516.8		11.4	
STA. 144+62.16 TO STA. 145+76.92	114.76	114.8		114.8								
STA. 170+72.80 TO STA. 171+86.80	114.00	114.0		114.0			1.0	539.2	539.2		11.9	
STA. 170+99.64 TO STA. 171+86.80	87.16	86.5	86.5									
STA. 171+86.80 TO STA. 172+55.83	69.03						1.0	405.8		405.8		
STA. 171+01.60 TO STA. 171+74.55	72.95							409.0		409.0		
STA. 171+74.55 TO STA. 172+65.40	90.85	99.4	99.4				1.0	587.8	587.8		12.9	
STA. 171+74.55 TO STA. 172+72.46	97.91	97.8		97.8			1.0					
STA. 173+31.39 TO STA. 174+30.02	98.63	97.2		97.2				611.7	611.7		13.5	
STA. 173+38.71 TO STA. 174+30.02	91.31	100.7	100.7									
STA. 174+30.02 TO STA. 175+01.50	71.48						3.0	407.4		407.4		
STA. 173+47.72 TO STA. 174+21.06	73.34							405.6		405.6		
STA. 174+21.06 TO STA. 175+03.65	82.59	82.4	82.4				1.0	510.4	510.4		11.2	
STA. 174+21.06 TO STA. 175+31.27	110.21	110.2		110.2								
STA. 183+65.65 TO STA. 184+77.73	112.08	112.0		112.0				527.1	527.1		11.6	
STA. 183+90.94 TO STA. 184+77.73	86.79	86.4	86.4									
STA. 184+77.73 TO STA. 185+46.79	69.06						1.0	401.8		401.8		
STA. 183+93.87 TO STA. 184+66.34	72.47							423.8		423.8		
STA. 184+66.34 TO STA. 185+89.25	122.91	115.8		115.8			1.0					
STA. 184+66.34 TO STA. 185+89.25	122.91	135.9	135.9				1.0					
STA. 186+64.21 TO STA. 187+92.18	127.97	119.6		119.6			2.0	964.4	964.4		21.2	
STA. 186+64.21 TO STA. 187+92.18	127.97	143.0	143.0				1.0					
STA. 187+92.18 TO STA. 188+55.25	63.07						2.0	362.7		362.7		
STA. 187+01.04 TO STA. 187+72.51	71.47							402.8		402.8		
STA. 187+72.51 TO STA. 188+57.89	85.38	84.4	84.4				1.0	525.3	525.3		11.6	
STA. 187+72.51 TO STA. 188+83.56	111.05	111.0		111.0								
SUB-TOTAL =		2506.7	1202.9	1303.8	0.0	0.0	25.0	11443.3	6596.0	4847.3	145.3	
MUN 7070 (BRUNS LN)												
STA. 99+49.76 TO STA. 99+79.79	30.03	74.5			18.7	55.8		307.6	247.1		5.4	
STA. 99+72.03 TO STA. 100+12.83	40.80	95.6			34.6	61.0		422.4	337.7		7.4	
STA. 100+82.12 TO STA. 101+32.03	49.91	117.1			47.5	69.6		500.7	457.2		10.1	
STA. 101+17.76 TO STA. 101+47.96	30.20	70.1			20.3	49.8		274.1	212.1		4.7	
SUB-TOTAL =		357.3	0.0	0.0	121.1	236.2	0.0	1504.8	1254.1	0.0	27.6	
TR 151 (PALOMINO RD)												
STA. 20+16.79 TO STA. 20+49.23	32.44	91.8			25.0	66.8		371.6	334.1		7.4	
STA. 21+97.04 TO STA. 22+32.25	35.21	100.7			27.2	73.5		458.0	411.3		9.1	
SUB-TOTAL =		192.5	0.0	0.0	52.2	140.3	0.0	829.6	745.4	0.0	16.4	
TOTAL		3,057	1,202.9	1,303.8	173.3	376.5	25.0	13,777.7	8,595.5	4,847.3	189.3	

TREE REMOVAL			
LOCATION STATION	LOCATION (RT / LT)	NUMBER OF TREES (EACH)	TOTAL UNITS (UNITS)
IL 4 ( VETERANS PKWY)			
STA. 120+75.00	LT	1	6.0
STA. 121+56.00	RT	8	71.0
STA. 160+56.00	RT	3	20.0
STA. 162+07.00	LT	5	39.0
STA. 195+10.00	RT	2	21.0
STA. 194+98.00	LT	5	34.0
STA. 211+36.00	LT	5	39.0
TOTAL			230.0

PIPE UNDERDRAINS, 4"		
STATION TO STATION FAP 662 (IL 4)	LOCATION (RT / LT)	LENGTH (FT)
IL 4 (VETERANS PKWY)		
STA. 137+05.19 TO STA. 142+50.00	RT	544.81
STA. 144+00.00 TO STA. 150+03.37	LT	603.37
TOTAL		1148.18

OUTLET SPECIAL		
LOCATION STATION TO STATION FAP 662 (IL4)	LENGTH (FT)	OUTLET SPECIAL (EACH)
IL 4 (VETERANS PKWY)		
STA. 141+49.45 T STA. 141+53.45 SB C	4.0	1.00
STA. 145+46.80 T STA. 145+50.8 NB C	4.0	1.00
STA. 170+96.24 T STA. 171+00.2 SB C	4.0	1.00
STA. 175+03.14 T STA. 175+07.1 NB C	4.0	1.00
STA. 183+87.07 T STA. 183+91.0 SB C	4.0	1.00
STA. 188+56.76 T STA. 188+60.7 NB C	4.0	1.00
TOTAL		6.00