

SHOULDER SCHEDULE												
LOCATION STATION TO STATION FAP 662/67 (IL 4/97)	LENGTH (FT)	WIDTH (FT)	AREA (SQ YD)	PAVED SHOULDER REMOVAL (SQ YD)	HMA SURF REM (VAR DEPTH) (SQ YD)	HOT-MIX ASPHALT SHOULDERS,		HMA SHOULDERS, 8" (SQ YD)	BITUMINOUS MATERIALS (PRIME COAT) (POUND)			
						3 3/4" (TON)	VARIBLE DEPTH (TON)					
IL 4 (VETERANS PKWY)												
SOUTHBOUND												
OUTSIDE	STA. 117+00.00 TO STA. 137+05.19	2,005.19	10	2228.0			467.9		1002.60			
OUTSIDE	STA. 137+05.19 TO STA. 138+52.71	147.52	9 TO 4	106.5			22.4	106.5	47.94			
OUTSIDE	STA. 138+52.71 TO STA. 139+70.19	117.48	4	52.2			11.0	52.2	23.50			
OUTSIDE	STA. 139+70.19 TO STA. 142+35.19	265.00	4	117.8	618.4		24.7	117.8	53.00			
OUTSIDE	STA. 143+93.23 TO STA. 154+43.19	1,049.96	10	1166.6			245.0		524.98			
STA. EQ. 154+43.19 BK = 154+05.70 AH												
OUTSIDE	STA. 154+05.70 TO STA. 166+73.99	1,268.29	10	1409.2			295.9		634.15			
OUTSIDE	STA. 166+73.99 TO STA. 168+06.61	132.62	9 TO 4	95.8			20.1		43.10			
OUTSIDE	STA. 168+06.61 TO STA. 171+73.32	366.71	4	163.0			34.2		73.34			
OUTSIDE	STA. 174+19.05 TO STA. 176+00.00	180.95	10	201.1			42.2		90.48			
OUTSIDE	STA. 176+00.00 TO STA. 181+03.22	503.22	10	559.1		559.1		82.2	251.61			
OUTSIDE	STA. 181+03.22 TO STA. 186+13.06	509.84	11	623.1		623.1		91.6	280.41			
OUTSIDE	STA. 187+76.03 TO STA. 192+04.51	428.48	10	476.1		476.1		70.0	214.24			
OUTSIDE	STA. 192+04.51 TO STA. 198+70.93	666.42	10	740.5			155.5		333.21			
STA. EQ. 198+70.93 BK = 198+88.77 AH												
OUTSIDE	STA. 198+88.77 TO STA. 216+50.00	1,761.23	10	1956.9			411.0		880.62			
INSIDE	STA. 117+00.00 TO STA. 136+71.13	1,971.13	6	1314.1			276.0		591.34			
INSIDE	STA. 136+71.13 TO STA. 137+01.40	30.27	6 TO 4	16.8			3.5		7.57			
INSIDE	STA. 137+01.40 TO STA. 141+30.80	429.40	4	190.8			40.1		85.88			
INSIDE	STA. 141+30.80 TO STA. 141+49.45	18.65	4	8.3			1.7	8.3	3.73			
INSIDE	STA. 141+54.50 TO STA. 142+58.01	103.51	3 TO 7	57.5			12.1		25.88			
INSIDE	STA. 142+58.01 TO STA. 143+18.54	60.53	8	53.8			11.3		24.21			
INSIDE	STA. 143+91.41 TO STA. 144+08.21	16.80	1 TO 10	10.3			2.2		4.62			
INSIDE	STA. 144+08.21 TO STA. 145+47.26	139.05	10	154.5			32.4		69.53			
INSIDE	STA. 145+47.26 TO STA. 154+43.19	895.93	6	597.3			125.4		268.78			
STA. EQ. 154+43.19 BK = 154+05.70 AH												
INSIDE	STA. 154+05.70 TO STA. 166+14.28	1,208.58	6	805.7			169.2		362.57			
INSIDE	STA. 166+14.28 TO STA. 167+16.41	102.13	6 TO 4	56.7			11.9		25.53			
INSIDE	STA. 167+16.41 TO STA. 170+72.80	356.39	4	158.4			33.3		71.28			
INSIDE	STA. 170+72.80 TO STA. 170+96.24	23.44	4	10.4			2.2	10.4	4.69			
INSIDE	STA. 171+01.60 TO STA. 172+07.87	106.27	3 TO 9	70.8			14.9		31.88			
INSIDE	STA. 172+07.87 TO STA. 172+65.40	57.53	10	63.9			13.4		28.77			
INSIDE	STA. 173+47.72 TO STA. 173+63.60	15.88	0 TO 8	7.1			1.5		4.76			
INSIDE	STA. 173+63.60 TO STA. 175+03.65	140.05	8	124.5			26.1		84.03			
INSIDE	STA. 175+03.65 TO STA. 175+22.40	18.75	8 TO 6	14.6			3.1		9.84			
INSIDE	STA. 175+22.40 TO STA. 179+07.19	384.79	6	256.5			53.9		173.16			
INSIDE	STA. 179+07.19 TO STA. 183+65.65	458.46	4	203.8			42.8		137.54			
INSIDE	STA. 183+65.49 TO STA. 183+87.07	21.58	4	9.6			2.0	9.6	6.47			
INSIDE	STA. 183+93.87 TO STA. 184+97.84	103.97	3 TO 7	57.8			12.1		38.99			
INSIDE	STA. 184+97.84 TO STA. 185+93.73	95.89	8	85.2			17.9		57.53			
INSIDE	STA. 187+08.30 TO STA. 187+44.90	36.60	1 TO 7	16.3			3.4		10.98			
INSIDE	STA. 187+44.90 TO STA. 188+57.89	112.99	8	100.4			21.1		67.79			
INSIDE	STA. 188+57.89 TO STA. 198+70.93	1,013.04	6	675.4			141.8		455.87			
STA. EQ. 198+70.93 BK = 198+88.77 AH												
INSIDE	STA. 198+88.77 TO STA. 216+50.00	1,761.23	6	1174.2			246.6		792.55			
				SUB-TOTAL			618.4	1658.4	3051.8	243.8	304.8	7898.94

FILE NAME =	USER NAME = sparksgw	DESIGNED - JWC	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES FAP 662 (IL 4)				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.			
Default	Default	DRAWN - JWC	REVISED -		SCALE: 50	SHEET	OF	SHEETS	STA.	TO	STA.	662	(1-2) RS-1,N	SANGAMON	89	12
		CHECKED - JWC	REVISED -													
		DATE -	REVISED -													