



Note:
The studs of the anchor devices shall be placed below the top reinforcement bars and the outermost longitudinal reinforcement bar shall be placed directly above the studs of the rail post anchor device.

Notes:
See Sheet 11 of 17 for superstructure details, Section A-A, Section B-B, and Bill of Material.

MINIMUM BAR LAP
#5 bar = 2'-3"
#6 bar = 3'-6"
#9 bar = 5'-11"

HALF PLAN-TOP REINFORCEMENT



JOB = 2223.8
FILE = 0150065-74167-09-11-Super.dgn
DATE = 7/24/2014

DESIGNED - AAN
CHECKED - MDC
DRAWN - SJS
CHECKED - MDC

REVISED -
REVISED -
REVISED -
REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**TOP REINFORCEMENT
SUPERSTRUCTURE STRUCTURE NO. 015-0065**

SHEET NO. 9 OF 17 SHEETS

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
673	2BR	COLES	24	16
CONTRACT NO. 74167				

ILLINOIS FED. AID PROJECT