

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				80% FED 20% STATE		
				ROADWAY 0004	BRIDGE SN 079-0020 0014	BRIDGE SN 079-0019 0014
50500505	STUD SHEAR CONNECTORS	EACH	2445		2445	
50800205	REINFORCEMENT BARS, EPOXY COATED	FOUND	98990		97910	1080
50800515	BAR SPLICERS	EACH	66		66	
50900200	STEEL RAILING, TYPE 2399	FOOT	2664			2664
51500100	NAME PLATES	EACH	1		1	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	179.9		102	77.9
52000216	FINGER PLATE EXPANSION JOINT, 5"	FOOT	62.5			62.5
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	10		10	
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	5		5	
52100505	ANCHOR BOLTS, 5/8"	EACH	20		20	
52100520	ANCHOR BOLTS, 1"	EACH	10		10	
58100200	WATERPROOFING MEMBRANE SYSTEM	SO YD	4116			4116
58700300	CONCRETE SEALER	SO FT	550.6		550.6	
59100100	GEOCOMPOSITE WALL DRAIN	SO YD	96		96	

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				80% FED 20% STATE		
				ROADWAY 0004	BRIDGE SN 079-0020 0014	BRIDGE SN 079-0019 0014
63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	3414	3414		
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4		
63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4	4		
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	6	6		
63200310	GUARDRAIL REMOVAL	FOOT	3832	3832		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	7	7		
67100100	MOBILIZATION	L SUM	1	1		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2	2		
78009004	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	10548	10548		
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	4	4		
78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	21	21		
78200410	GUARDRAIL MARKERS, TYPE A	EACH	38	38		
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	6	6		

* SPECIALTY ITEMS

FILE NAME *	USER NAME * #USER#	DESIGNED - JLS	REVISED - 12-20-2011	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			P.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#		DRAWN - POB	REVISED -		SCALE:	SHEET NO. 2 OF 3 SHEETS	STA.	TO STA.	85B	12VB-11	RANDOLPH	72	3A
		CHECKED - BRM	REVISED -		CONTRACT NO. 76409								
		DATE - 03-28-11	REVISED -		ILLINOIS FED. AID PROJECT								