

PAVEMENT MARKING SCHEDULE															
LOCATIONS				THERMOPLASTIC PAVEMENT MARKING								PAINT CURB			
				THERMOPLASTIC PAVEMENT MARKING-LINE 4" YELLOW SKIP DASH	THERMOPLASTIC PAVEMENT MARKING-LINE 4" YELLOW	THERMOPLASTIC PAVEMENT MARKING-LINE 4" DOUBLE YELLOW	THERMOPLASTIC PAVEMENT MARKING-LINE 4" WHITE SKIP DASH	THERMOPLASTIC PAVEMENT MARKING-LINE 2' 6" WHITE SKIP DASH	THERMOPLASTIC PAVEMENT MARKING-LINE 4" WHITE SOLID LINE	THERMOPLASTIC PAVEMENT MARKING-LETTERS AND SYMBOLS	THERMOPLASTIC PAVEMENT MARKING-LINE 12" WHITE DIAGONAL		THERMOPLASTIC PAVEMENT MARKING-LINE 12" CROSS WALK	THERMOPLASTIC PAVEMENT MARKING-LINE 24" WHITE STOP BAR	
FROM		TO		FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	FOOT	FOOT	FOOT	FOOT	
FROM	156+31	TO	179+89	1,160.00	4,686.00	172.00	1,180.00			4,379.00	279.00				
FROM	198+42	TO	222+60	1,080.00	4,406.00	300.00	1,200.00			4,398.00	341.00		55.00		
FROM	222+60	TO	249+13	1,240.00	4,592.00	512.00	1,260.00			4,953.00	406.00		94.00		
FROM	249+13	TO	277+29	920.00	3,604.00	1,804.00	1,390.00	98.00		5,945.00	312.00	48.00	72.00		
FROM	277+29	TO	296+82	880.00	3,576.00	262.00	950.00			3,475.00	312.00		120.00		
FROM	306+91	TO	328+13	650.00	3,232.00	558.00	960.00	40.00		5,687.00	374.00		130.00	140.00	
FROM	328+13	TO	339+09		1,851.00		800.00	137.00		3,297.00	220.00		225.00	347.00	
FROM	339+09	TO	339+95												
FROM	357+30	TO	363+87		1,033.00		300.00	40.00		2,500.00	192.00	247.00	72.00	207.00	
FROM	365+38	TO	376+99		2,127.00	362.00	480.00	40.00		2,201.00	125.00			225.00	
			FRANK SCOTT PKWY									51.00			
			LINCOLN HWY				390.00			1,500.00	141.00	67.00	136.00	430.00	
			LUDWING DR/SALEM			250.00				640.00	62.00		86.00		
			FOUNTAINS PKWY EAST				20.00			684.00	63.00	78.00	56.00	317.00	
			CALCULATED QUANTITY:	5,930.00	29,107.00	4,220.00	8,930.00	355.00		39,659.00	2,827.00	491.00	558.00	1,046.00	1,666.00
			PLAN QUANTITY:				88,201.00				2,827.00		1,049.00	1,046.00	1,666.00

**NOTES:**

LETTERS & SYMBOLS: TURN ARROWS AREA IS 15.6 SQ FT EACH

GENERAL NOTE: RAISED REFLECTIVE PAVEMENT MARKER QUANTITIES ARE BASED ON PREVIOUS JOB, MICROFILM AND FIELD MEASUREMENTS. ALL SHALL BE ASSUMED TO BE APPROXIMATE

THE CONTRACTOR SHALL VERIFY DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.

TWO ARROW COMBO WILL NOT BE REPLACED

REFER TO COVER SHEET FOR OMISSION LOCATIONS

WHITE EDGE LINE TO BE PLACED ON THE ENTIRE LENGTH OF THE PROJECT

(1) INCLUDES HMA SURFACE REMOVAL AND RESURFACING ON FRANK SCOTT PKWY TO 13' EAST OF THE THRU EDGE OF IL 159

(2) INCLUDES HMA SURFACE REMOVAL AND RESURFACING ON LINCOLN HWY FROM STA 20+37 TO STA 24+30 AND 17+58 TO STA 19+64

(3) INCLUDES HMA SURFACE REMOVAL AND RESURFACING ON LUDWIG DR/SALEM PL TO 80' EAST AND 85' WEST OF THE THRU EDGE OF IL 159

(4) INCLUDES HMA SURFACE REMOVAL AND RESURFACING ON FOUNTAINS PKWY TO 107' EAST OF THE THRU EDGE OF IL 159

ADA RAMPS/SIDEWALK/ISLANDS														
DESCRIPTION	LOCATION	SIDEWALK REMOVAL	COMB. CURB & GUTTER REMOVAL	PAVEMENT REMOVAL	MEDIAN REMOVAL	SUB GRANULAR MATERIAL, TYPE B	PCC SIDEWALK, 4"	DETECTABLE WARNINGS	CONC. MEDIAN SURFACE 4"	COMB. CONC. CURB & GUTTER, TYPE B-6.06	COMB. CONC. CURB & GUTTER, TYPE B-6.24	CLASS B PATCHES, 13" TYPE III	PAVEMENT FABRIC	DOWEL BARS, 1 1/2"
		SQ FT	FOOT	SQ YD	SQ FT	CU YD	SQ FT	SQ FT	SQ FT	FOOT	FOOT	SQ YD	SQ FT	EACH
LOWE'S/SMOKEY BONES	WEST/LOWES	250	54				250	20			54			
	EAST/SMOKEY BONES	63	27				180	34			27			
IL 159/LINCOLN TRAIL	SOUTHWEST QUADRANT	76.5	8				85	10			13			
	SOUTHEAST QUADRANT	142.5	25				158	10			29			
	NORTHEAST QUADRANT	105	15				110	10			19			
	SOUTHWEST ISLAND		44		71							20	176	49
	SOUTHEAST ISLAND		69	24	208	6	154	30	211	30	57			
	NORTHEAST ISLAND		36	9	46	2	40	20	55	15	30			
TOTAL QUANTITY		637	278	33	325	8	977	134	266	45	229	20	176	49

SEE CLASS B PATCHES SCHEDULE FOR ADDITIONAL QUANTITIES

**NOTES:**

- SIDE CURB REMOVAL INCLUDED IN SIDEWALK REMOVAL
- EARTH EXCAVATION IS INCLUDED IN THE COST OF MEDIAN REMOVAL AND PCC SIDEWALK, 4"
- SIDE CURB IS MEASURED FOR PAYMENT AS PCC SIDEWALK, 4"
- SEEDING IS INCLUDED IN THE COST OF PCC SIDEWALK, 4"

- SIDEWALK REMOVAL AND PCC SIDEWALK LIMITS SHOWN IN THE SCHEDULE ARE MINIMUMS. ACTUAL REMOVAL AND REPLACEMENT LIMITS SHALL EXTEND TO THE NEXT SIDEWALK JOINT.
- SEE CLASS B PATCHING SCHEDULE FOR ADDITIONAL PATCHING QUANTITIES
- COMBINATION CURB AND GUTTER SHALL INCLUDE VARIABLE WIDTH FLAGS AS SHOWN ON THE PLANS.

FILE NAME =	USER NAME = *USER*	DESIGNED - ___	REVISED - ___	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>PAVEMENT MARKING SCHEDULE</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*FILE#		DRAWN - ___	REVISED - ___					600	(130-1, 130-2)RS-2	ST. CLAIR	36	17
	PLOT SCALE = *SCALE*	CHECKED - ___	REVISED - ___		SCALE: NIS _____ SHEET NO. 4 OF 4 SHEETS			STA. _____ TO STA. _____		CONTRACT NO. 76G55		
	PLOT DATE = *DATE*	DATE - _____	REVISED - ___		FED. ROAD DIST. NO. - [ILLINOIS] FED. AID PROJECT							