

80/20 FEED/ST
CONSTR. CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	RETAINING WALL
				0040 S. N. 042-W001
20300100	CHANNEL EXCAVATION	CU YD	3927	3927
28100707	STONE DUMPED RIPRAP, CLASS A4	SQ YD	589	589
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	1223	1223
40603087	HOT-MIX ASPHALT BINDER COURSE, IL-19.0 FG, N70	TON	274	274
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	103	103
44000100	PAVEMENT REMOVAL	SQ YD	518	518
50300225	CONCRETE STRUCTURES	CU YD	8.5	8.5
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	97070	97070
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	770	770
51201900	FURNISHING STEEL PILES HP14X89	FOOT	1020	1020
51500100	NAME PLATES	EACH	1	1
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	687.5	687.5
63200310	GUARDRAIL REMOVAL	FOOT	700	700
* 63301990	REMOVE AND REERECT TRAFFIC BARRIER TERMINALS, TYPE 1	EACH	1	1
	* SPECIALTY ITEMS			

FILE NAME =	USER NAME = ohallendaska	DESIGNED -	REVISED -
c:\pvc\work\pvc\dot\ohallendaska\08374498	0876G94-aht-500.dgn	DRAWN -	REVISED -
	PLOT SCALE = 100.0000 / 1"	CHECKED -	REVISED -
#MODELNAME#	PLOT DATE = 6/27/2014	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
304	21-5	JERSEY	20	3
SCALE: SHEET OF SHEETS STA. TO STA.			CONTRACT NO. 76G94	
ILLINOIS FED. AID PROJECT				