

80/20 FED/ST

CONSTR. CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	RETAINING WALL
				0040 S. N. 042-W001
67100100	MOBILIZATION	L SUM	1	1
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	580	580
70400100	TEMPORARY CONCRETE BARRIER	FOOT	325	325
70600255	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2	EACH	1	1
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	69	69
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1600	1600
78200410	GUARDRAIL MARKERS, TYPE A	EACH	12	12
78300100	PAVEMENT MARKING REMOVAL	SQ FT	494	494
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	2550	2550
X5121800	PERMANENT STEEL SHEET PILING	SO FT	14609	14609
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1
Z0065000	SETTING PILES IN ROCK	EACH	17	17
X0327780	FIBERGLASS REINFORCED POLYESTER RAILING	FOOT	313	313
X0327782	FIBERGLASS REINFORCED POLYESTER STAIR AND GRATING SYSTEM	SQ FT	351	351
	*SPECIALTY ITEMS			

FILE NAME =	USER NAME = ehallandaka	DESIGNED -	REVISED -
o:\pvc\work\pvc\dot\ehallandaka\d0374490	0876094-ah1-500.dgn	DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / IN	CHECKED -	REVISED -
#MODELNAME#	PLOT DATE = 6/27/2014	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
304	2I-5	JERSEY	20	4
SCALE: SHEET OF SHEETS STA. TO STA.			CONTRACT NO. 76694	
ILLINOIS FED. AID PROJECT				