

REMOVE AND REERECT TRAFFIC BARRIER TERMINALS, TYPE 1



THERMOPLASTIC PAVEMENT MARKING -
LETTERS AND SYMBOLS - 11.5 SQ FT, TYPICAL

THERMOPLASTIC PAVEMENT MARKING -
LINE 4" WHITE - 1600'

Ø RTE 100 | 1155+00

PROPOSED SPBGR 31.25'
24' RADIUS

PROPOSED SPBGR 75'

PROPOSED SPBGR 75'
65' RADIUS

PROPOSED SPBGR 25'

PROPOSED SPBGR 25'
45' RADIUS

PROPOSED SPBGR 31.25'

PROPOSED SPBGR - 25'
25' RADIUS

PROPOSED SPBGR - 12.5'

PROPOSED SPBGR - 87.5'
300' RADIUS

PROPOSED SPBGR - 162.5'

PROPOSED SPBGR - 162.5'

NOTE: EACH RUN OF GUARDRAIL IS TO HAVE
4 - GUARDRAIL MARKERS, TYPE A
INSTALLED AS PER STANDARD 635006-03.

FILE NAME =	USER NAME = challandeske	DESIGNED - John Uehle	REVISED -
et:\pw\work\p1dot\challandeske\d0374498	D876094-sht.pmk.dgn	DRAWN - John Uehle	REVISED -
#MODELNAME#	PLOT SCALE = 50:0.001 fts/in.	CHECKED -	REVISED -
	PLOT DATE = 6/27/2014	DATE - 4/7/14	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

PLAN SHEET

SCALE: 1"=25' SHEET 1 OF 1 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
304	2I-5	JERSEY	20	7
CONTRACT NO. 76C94				
ILLINOIS FED. AID PROJECT				