


## CONDUIT SUPPORT DETAIL UNDER WB 63RD ST. LANES




LOOKING EAST

## CONDUIT MOUNTING DETAILS ALONG BRIDGE N.T.S.

## NOTES:

- 1. CONDUIT SUPPORT SHALL BE INSTALLED EVERY 10FT. COORDINATE WITH STRUCTURAL ENGINEER FOR SUPPORT INSTALLATION.
- 2. CONDUIT SUPPORT SYSTEM INCLUDING ALL ASSOCIATED HARDWARE SHALL BE INCLUDED IN THE COST OF 3-INCH RGS CONDUIT PAY ITEM INCLUDED IN TRAFFIC SIGNAL PLANS, SEE TRAFFIC SIGNAL PLANS FOR CONDUIT ROUTING.
- 3. SEE STRUCTURE PLANS FOR LOCATION OF CONDUIT MOUNTING ASSMBLIES.
- 4. SEE PPROPOSED UNDERPASS LIGHTING PLANS SHEET E-2 FOR CONDUIT ROUTING.
- 5. CONDUIT SUPPORT SYSTEM INCLUDING ALL HARDWARE SHALL BE INCLUDED IN THE COST OF 3-INCH PVCC RGC FOR HIGHMAST LIGHTING.



CONDUIT CLAMP DETAIL

DESIGNED - BN REVISED REVISED PLOT SCALE . 60.0000001.000000 CHECKED - KGP REVISED -SNIGH + ASSOCIATES P.C. PLOT DATE = 15-MAY-2013 17:25 5/15/2013 REVISED

STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION** 

63rd STREET OVER DAN RYAN EXPRESSWAY (1-90 /94) CONDUIT MOUNTING DETAILS ALONG BRIDGE SCALE: N.T.S. SHEET NO. 5 OF 13 SHEETS STA.

COUNTY TOTAL SHEET NO. SECTION CQOK 137 51 1920-8 CONTRACT NO. 60JI5