

The above deflections are not to be used in the field if the engineer is working from the grade elevations adjusted for dead load deflections as shown on Sheets 5 and 6 of 20. To determine ''t": After all precast prestressed beams have been erected, elevations of the top flanges of the beams shall be taken at intervals shown below. These elevations subtracted from the ''Theoretical Grade Elevations Adjusted for Dead Load Deflections" shown on Sheets 5 and 6 of 20, minus slab thickness, equals the fillet heights ''t" above top flanges of beams.



PLAN

					(Sheet 1 of 3)			
Wight		DESIGNED - MWS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	TOP OF SLAB ELEVATIONS Structure No. 081–0196	F.A.P.	SECTION	COUNTY TOTAL SHEET
		CHECKED - TAY	REVISED -			599	103MFT-BR	ROCK ISLAND 88 35
		DRAWN - MWS	REVISED -					CONTRACT NO. 64D18
	PLOT DATE = 6/19/2013	CHECKED - BJM	REVISED -		SHEET NO. 4 OF 20 SHEETS	ILLINOIS FED. AID PROJECT		





