

HOT MIX ASPHALT SCHEDULE

LOCATION	LENGTH	WIDTH	AREA	QUANTITY DEPTH	40603310	40600625	40603080	40701906	48203021	40600982	44004250	Z0004638	44300200
					HMA SC "C" N50	LEV BIND MM N50	HMA BC IL- 19.0 N50	HMA PAVT FD 11.25	HMA SHLDR 6	HMA SUR REM BUTT JT	PAVED SHLD REMOVAL	PAVT BREAKING	STRIP REF CON TR
	FOOT	FOOT	SQ YD	INCHES	TON	TON	TON	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	FOOT
STA. 283+00 TO STA. 284+12	112	26.00	324							324			
STA. 283+00 TO STA. 284+21	121	26.33	354	2.25	45								
STA. 282+60 TO STA.286+57.5 LT	397.5		317	2.00	36								
STA. 282+60 TO STA.286+57.5 RT	397.5		317	6.00				317			280		
STA. 282+43 TO STA.286+57.5 RT	414.5		312	2.00	35								
STA. 282+43 TO STA.286+57.5 RT	414.5		312	6.00				312			298		
STA. 284+21 TO STA. 285+15	94	26.33	275	2.00	31								
STA. 284+21 TO STA. 285+15	94	26.77	280	5.00		78							282
STA. 285+15 TO STA.286+57.5	142.5	26.94	427	11.25				427					
STA. 285+15 TO STA.286+57.5	142.5	33.61	532	3.34			99						428
STA.287+87.5 TO STA. 290+90	302.5	26.94	905	11.25				905			905		
STA.287+87.5 TO STA. 293+50 LT	562.5		222	2.00	25								
STA.287+87.5 TO STA. 293+50 LT	562.5		323	6.00				323		151			
STA.287+87.5 TO STA. 293+50 RT	562.5		222	2.00	25								
STA.287+87.5 TO STA. 293+50 RT	562.5		315	6.00				315		100			
STA. 290+90 TO STA. 291+85	95	26.33	278	2.00	31								
STA. 290+90 TO STA. 291+85	95	27.10	286	5.00			53						285
STA. 291+85 TO STA. 292+83	98	26.33	287	2.00	32								
STA. 291+85 TO STA. 292+83	98	26.77	292	5.00		82							294
STA. 292+83 TO STA. 293+50	67	26.33	196	2.25	25								
STA. 292+94 TO STA. 293+50	56	26.00	162	2.00						162			
HAHNAMAN ROAD AND IL 40 LT			156	11.25				156					150
HAHNAMAN ROAD AND IL 40 LT			44	2.00	5			44					
TOTALS =					290	160	152	1488	1311	486	829	905	1439

GUARDRAIL SCHEDULE

LOCATION	63200310	63000001	63100085	63100169	63500105	78200410	78200520	78201000
	GUARDRAIL REMOVAL	SPBGR TY A 6FT POSTS	TR BAR TRM T6	TR BAR TRM T1 SPL FLR	DELINEATORS	GUARDRAIL MKR TYPE A	BAR WALL MKR TYPE B	TERM MARK DIR APPLIED
	FOOT	FOOT	EACH	EACH	EACH	EACH	EACH	EACH
STA. 282+61 TO STA. 285+05 LT	244							
STA. 282+43 TO STA. 284+01 RT	159							
STA. 285+40 TO STA. 289+66 LT	426							
STA. 284+53 TO STA. 289+04 RT	451							
STA. 282+43 TO STA. 282+86 RT			1					
STA. 282+86 TO STA. 283+23 RT		37.5				1		
STA. 283+23 TO STA. 283+73 RT				1	1			1
STA. 282+61 TO STA. 283+03 LT			1					
STA. 283+03 TO STA. 283+78 LT		75.0			1	1		
STA. 283+78 TO STA. 284+28 LT				1	1			1
STA. 285+29 TO STA. 285+79 RT				1	1			1
STA. 285+79 TO STA. 286+29 RT		50.0				1		
STA. 286+29 TO STA. 286+58 RT			1					
STA. 285+54 TO STA. 286+04 LT				1	1			1
STA. 286+04 TO STA. 286+29 LT		25.0				1		
STA. 286+29 TO STA. 286+58 LT			1					
STA. 286+58 TO STA. 287+88 LT							1	
STA. 287+88 TO STA. 287+88 RT							1	
STA. 287+73 TO STA. 288+16 RT			1					
STA. 288+16 TO STA. 288+41 RT		25.0				1		
STA. 288+41 TO STA. 288+91 RT				1	1			1
STA. 287+73 TO STA. 288+16 LT			1					
STA. 288+16 TO STA. 288+66 LT		50.0				1		
STA. 288+66 TO STA. 289+16 LT				1	1			1
TOTALS =	1280	262.5	6	6	7	6	2	6

DRAINAGE SCHEDULE

LOCATION	54200220	61000335	60100945	54215547	54215550	60900515	60100080
	P CUL CL D 1 15	TY G INLET BOX 610001	PIPE DRAINS 12	METAL END SECTIONS 12"	METAL END SECTIONS 15"	CONC THRUST BLOCKS	FRENCH DRAINS
	FOOT	EACH	EACH	EACH	EACH	EACH	CU YD
STA. 289+53 TO STA. 290+22	45.3RT				2		
STA. 289+72 TO STA. 290+28	45.4LT				2		
STA. 286+86 TO STA. 286+86	30.0' LT						
STA. 289+72 TO STA. 286+86	30.0' LT						
STA. 286+55 TO STA. 286+55	30.0LT	1	16	1		1	
STA. 286+55 TO STA. 286+55	36.0RT	1	22	1		1	
STA. 287+94 TO STA. 287+94	26.2LT						1.5
STA. 287+94 TO STA. 287+94	28.5RT						1.7
STA. 290+90 TO STA. 290+90	25.2LT						1.4
STA. 290+90 TO STA. 290+90	25.2RT						1.4
HAHNAMAN ROAD AND IL 40		50			2		
TOTALS =	177	2	38	2	6	2	6.0

AGGREGATE SCHEDULE

LOCATION	35102000	30300011	48102100
	AGG BASE CSE B 8	AGG SUBGRADE IMPR	AGG WEDGE SHLD TYPE B
	SQ YD	TON	TON
STA. 284+15 (FE) RT	159		
STA. 285+00 (FE) LT	199		
STA. 289+81 (FE) RT	159		
STA. 290+00 (FE) LT	159		
STA. 285+15 TO STA.286+57.5 LT		52	
STA. 285+15 TO STA.286+57.5 RT		51	
STA.287+87.5 TO STA. 290+90		459	
HAHNAMAN ROAD AND IL 40			3
HAHNAMAN ROAD AND IL 40 (FE)	65		
TOTALS =	741	562	3

ROW AND SECTION MARKERS SCHEDULE

LOCATION	66600105	Z0049300
	FUR ERECT ROW MARKERS	REF LAND MARKERS
	EACH	EACH
STA. 285+57.76 49.90' RT	1	
STA. 286+75.00 75.00' RT	1	
STA. 289+50.00 75.00' RT	1	
STA. 290+50.00 60.00' RT	1	
STA. 291+50.00 50.00' RT	1	
STA. 292+00.00 40.04' RT	1	
STA. 285+58.29 54.71' LT	1	
STA. 286+50.00 65.00' LT	1	
STA. 289+50.00 65.00' LT	1	
STA. 291+50.00 55.00' LT	1	
STA. 291+97.00 41.99' LT	1	
STA. 561+95.00 40.00' LT	1	
STA. 159+40.00 40.00' LT	1	
STA. 286+57.84 7.81' LT		1
TOTALS =	13	1

EARTHWORK SCHEDULE

LOCATION	20200100	75%	EMBANKMENT	EARTHWORK BALANCE
	EARTH EXCAVATION	EARTH EXCAVATION	CU. YD.	BALANCE WASTE (+) OR SHORTAGE (-)
	CU. YD.	CU. YD.	CU. YD.	CU. YD.
STA. 283+00 TO STA. 286+88	92	69	600	-531
STA. 287+58 TO STA. 293+50	344	258	2045	-1787
HAHNAMAN ROAD AND IL 40	2	2	5	-3
TOTAL =	438	329	2649	-2320

EROSION CONTROL SCHEDULE

LOCATION	28000400	28000305	28000500
	PERIMETER EROS BAR	TEMP DITCH CHECKS	INLET & PIPE PROTECT
	FOOT	FOOT	FOOT
STA. 282+72 TO STA. 284+83 LT	236		
STA. 285+20 TO STA. 286+75 LT	196		
STA. 287+68 TO STA. 289+69 LT	228		
STA. 290+37 TO STA. 293+01 LT	268		
STA. 282+45 TO STA. 283+97 RT	166		
STA. 284+36 TO STA. 286+76 RT	262		
STA. 287+58 TO STA. 289+64 RT	216		
STA. 290+15 TO STA. 293+34 RT	321		
STA. 287+90		10	
STA. 287+90		10	
STA. 291+40		10	
STA. 291+40		10	
STA. 290+22			1
STA. 290+28			1
HAHNAMAN ROAD AND IL 40			1
TOTALS =	1893	40	3

SEEDING SCHEDULE

LOCATION	25000210	25100125	25100630	28000250	25000750
	SEEDING CL 2A	MULCH METHOD 3	EROSION CONTR BLANKET	TEMP EROS CONTR SEED	MOWING
	ACRE	ACRE	SQ YD	POUND	ACRE
STA. 282+92 TO STA. 284+88 LT	0.12	0.06	290	24	0.12
STA. 285+12 TO STA. 286+73 LT	0.09	0.05	218	18	0.09
STA. 287+73 TO STA. 289+88 LT	0.15	0.08	363	30	0.15
STA. 290+12 TO STA. 293+50 LT	0.16	0.08	387	32	0.16
STA. 282+90 TO STA. 284+03 RT	0.05	0.02	97	10	0.05
STA. 284+27 TO STA. 286+73 RT	0.14	0.07	339	28	0.14
STA. 287+73 TO STA. 289+69 RT	0.23	0.10	484	46	0.23
STA. 289+93 TO STA. 293+50 RT	0.22	0.09	411	44	0.22
HAHNAMAN ROAD AND IL 40	0.11				0.11
TOTALS =	1.3	0.5	2589	232	1.3

PAVEMENT MARKING

LOCATION	NUMBER OF APPLICATIONS	78001110	78001110	78100100
		PAINT PVT MK LINE 4 (WHITE)	PAINT PVT MK LINE 4 (YELLOW)	RAISED REFL PAVT MKR
		FOOT	FOOT	EACH
STA. 282+43 TO STA. 293+50 LT	2	2214		
STA. 283+61 TO STA. 293+50 RT	2	1978		
STA. 283+43 TO STA. 293+50	2		504	14
TOTALS =		4192	504	14

CONCRETE CURB AND APPROACH SLAB REMOVAL SCHEDULE

LOCATION	44000100	66201120	Z0004552
	PAVEMENT REM	CONC SHLD CURB	APPROACH SLAB RM
	SQ YD	FOOT	SQ YD
STA. 286+50 16.0' LT TO STA. 286+55 16.0' LT		5	
STA. 286+50 16.0' RT TO STA. 286+55 16.0' RT		5	
STA. 286+56 TO STA. 286+80	71		
STA. 286+80 TO STA. 287+00			53
STA. 287+44 TO STA. 287+64			53
STA. 287+64 TO STA. 287+90	75		
TOTALS =	146	10	106