



PLAN FOR TOP OF SLAB ELEVATIONS

WEST EDGE OF SHOULDER

Location	Station	Offset	Theoretical Grade Elevations
S. End S. Appr. Pvmt.	286+57.50	-16.00	631.06
A1	286+67.50	-16.00	631.11
B1	286+77.50	-16.00	631.16
N. End S. Appr. Pvmt.	286+87.50	-16.00	631.21

WEST EDGE OF PAVEMENT

Location	Station	Offset	Theoretical Grade Elevations
S. End S. Appr. Pvmt.	286+57.50	-12.00	631.14
A1	286+67.50	-12.00	631.19
B1	286+77.50	-12.00	631.24
N. End S. Appr. Pvmt.	286+87.50	-12.00	631.29

Q & PGL IL 172

Location	Station	Offset	Theoretical Grade Elevations
S. End S. Appr. Pvmt.	286+57.50	0.00	631.33
A1	286+67.50	0.00	631.38
B1	286+77.50	0.00	631.43
N. End S. Appr. Pvmt.	286+87.50	0.00	631.48

EAST EDGE OF PAVEMENT

Location	Station	Offset	Theoretical Grade Elevations
S. End S. Appr. Pvmt.	286+57.50	12.00	631.14
A1	286+67.50	12.00	631.19
B1	286+77.50	12.00	631.24
N. End S. Appr. Pvmt.	286+87.50	12.00	631.29

EAST EDGE OF SHOULDER

Location	Station	Offset	Theoretical Grade Elevations
S. End S. Appr. Pvmt.	286+57.50	16.00	631.06
A1	286+67.50	16.00	631.11
B1	286+77.50	16.00	631.16
N. End S. Appr. Pvmt.	286+87.50	16.00	631.21

FILE NAME = ...E4D81-SN09820119-005-5Appr-TSE.dgn



Zroka Engineering, P.C.
4216 North Hermitage
Chicago, IL 60613

USER NAME = SAW	DESIGNED - PMM	REVISED -
PLOT SCALE = 0:2.0000 't' / in.	CHECKED - DAZ	REVISED -
PLOT DATE = 5/2/2013	DRAWN - SAW	REVISED -
	CHECKED - LAS	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SOUTH APPROACH TOP OF SLAB ELEVATIONS
S.N. 098-0119

SHEET NO. 5 OF 19 SHEETS

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
200	141B-2	WHITESIDE	77	30
CONTRACT NO. 64D81				
ILLINOIS FED. AID PROJECT				