

GENERAL NOTES

PLAN DIMENSIONS AND DETAILS RELATIVE TO EXISTING PLANS ARE SUBJECT TO ROUTINE VARIATIONS. THE CONTRACTOR SHALL FIELD VERIFY EXISTING DIMENSIONS AND DETAILS AFFECTING NEW CONSTRUCTION AND MAKE NECESSARY APPROVED ADJUSTMENTS PRIOR TO CONSTRUCTION OR ORDERING OF MATERIALS. SUCH VARIATIONS SHALL NOT BE CAUSE FOR ADDITIONAL COMPENSATION FOR A CHANGE IN THE SCOPE OF THE WORK. HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY FURNISHED BASED UPON THE UNIT BID FOR THE WORK.

FOR STABILIZATION, ALL TYPE III BARRICADES SHALL REQUIRE A MINIMUM OF FOUR SAND BAGS PER BARRICADE.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING UTILITY PROPERTY FROM CONSTRUCTION OPERATIONS AS OUTLINED IN ARTICLE 107.31 OF THE STANDARD SPECIFICATIONS. THE "JULIE" NUMBER IS 1-800-892-0123. A MINIMUM OF FORTY-EIGHT (48) HOURS ADVANCE NOTICE IS REQUIRED.

ANY REFERENCE TO A STANDARD IN THESE PLANS SHALL BE INTERPRETED TO MEAN THE EDITION AS INDICATED BY THE SUBNUMBER LISTED ON THE INDEX OF SHEETS OR THE COPY OF THE STANDARD INCLUDED IN THESE PLANS.

THE CONTRACTOR SHALL BE REQUIRED TO SECURE WASTE CONTAINERS THAT REMAIN ON THE JOB SITE. THIS WILL ENTAIL THAT ALL WASTE CONTAINERS CAN NOT BE MOVED OR OPENED DURING NON-WORKING HOURS.

WORKING DAYS SHALL BE CHARGED UNTIL THE CONTRACTOR/ SUBCONTRACTOR LICENSED TO DISPOSE OF LEAD PAINT RESIDUE HAS REMOVED THE WASTE MATERIAL FROM THE JOB SITE ACCORDING TO ALL FEDERAL, STATE AND LOCAL LAWS AND ORDINANCES.

THE EXISTING STEEL CONTAINS LEAD. THE CONTRACTOR SHOULD TAKE APPROPRIATE PRECAUTIONS TO DEAL WITH THE PRESENCE OF LEAD PAINT ON THIS PROJECT.

THE SSPC-OP1 AND SSPC-OP2 PAINTING CONTRACTOR CERTICATIONS WILL BE REQUIRED FOR THIS PROJECT.

THE CLEANING AND PAINTING OF THE EXISTING STEEL SHALL BE AS SPECIFIED IN THE SPECIAL PROVISION FOR "CLEANING AND PAINTING EXISTING STEEL BUILDINGS".

ALL EXISTING EXTERIOR STEEL, INCLUDING WALLS, DOORS, TRIM WORK, GUTTERS AND ROOFS SHALL BE CLEANED PER "LOW PRESSURE WATER CLEANING" SSPC-SP12. ALL EXISTING EXTERIOR STEEL INCLUDING WALLS, DOORS, TRIM WORK GUTTERS AND ROOFS SHALL BE PAINTED WITH AN APPROVED GALVANIZED METAL PRIMER OR ACRYLIC PRIMER SUITABLE FOR METAL AND TWO (2) COATS OF AN APPROVED "ACRYLIC PAINT". THE COLOR OF THE FINAL FINISH COAT FOR THE EXTERIOR WALLS SHALL BE "TAN". THE COLOR OF THE FINAL FINISH COAT FOR DOORS, WINDOWS AND ROOFS SHALL BE "WHITE". THE FINAL FINISH COAT FOR ALL TRIM WORK SHALL BE DARK BROWN. ALL PAINT MATERIALS SHALL BE APPROVED BY THE ENGINEER PRIOR TO THE ORDERING OF MATERIALS.

DATE: 7-9-13

PREPARED BY: Don Bonail
DISTRICT STUDIES & PLANS ENGINEER

EXAMINED BY: Herb Jones
DISTRICT CONSTRUCTION ENGINEER

Wynne Mullins
DISTRICT MATERIALS ENGINEER

Bruce A. Huber
DISTRICT OPERATIONS ENGINEER

FILE NAME =	USER NAME = woodshankr1	DESIGNED - RW	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL NOTES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\pido\woodshankr1\0336544\366004\shc\detail.dgn	DRAWN - RW	REVISED -	VAR			03 FACILITY PRESERVATION 2014-1	*	6	2	
#MODELNAME#	PLOT SCALE = 1/8"=1'-0" / in.	CHECKED -	REVISED -			* IROQUOIS AND LIVINGSTON			CONTRACT NO. 66004	
	PLOT DATE = 7/2/2013	DATE -	REVISED -			ILLINOIS FED. AID PROJECT				
				SCALE:	SHEET 1 OF 1 SHEETS	STA.	TO STA.			