

039

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

F.A.I. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70 / 57		EFFINGHAM	3	1
ILLINOIS CONTRACT NO. 74922				

FOR INDEX OF SHEETS, SEE SHEET NO. 2


# PROPOSED HIGHWAY PLANS

FAI ROUTE 70 /57 (I-70 & I-57)  
SECTION D7 ASH BORER CONTROL 2020-1  
TREE REMOVAL  
EFFINGHAM COUNTY

C-97-084-19

PROJECT LOCATION:  
I-70 R.O.W. & MEDIAN FROM M.P. 98 TO M.P. 105  
I-57 R.O.W. & MEDIAN FROM 70/57 INTERCHANGE TO M.P. 166


D-97-040-19



FULL SIZE PLANS HAVE BEEN PREPARED USING STANDARD ENGINEERING SCALES. REDUCED SIZED PLANS WILL NOT CONFORM TO STANDARD SCALES. IN MAKING MEASUREMENTS ON REDUCED PLANS, THE ABOVE SCALES MAY BE USED.

J.U.L.I.E.  
JOINT UTILITY LOCATION INFORMATION FOR EXCAVATORS  
1-800-892-0123  
OR 811

PROJECT ENGINEER DEBRA BARRETT  
PROJECT MANAGER KYLE PRICE  
PHONE No. (217) 342-8244  
CONTRACT NO. 74922



STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUBMITTED July 10 20 19  
Jeffrey P. Myers REGIONAL ENGINEER  
Aug 16 20 19  
Paul P. [Signature] ENGINEER OF DESIGN AND ENVIRONMENT  
Aug 16 20 19  
Paul P. [Signature] DIRECTOR OF HIGHWAYS PROJECT IMPLEMENTATION 3

PRINTED BY THE AUTHORITY  
OF THE STATE OF ILLINOIS

INDEX OF SHEETS

<u>SHEET NO.</u>	<u>TITLE</u>
1	COVER SHEET
2	GENERAL NOTES, INDEX OF SHEETS, LIST OF STANDARDS
3	SUMMARY OF QUANTITIES

THE FOLLOWING STANDARDS ARE A PART OF THESE PLANS AND ARE INCLUDED AFTER SHEET 3:

000001-07	STANDARD SYMBOLS, ABBREVIATIONS, AND PATTERNS
701101-05	OFF-ROAD OPERATIONS, MULTILANE, 15' TO 24" FROM PAVEMENT EDGE
701106-02	OFF-ROAD OPERATIONS, MULTILANE, MORE THAN 15' FROM EDGE OF PAVEMENT
701426-09	LANE CLOSURE, MULTILANE, INTERMITTENT OR MOVING OPERATION, FOR SPEEDS $\geq$ 45 MPH
701901-08	TRAFFIC CONTROL DEVICES

GENERAL NOTES

THE WORK INCLUDED IN THIS CONTRACT CONSISTS OF TREE REMOVAL, SEEDING, AND TRAFFIC CONTROL.

ALL TREES CUT DOWN SHALL BE REMOVED FROM THE STATE RIGHT OF WAY AND DISPOSED OF PER SECTION 201 OF THE "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION" AND THE CONTRACT SPECIAL PROVISIONS.

ALL TREE REMOVAL WILL BE ON THE EASTBOUND, WESTBOUND IN THE MEDIAN OF THE I-70 RIGHT OF WAY BETWEEN M.P. 98 AND M.P. 105, AND ON THE NORTHBOUND, SOUTHBOUND IN THE MEDIAN OF THE I-57 RIGHT OF WAY BETWEEN THE I-57 AND I-70 INTERCHANGE AND M.P. 166. ALL TREES TO BE REMOVED WILL BE MARKED BY DISTRICT 7 OPERATIONS.

THIS PROJECT HAS AN URBAN/RURAL SPLIT ON I-70. M.P. 98 TO M.P. 98.48 IS URBAN. M.P. 98.48 TO M.P. 105 IS RURAL.

THIS PROJECT HAS AN URBAN/RURAL SPLIT ON I-57. FROM THE I-70/I-57 INTERCHANGE TO M.P. 165 IS URBAN. M.P. 165 TO M.P. 166 IS RURAL.

THE CONTRACTOR SHALL NOTIFY DISTRICT 7 OPERATIONS AT 217-342-8265 THIRTY DAYS PRIOR TO THE START OF THE PROJECT.

REV. - MS

\*\* D7 ASH BORER CONTROL 2020-1

MODEL: Default  
FILE: M:\MS15\_PlanRoom.dwg  
PROJECT: 174922\_CADDData\CAD\Sheets\174922-shc-genote.dgn

USER NAME = steffemk	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>INDEX OF SHEETS &amp; GENERAL NOTES</b>	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
	DRAWN -	REVISED -			70 / 57	**	EFFINGHAM	3	2	
PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -			CONTRACT NO. 74922					
PLOT DATE = 7/10/2019	DATE -	REVISED -			SCALE:	SHEET OF SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT		

