FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT

IL-60 - TOTAL EARTHWORK QUANTITIES BY STATION

STATION TO STATION	EARTH EXCAVATION (CU YD)	EARTH EXCAVATION (SPECIAL) (CU YD)	REM. & DISP. UNSUITABLE MATERIAL (CU YD)	EARTHWORK BALANCE (CU YD)	POROUS GRAN, MAT SUBGRADE (CU YD)
434+50 TO 441+25	1415.0	730.0	1790.0	7005.0	0.0
441+50 TO 444+50	575.0	1610.0	2100.0	20490.0	0.0
446+50 TO 451+50	855.0	1130.0	4825.0	26445.0	2715.0
452+00 TO 460+00	2670.0	1595.0	4295.0	13815.0	1470.0
460+50 TO 470+50	1580.0	0.0	1635.0	-1900.0*	0.0
TOTAL (ROUNDED)	7095.0	5065.0	14645.0	65855 . 0*	4185.0

EARTHWORK BALANCE = FURNISHED EXCAVATION (SEE FORMULA BELOW)

IL-60 - EARTH EXCAVATION BY STAGE AND STATION

STATION TO STATION	PRE STAGE (CU YD)	STAGE 1 (CU YD)	STAGE 1A (CU YD)	STAGE 2 (CU YD)	STAGE 3 (CU YD)	STAGE 3A (CU YD)	STAGE 4 (CU YD)	STAGE 5 (CU YD)	TOTALS BY STATION (ROUNDED)
434+50 TO 441+25	91.0	524.8	43.7	129.7	375.8	82.5	121.8	41.3	1415.0
441+50 TO 444+50	24.0	384.6	0.0	0.0	162.9	0.0	0.0	0.0	575.0
446+50 TO 451+50	81.7	145.5	81.5	142.8	311.3	12.4	55.7	21.8	855.0
452+00 TO 460+00	107.9	1107.8	0.0	27.3	1084.9	0.0	19.8	321.8	2670.0
460+50 TO 470+50	363.0	0.0	0.0	0.0	1094.7	0.0	0.0	119.1	1580.0
TOTAL (ROUNDED)	670.0	2165.0	130.0	300.0	3030.0	95.0	200.0	505.0	7095.0

IL-60 - EARTH EXCAVATION (SPECIAL) BY STAGE AND STATION

STATION TO STATION	PRE STAGE (CU YD)	STAGE 1 (CU YD)	STAGE 1A (CU YD)	STAGE 2 (CU YD)	STAGE 3 (CU YD)	STAGE 3A (CU YD)	STAGE 4 (CU YD)	STAGE 5 (CU YD)	TOTALS BY STATION (ROUNDED)
434+50 TO 441+25	0.0	386.6	0.0	144.7	198.7	0.0	0.0	0.0	730.0
441+50 TO 444+50	0.0	940.9	0.0	0.0	668.2	0.0	0.0	0.0	1610.0
446+50 TO 451+50	0.0	413.6	0.0	128.3	453.1	0.0	131.7	0.0	1130.0
452+00 TO 460+00	0.0	1155.2	0.0	76.3	324.4	0.0	38,1	0.0	1595.0
460+50 TO 470+50	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
TOTAL (ROUNDED)	0.0	2900.0	0.0	350.0	1645.0	0.0	170.0	0.0	5065.0

IL-60 - REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL BY STAGE AND STATION

STATION TO STATION	PRE STAGE (CU YD)	STAGE 1 (CU YD)	STAGE 1A (CU YD)	STAGE 2 (CU YD)	STAGE 3 (CU YD)	STAGE 3A (CU YD)	STAGE 4 (CU YD)	STAGE 5 (CU YD)	TOTALS B STATION (ROUNDED
434+50 TO 441+25	0.0	773.8	0.0	187.0	689.1	0.0	135.3	0.0	1790.0
!									
441+50 TO 444+50	0.0	1095.0	0.0	0.0	1003.3	0.0	0.0	0.0	2100.0
446+50 TO 451+50	0.0	3389.6	0.0	192.7	1047.2	0.0	194.6	0.0	4825.0
452+00 TO 460+00	269.3	1574.1	0.0	96.6	2054.8	0.0	73.3	223.5	4295.0
460+50 TO 470+50	680.5	0.0	0.0	0.0	951.6	0.0	0.0	0.0	1635.0
TOTAL (ROUNDED)	950.0	6835.0	0.0	480.0	5750.0	0.0	405.0	225.0	14645.0

IL-60 - REQUIRED EMBANKMENT AND EARTHWORK BALANCE BY STAGE AND STATION

	PRE. S	STAGE	STA	GE 1	STAC	GE 1A	STA	GE 2	2 STAGE 3		STAGE 3A		STAGE 4		STAGE 5		TOTALS BY STATION (ROUNDED)	
STATION TO STATION	EMBANKMENT (CU YD)	EARTHWORK BALANCE (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE (CU YD)														
434+50 TO 441+25	0.0	-77.4	3132.2	2357.3	0.0	-37.1	927.2	693.9	3560.6	3072.5	0.0	-70.1	582.8	479.3	618.3	583.1	8825.0	7005.0
441+50 TO 444+50	0.0	-20.4	13876.3	12749.7	0.0	0.0	0.0	0.0	8219.1	7512.7	0.0	0.0	0.0	0.0	243.3	243.3	22340.0	20490.0
446+50 TO 451+50	0.0	-69.5	13199.7	12724.5	0.0	-69.3	957.1	726.7	11957.9	11308.6	0.0	-10.5	1575.0	1415.3	434.4	415.9	28125.0	26445.0
452+00 TO 460+00	143.6	51.9	10706.0	8782.5	0.0	0.0	770.6	682.5	4949.5	3751 . 6	0.0	0.0	610.8	561.6	253.1	-19.1	17435.0	13815.0
460+50 TO 470+50	4.4	-304.2	0.0	-682.4*	0.0	0.0	.0.0	-28.6*	164.2	-1056.6*	0.0	-252.3*	0.0	0.0	520.4	419.2	690.0	-1900.0*
TOTAL (ROUNDED)	150.0	-415.0	40915.0	35935 . 0*	0.0	-105.0	2655.0	2075.0*	28855.0	24590.0*	0.0	-330.0*	2770.0	2460.0	2070.0	1645.0	77415.0	65855 . 0*

EARTHWORK BALANCE = FURNISHED EXCAVATION = EMBANKMENT - (1 - (SHRINKAGE FACTOR (0.15)) X (EARTH EXCAVATION + EARTH EXCAVATION (SPECIAL))).

A POSITIVE QUANTITY IMPLIES THAT FURNISHED EXCAVATION WILL BE REQUIRED. A NEGATIVE QUANTITY IMPLIES THAT THERE IS EXCESS EXCAVATED MATERIAL

THAT CAN BE USED ELSEWHERE WITHIN THE PROJECT LIMITS.

* - INCLUDES EARTHWORK BALANCE QUANTITIES ALONG FIELD DRIVE, ALONG SAUNDERS ROAD, AND ALONG THE NORTH SIDE OF IL-60 EAST OF THE FIELD DRIVE/SAUNDERS ROAD INTERSECTION (SEE SCHEDULE OF QUANTITIES - EARTHWORK SHEETS 3, 4, AND 5 OF 5 FOR A DETAILED BREAKDOWN OF THE ADDITIONAL EARTHWORK BALANCE QUANTITIES BY STAGE AND LOCATION).

REVISIONS NAME

ILLINOIS DEPARTMENT OF TRANSPORTATION ILLINOIS RTE 60 OVER I-94

SCHEDULE OF QUANTITIES IL RTE. 60 (TOWNLINE RD) EARTHWORK QUANTITIES - SHEET 1 OF 5

DRAWN BY: JDF 08/31/07 DATE: MAY 8, 2007

TYLININTERNATIONAL