STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION





SB-1 11-1-06

ALLEN HENDERSON & ASSOCIATES, INC.

CONSULTING CIVIL AND STRUCTURAL ENGINEERS SPRINGFIELD, IL. PHONE: (217) 544-8033 IL DESIGN FIRM NO. 184-001907

	ROUTE NO.	SECTION	COUNTY	TOTAL	SHEET NO.	
	F.A.P. 656	(1)1	TAZEWELL	32	29	SHEET NO. 18 OF 18 SHEETS
	FED. ROAD DIST. NO. 4		ILLINOIS FED. AID PROJECT			
CONTRACT NO. 68024						

When contilever forming brackets are used, the work shall be done according to Article 503.06(b) of the Standard Specifications, except

as modified below and in the details shown on this sheet. The finishing machine rails shall be placed on the top flange of the exterior beams.

The beams or girders, supporting cantilever forming brackets, shall be tied together at 4 foot intervals.

For Standard construction, or Stage Construction the Hardwood bracing materials shall be placed as shown between webs of beams in each bay.

