

F.A.I. SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74 72(7,8,9,9-1)LS	PEORIA	19	9
STA. TO STA.		FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT	

MOBILIZATION	
Jobsite	1 Lump Sum

TRAFFIC CONTROL AND PROTECTION	
Jobsite	1 Lump Sum

SUPPLEMENTAL WATERING				
Location	No. of Plants	Rate liters/plant	No. of Waterings	Units
Trees	194	38	5	36.86
Shrubs	7956	11	5	437.58
Perennials	1332 SQM	15 L/SQM	14	279.72
Vines	482	11	5	26.51
			Total	781

CARE OF PLANT MATERIALS			
Location	No. of Plants	No. of Care Cycles	Each
Tree Care	194	2	388
Shrub Care	7956	2	15912
Vine Care	482	2	964
Perennial Plant Care	1332 SQM	8	10653 SQM
Note: Perennial Plant Care will be measured by SQM.			

WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE				
Location	Appl. Rate (kg/SQM)	Area (SQ M)	No. of Appl.	Kilograms
Perennial Plant Beds	0.01	1332	3	40

FERTILIZER NUTRIENTS				
Location	Appl. Rate (kg/SQM)	Area (SQ M)	No. of Appl.	Kilograms
Perennial Plant Beds				
Nitrogen Fert. Nutr.	0.01	1332	1	13
Phosphorus Fert. Nutr.	0.006	1332	1	8
Potassium Fert. Nutr.	0.004	1332	1	5

PERENNIAL PLANTS, FOR SUN, 1/2 Gallon					
Forbs	Totals By Layout Sheet				Totals by Plant Name
	Sheet 1	Sheet 2	Sheet 3	Sheet 6	
Aster Laevis -Smooth Aster	0	0	0	0	0
Aster Novae angliae-New England Aster	0	0	0	0	0
Baptisia Leucantha - White Indigo	0	400	570	0	970
Echinacea Purpurea - Purple Coneflower	875		560	0	1435
Eupatorium Purpureum- Joe Pye Weed	500	570	0	0	1070
Helianthus Strumosus- Woodland Sunflower	0	0	500	0	500
Monarda Fistulosa- Wild Bergamont	0	0	0	0	0
Physostegia Virginiana-Obedient Plant	0	570	0	0	570
Rudbeckia Goldstrum- Goldstrum Brown Eyed Susan	303	993	0	0	1296
Silphium Integrefolium- Rosin Weed	875	0	370	0	1245
Silphium Laciniatum-Compass Plant		992	500	0	1492
Silphium Terebinthinaceum- Prairie Dock	300	820	745	0	1865
Solidago Speciosa - Showy Goldenrod	0	0	0	0	0
Vernonia Fasticulata- Ironweed	300	0	0	0	300
Veronicastrum Virginicum-Culvers Root	200	0	0	0	200
Grasses					
Andorpogon Scoparius- Little Bluestem	0	0	540	0	540
Sorghastrum Nutans-Indiangrass	0	400	260	0	660
Sporobulus Heterolepsis-Dropseed	0	720	1210	0	1930
Sub Total	3353	5465	5255	0	
Grand Total	14073 =140.73 UNITS				

NOTE: PERENNIAL PLANTS TO BE PLANTED IN LARGE GROUPINGS. LAYOUT TO BE DETERMINED BY LANDSCAPE ARCHITECT PRIOR TO PLANTING.

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION FAI ROUTE 74 ( I-74)
NAME	DATE	
PS&E RJD	04/18/07	SCHEDULE OF QUANTITIES
FINAL PLAN	05/11/04	
PREFINAL PLAN	03/01/04	
PRELIMINARY	11/17/03	
DATE: 07/16/2004		DRAWN BY: KC/DL
		CHECKED BY: JB