

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
①	②	SANGAMON	80	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
① FAP 666 & FAP 67				
② (ISP-2)RS-4; (1072)RS-8				

CODED PAYITEM	DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION CODE					
				ROADWAY NINTH ST	ROADWAY JEFFERSON ST	TRAFFIC SIGNALS NINTH ST - SEE NOTE 1	TRAFFIC SIGNALS NINTH ST - SEE NOTE 2	PARKING JEFFERSON ST	ADJUSTMENTS JEFFERSON ST
				80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 10% STATE / 10% CITY	50% STATE 50% CITY	100% CITY
				URBAN SANGAMON CO. 1000	URBAN SANGAMON CO. 1000	URBAN SANGAMON CO. Y031-1F	URBAN SANGAMON CO. Y031-1F	URBAN SANGAMON CO. Y025	URBAN SANGAMON CO. Y060
20800150	TRENCH BACKFILL	CU YD	3	3					
31100100	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	15	15					
35100100	AGGREGATE BASE COURSE, TYPE A - B	SQ YD	15	15					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	47.1	37.4	8.7			1.0	
40600300	AGGREGATE (PRIME COAT)	TON	72	72					
40600635	LEVELING BINDER (MACHINE METHOD), NTO	TON	3889	3889					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	4686	3130	1556				
40600990	TEMPORARY RAMP	SO YD	849	849					
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", NTO	TON	7697	5085	1295			218	299
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	380	290	98				
42000500	PORTLAND CEMENT CONCRETE PAVEMENT 10"	SO YD	67	67					
42101300	PROTECTIVE COAT	SO YD	211	211					
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT 8 INCH	SO YD	27	27					
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SO FT	1078	983	82		13		
42400800	DETECTABLE WARNINGS	SO FT	140	140					
44000100	PAVEMENT REMOVAL	SQ YD	15	15					
44000198	HOT-MIX SURFACE REMOVAL, VARIABLE DEPTH	SO YD	90,614	69,421	15,031			2604	3558
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	181	181					
44000600	SIDEWALK REMOVAL	SO FT	1154	1041	100		13		
44200164	PAVEMENT PATCHING, TYPE I, 14 INCH	SO YD	24	24					
44200168	PAVEMENT PATCHING, TYPE II, 14 INCH	SO YD	512	411	101				
44200172	PAVEMENT PATCHING, TYPE III, 14 INCH	SO YD	550	506	44				
44200174	PAVEMENT PATCHING, TYPE IV, 14 INCH	SO YD	785	601	184				
44213200	SAW CUTS	FOOT	50	50					
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	10	10					
56109210	WATER VALVES TO BE ADJUSTED	EACH	145	83					62
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	1	1					
60255500	MANHOLES TO BE ADJUSTED	EACH	138	70					68
60260100	INLETS TO BE ADJUSTED	EACH	1	1					
60260400	INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1					
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	105	105					
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	10	10					
* 66900450	SPECIAL WASTE PLANS AND REPORT	L SUM	1	1					
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	2	2					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	4.5	4.5				

NOTE 1: NINTH ST WITH INTERSECTIONS OF: MADISON, JEFFERSON, AND SOUTH GRAND
 NOTE 2: NINTH ST WITH INTERSECTIONS OF: CONVERSE, ENOS, CARPENTER, WASHINGTON, AND COOK
 * SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
 FAP 666 (I-55 BUSINESS LOOP-NINTH STREET)
 FAP 67 (IL 97/IL 29-JEFFERSON STREET)
 SCALE: VERT. DATE: DRAWN BY: CHECKED BY:

PLT DATE : DATE
 FILE NAME : DATE
 PLOT SCALE : DATE
 USER NAME : DATE

Rev.