1545 00 STA. 1+3 FED. ROAD

COUNTY 10% 0-8R DUPAGE 97 TO STA. 5+50.00

ILLINOIS FED. AID PROJECT CONTRACT 83961

GENERAL NOTES:

- THE CONTRACTOR SHALL MAINTAIN ALL ROADWAYS OPEN TO TRAFFIC AS SHOWN PER THE MAINTENANCE OF TRAFFIC DETAILS.
- BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL J.U.L.I.E. AT (800) 892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC. TELEPHONE. CABLE, AND GAS FACILITIES (48 HOURS NOTIFICATION IS REQUIRED).
- 3. THE CONTRACTOR SHALL NOT BE ALLOWED TO ERECT A YARD OR FIELD OFFICE ON CITY RIGHT-OF-WAY OR PROPERTY WITHOUT WRITTEN PERMISSION FROM THE CITY OF NAPERVILLE.
- THE ENGINEER SHALL BE THE SOLE JUDGE CONCERNING THE PROPER CURING TIME FOR THE VARIOUS HMA LIFTS.
- ALL ELEVATIONS REFER TO DUPAGE COUNTY DATUM (SEE SHEET 7).
- NO WORK SHALL COMMENCE UNTIL TRAFFIC CONTROL REQUIREMENTS AND EROSION CONTROL MEASURES ARE MET.
- ALL UTILITIES, SCHOOL DISTRICTS, PARK DISTRICT, LOCAL POLICE, AND FIRE DEPARTMENTS SHALL BE NOTIFIED BY THE CONTRACTOR PRIOR TO THE START OF CONSTRUCTION.
- UNLESS AUTHORIZED BY THE ENGINEER, ALL EXISTING ACCESS POINTS SHALL BE MAINTAINED AT ALL TIMES BY THE CONTRACTOR.
- BOXED ITEMS ARE INCLUDED IN THIS CONTRACT AND SHALL NOT BE PAID FOR SEPARATELY.
- TREES NOT MARKED FOR REMOVAL SHALL BE CONSIDERED AS DESIGNATED TO BE SAVED AND SHALL BE PROTECTED UNDER THE PROVISIONS OF ARTICLE 201.05 OF
- ALL LIMBS, BRANCHES, AND OTHER DEBRIS RESULTING FROM THIS WORK SHALL BE DISPOSED OF BY THE CONTRACTOR AT HIS OWN EXPENSE OUTSIDE THE LIMITS OF
- 12. ALL CLEARING, REMOVAL OF BUSHES, HEDGES AND TREES UNDER SIX (6) INCHES IN DIAMETER WILL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR EARTH EXCAVATION.
- 13. DURING THE CONSTRUCTION, THE CONTRACTOR WILL BE REQUIRED, AT HIS EXPENSE, TO HAVE AVAILABLE A WATER TRUCK OR SIMILAR EQUIPMENT TO CONTROL DUST. IF NECESSARY, THE CONTRACTOR SHALL BE REQUIRED TO CONTROL DUST DURING
- 14. THE CONTRACTOR MUST MAKE PRIOR ARRANGEMENTS WITH THE CITY OF NAPERVILLE WATER DEPARTMENT PRIOR TO THE USE OF ANY FIRE HYDRANT. HYDRANT METERS AND RPZ'S MUST BE USED. CONTACT THE ENGINEERING DEPARTMENT AT (630) 420-4122.
- 15. ALL OPEN EXCAVATIONS MUST BE ADEQUATELY COVERED (STEEL PLATED) OR FILLED IN AT THE END OF EACH DAY. NO OPEN EXCAVATIONS ARE ALLOWED OVERNIGHT. THE COST OF THIS WORK SHALL BE INCLUDED IN THE COST OF THE ITEM REQUIRING EXCAVATION.
- 16. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE REMOVAL AND CLEAN UP OF MUD AND OTHER DEBRIS TRACKED ON ALL STREETS LEADING TO THE PROJECT SITE CAUSED BY THE CONSTRUCTION OPERATIONS. THE CLEAN UP IS AT THE DISCRETION OF AND MUST BE DONE TO THE SATISFACTION OF THE CITY ENGINEER.
- 17. THE CONTRACTOR SHALL OBSERVE THE FOLLOWING WORKING HOURS:
 - WORK SHALL BE PERFORMED BETWEEN THE HOURS OF 7:00 AM AND 7:00 PM MONDAY THROUGH FRIDAY. WORK ON SATURDAYS SHALL BE LIMITED TO 8:00 AM
 TO 4:00 PM. NO WORK SHALL BE PERFORMED ON SUNDAYS OR THE FOLLOWING
 HOLIDAYS: NEW YEARS DAY, MEMORIAL DAY, 4th OF JULY, LABOR DAY, THANKSGIVING
 AND CHRISTMAS. ANY LANE CLOSURES ON WASHINGTON STREET SHALL BE LIMITED
 TO THE HOURS OF 9:00 AM TO 3:30 PM. ANY ADJUSTMENTS SHALL BE APPROVED
- 18. ALL TRENCHES, HOLES OR OTHER EXCAVATIONS REQUIRED FOR UTILITY INSTALLATION ALL TRENCHES, HOLES ON OTHER EXCAVATIONS REQUIRED FOR STILLING THE SHOULD BE BACK-FILLED, STABILIZED AT THE END OF EACH WORKING DAY. NO EXCAVATION SHOULD BE OPENED MORE THAN WHAT CAN BE STABILIZED BY THE END OF THE SAME DAY. IF AN EXCAVATION MUST BE LEFT UNSTABILIZED OR OPENED OVERNIGHT, SOIL EROSION AND SAFETY PROTECTION MEASURES SHALL BE INSTALLED.
- 19. ALL WASTE GENERATED AS A RESULT OF CONSTRUCTION ACTIVITIES (CONCRETE TRUCK WASHOUT, CHEMICALS, LITTER, SANITARY WASTE OR ANY OTHER WASTE) SHALL BE PROPERLY DISPOSED OF AND BE PREVENTED FROM BEING CARRIED OFF THE SITE BY EITHER WIND OR

INDEX OF STATE STANDARDS

0

STD. NO. 000001-04	TITLE STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS	SHEET	NO.	SHEET TITLE COVER SHEET
280001-03	TEMPORARY EROSION CONTROL SYSTEM	-		
424001-04	CURB RAMPS FOR SIDEWALKS	2		GENERAL NOTES, INDEX OF STATE STANDARDS, & INDEX OF SHEETS
442101-06	CLASS B PATCHES	3	- 5	SUMMARY OF QUANTITIES
442201-02	CLASS C AND D PATCHES	6		SCHEDULES OF QUANTITIES
515001-02	NAME PLATE FOR BRIDGES	7		EXISTING AND PROPOSED TYPICAL SECTIONS
542301-01	PRECAST REINFORCED CONCRETE FLARED END SECTION	8		ALIGNMENT AND SURVEY TIES FOR CONTROL POINTS
601101-00	CONCRETE HEADWALL FOR PIPE DRAIN	9		PLATS OF TEMPORARY EASEMENT (FOR INFORMATION ONLY)
602001-00	CATCH BASIN, TYPE A			
602401-0.1	MANHOLE, TYPE A	10	- 13	MAINTENANCE OF TRAFFIC PLANS
602701-0	CAST IRON STEPS	14		REMOVAL PLAN AND EXISTING UTILITIES
604001-02	FRAME AND LIDS, TYPE 1	15		PROPOSED PLAN AND PROFILE
604051-02	FRAME AND GRATE, TYPE 11	16	- 17	EXISTING AND PROPOSED DRAINAGE PLANS AND DETAILS
630001-07	STEEL PLATE BEAM GUARDRAIL	18		EROSION CONTROL PLANS
631031-06	TRAFFIC BARRIER TERMINAL, TYPE 6	19		PROPOSED GRADING PLANS
667101	PERMANENT SURVEY MARKERS			
701501-03	URBAN LANE CLOSURE, 2 LANE, 2 WAY, UNDIVIDED	20		PAVEMENT MARKING & SIGNING PLANS/LANDSCAPING PLANS
701606-04	URBAN LANE CLOSURE, MULTILANE, 2 WAY WITH MOUNTABLE MEDIAN	21		MISCELLANEOUS DETAILS
701701-04	URBAN LANE CLOSURE, MULTILANE INTERSECTION		BRIDGE PLANS	
701801-03	LANE CLOSURE MULTILANE 1W OR 2W CROSSWALK OR SIDEWALK CLOSURE	22	- 60	PROPOSED PLANS (SN 022-3028)
702001-06	TRAFFIC CONTROL DEVICES	61	- 66	EXISTING PLANS (FOR INFORMATION ONLY)
704001-03	TEMPORARY CONCRETE BARRIER			ELECTRICAL PLANS
720001-00	SIGN PANEL MOUNTING DETAILS	67	- 89	CITY OF NAPERVILLE (DPU-E)
720006-01	SIGN PANEL ERECTION DETAILS	90		BD-01, DRIVEWAY DETAILS
720011-00	METAL POSTS FOR SIGNS, MARKERS & DELINEATORS	91		BD-07, DETAIL OF STORM SEWER CONNECTION TO EXISTING SEWER
729001-00	APPLICATION OF TYPE A AND TYPE B METAL POSTS	92		BD-32, BUTT JOINT AND HMA TAPER DETAILS
780001-01	TYPICAL PAVEMENT MARKINGS	93		
BLR 23-1	TRAFFIC BARRIER TERMINAL, TYPE 1			TC-13, DISTRICT ONE TYPICAL PAVEMENT MARKINGS
		94	- 95	SOIL BORINGS
		96	- 97	ROADWAY CROSS SECTIONS

REVISION	IS .	BRIDGE REHABILITATION
NAME	BATE	BAILEY ROAD OVER
		WEST BRANCH OF THE DUPAGE RIVER
		GENERAL NOTES.
		INDEX OF STATE STANDARDS.
		& INDEX OF SHEETS
		or index of officero

City of Naperville DRAWN: RTM

CHECKED: SP APPROVED: DATE: JULY 13, 2007 SCALE: NONE JOB NO.: C-91-062-04 PROJECT NO. BHM-8003(343)

TYLININTERNATIONAL

INDEX OF SHEETS