PROPOSED ELECTRIC CONSTRUCTION ALONG BAILEY RD. (DUPAGE COUNTY) BETWEEN WASHINGTON ST. AND COACH DR. AT THE DUPAGE RIVER IN THE CITY OF NAPERVILLE, STATE OF ILLINOIS

F.A.U. RTE.	SECTI	ON	COUNTY	TOTAL SHEETS	SHEET NO		
1545	00-00115	5-00-BR	DUPAGE	17	68		
STA. 1+31.77 TO STA. 5+50.00							
FED. ROAD DIST. NO. ILLINOIS			FED. AID PROJECT				

CONTRACT 83961

GENERAL NOTES (CONTINUED)

- 17) THE CONTRACTOR SHALL PROVIDE TIME DURING CONSTRUCTION 17) THE CONTRACTOR SHALL PROVIDE TIME DURING CONSTRUCTION OPERATIONS FOR THE LANDSCAPER TO REMOVE, PRESERVE, AND REINSTALL ANY BUSH OR SIRVUB. BUSHES, SIRVUBS, VINES, AND SEEDINGS SHALL BE DUG UP WITH CARE, AVOIDING INJURY TO THE PLANTS OR LOSS OR DAMAGE OF THE ROOTS. IMMEDIATELY AFTER DIGGING, ROOTS SHALL BE PROTECTED AGAINST DRYING OUT AND FREEZING BY WRAPPING ROOT SYSTEM IN BURILAP, REMOVED VEGETATION SHALL BE PLACED IN TEMPORARY STORAGE EITHER ON SITE OR AT OTHER APPROVED LOCATIONS. IF LANDSCAPER IS UNABLE TO REUSE EXISTING VEGETATION, HE SHALL REPLACE WITH SAME SIZE AND SPECIES AT HIS OWN EXPENSE. COST OF THIS WORK SHALL NOT BE PAID FOR SEPARATELY BUT SHALL BE CONSIDERED INCIDENTAL TO THE LANDSCAPING CONTRACT AND IS PART OF THE RESTORATION.
- 18) DURING CONSTRUCTION OPERATIONS, THE CONTRACTOR IS NOT ALLOWED TO PERMANENTLY STOCK PILE MATERIAL ON SITE. CONTRACTOR SHALL SUPPLY LIGHTED BARRICADES AROUND ALL STOCKPILES AND IS RESPONSIBLE FOR THE SECURITY OF ALL THE MATERIALS STORED OFF SITE.
- 19) ALL RESTORATION IS DIRECTED BY THE CITY PERMIT WHICH THE CONTRACTOR IS REQUIRED TO OBTAIN PRIOR TO STARTING WORK. ALL REQUESTS REQUIRED BY THE CITY SHALL BE HONORED AND COMPLETED BY THE LANDSCAPER AT NO EXPENSE TO THE CITY. THE LANDSCAPE CONTRACTOR SHALL PERFORM ALL RESTORATION PER CITY OF NAPERVILLE SPECIFICATIONS. THE CONTRACTOR SHALL PERFORM ALL WORK TO THE MOST RESTRICTIVE REQUIREMENT OF THE GOVERNING BODIES. THIS IS PART OF THE RESTORATION PRICE.
- 20) ALL IDENTIFIED OR SUSPECTED UNDERGROUND FACILITIES OR OBSTRUCTIONS SHALL BE LOCATED BY HAND DIGGING TO A DEPTH OF 8 FRET, WIDTH OF 4 FEET AND LENGTH OF 5 FEET AND IDENTIFIED
- 21) WHEN REPAIRING, REPLACING, OR INSTALLING ITEMS, THE ITEMS SUPPLIED BY THE CONTRACTOR SHALL BE NEW AND NOT USED.

- 22) THE COST TO LOCATE SUPPORT, MOVE AND PROTECT THE UTILITIES (SHOWN ON THE DRAWINGS) SHALL NOT BE PAID FOR SEPARATELY BUT SHALL BE CONSIDERED INCIDENTAL TO WORK.
- 23) ALL MATERIALS REMOVED DURING THE CONSTRUCTION OF THE PROJECT AND DESIGNATED ON THE PLANS OR BY THE CITY AS SALVAGED MATERIALS SHALL BE REMOVED, CLEANED, AND STACKED AT THE DESIGNATED CITY OF NAPERVILLE SITE. ALL UNUSED MATERIALS SHALL BE THE PROPERTY OF THE CITY.
- 24) AIL MATERIALS REMOVED BY THE CONTRACTOR, SUCH AS POLES, WIRE, STEEL POLES, FOUNDATIONS, ANCHORS, GUYS, CROSS ARMS, INSULATOR GROUND WIRES, CONDUCTORS, AND HARDWARE AND DESIGNATED ON THE PLAN FOR REMOVAL SHALL BE REMOVED TO AN APPROPRIATE DUMP SITE FOR WASTE. DUMP TICKETS RECEIVED AND RETURNED TO THE CITY, ALL ARRAS LEFT DAMAGED BY THE REMOVAL SHALL BE REPAIRED, REPLACED OR INSTALLED TO ROUGH GRADE.
- 25) THE CITY OF NAPERVILLE DOES NOT GUARANTEE A SEQUENCE OF WORK OR AVAILABILITY OF THE WORK AREA OR QUANTITY OF WORK.
- 26) ALL WORK WILL OCCUR DURING AIL 4 SEASONS OF THE YEAR. THEREFORE, THERE SHALL BE NO COMPENSATION PAID BY THE CITY FOR SNOW, ICE, RAIN, WIND, OR HOT OR COLD WEATHER, IT IS ASSUMED THE CONTRACTOR HAS INCLUDED THESE ITEMS IN THE DEVINIOR.
- 27) THE CONTRACTOR IS ADVISED THAT JOINTED, FISSURED ROCK, LARGE BOULDERS (12 INCHES OR LARGER) AND VERY TOUGH LARGE BOULDERS (12 INCHES OR LARGER) AND VERY TOUGH
 STRATIFIED ROCK/EHALE EXISTS FROM 1'-0" TO 5'-0" BELOW GRADE
 AND SOLID ROCK EXISTS FROM 5'-0" TO 20'-0" BELOW GRADE AND
 REQUIRES ADDITIONAL WORK AND IS INCLUDED IN THE COST OF
 INSTALLING THE DUCT BANK OR HAND HOLE WORK OR RISER WORK.
 THE CONTRACTOR WILL EXCAVATE IN ROCK ACCORDING TO SECTION
 502 OF THE STANDARD SPECIFICATIONS FOR ROCK EXCAVATION FOR
 STRUCTURES. THE BOTTOM OF THE TRENCH SHALL BE LINED WITH 2
 INCHES OF FAZ MATERIALS OR CA-6 MATERIALS TO FROM A BEDDING
 FOR THE DUCT PACKAGE AND IS INCIDENTAL TO THE COST. THE DUCT PACKAGE AND IS INCIDENTAL TO THE COST.
- 28) THE CONTRACTOR SHALL COORDINATE AND PERFORM ALL WORK OR 8) THE CONTRACTOR SHALL COORDINATE AND PERFORM ALL WORK OR AS MUCH AS POSSIBLE USING TRAFFIC CONTROL AND LANE CLOSURES AS REQUIRED FOR THE BRIDGE WORK. ALL ELECTRICAL WORK REQUIRING A LANE CLOSURE OR TRAFFIC CONTROL SHALL ONLY BE ACCEPTED IF THE BRIDGE WORK IS NOT INVOLVED. THE CONTRACTOR TO INCLUDE THESE COSTS UNDER THE TRAFFIC CONTROL PAY ITEM.
- 29) THE CONTRACTOR SHALL, DURING THE PROGRESS OF THE JOB, NOTE ANY AND ALL CHANGES OR DEVIATIONS FROM THE ORIGINAL DRAWING. THE CONTRACTOR SHALL PROVIDE THE ENGINEER WITH A COPY OF ALL RECORDED DIMENSIONS AND ELEVATIONS. ALL MANHOLES, HAND HOLES VAULTS OR RISERS, BENDS AND FITTINGS, SHALL BE TIED TO A MINIMUM OF TWO PERMANENT VISIBLE POINTS (i.e. PROPERTY IRONS AND BUILDINGS). DEVIATIONS FROM CHANGES IN GRADE SHALL ALSO BE NOTED ON THE RECORD DRAWINGS.
- 30) WATER MAIN VALVES, INCLUDING TAP VALVES, ADJACENT TO AN EXISTING WATER MAIN, AND EXISTING WATER MAIN VALVES SHALL ONLY BE OPERATED BY THE CITY OF NAPERVILLE, DEPARTMENT OF PUBLIC UTILITIES CEE/CM DIVISION PERSONNEL WITH 48-HOURS NOTICE (MONDAY-FRIDAY) 630-420-4122.

UTILITY CONTACTS:

CITY OF NAPERVILLE:

NDPU-WATER AND WASTEWATER

MR. PAT EYRE (630) 420-4122

ELECTRIC
MRS. LUCY HYNES NDPU-(630) 305~5375

PUBLIC WORKS MR. DAN VORREN NDPW-(630) 548-2981

TRANSPORTATION, ENGINEERING & DEVELOPMENT BUSINESS GROUP MR. BILL NOVAK TED-

(630) 420-6704

OTHER UTILITIES:

MR. GREG LAWERANCE AMERITECH AT&T-(630) 462-5846 MS. DONNA SZPYTEK

(630) 941-4223

(630) 723-2303

COMCAST-MR. BOB SCHULTER (830) 600-6347

COMMONWEALTH MR. LYNN CHRISTENSON


NICOR GAS-MS. CONSTANCE LANE

(630) 983-8676 X3830

WIDE OPEN WEST-MR. TOM JEBENS (630) 536-3153 MR. JIM PIRTANO

(630) 669-2707

DUPAGE COUNTY MR. ROBERT KOLARS PERMIT 401 N. COUNTY FARM RD. ADMINISTRATOR— WHEATON, IL 60187



CITY OF NAPERVILLE/DEPARTMENT OF PUBLIC UTILITIES — ELECTRIC									
		CAL	L J.U.Lil.	E. 48 HRS.	PRIOR TO CO	NSTF	JCTION		
BAILE	Y RD	. BRID	SE DUC	CTBANK IN	ISTALLATION	20	64/1323	CAD FILE JONE DOSE199001C2_DW	
PROJECT D				IDGE IMPRO		(PAGE)	JK	PROJECT NO. EU12-06-0	
DATE	66-15 07			WAX MIGLEST NO.	CHIC	98C:		COMPLETED IN:	
IGBUED ENGNEER	RP8			58199	APRIL .	SOAL	NTS	SHEET 2 OF 2	