

MUNICIPALITY	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
QUINCY	06-00300-00-LS	ADAMS	69	4

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

	ITEM	UNIT	TOTAL	CONSTRUCTION TYPE CODE	CONSTRUCTION TYPE CODE	CONSTRUCTION TYPE CODE
				I000	Y030 (2)	Y031 (2)
	20100110 TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	216	216		
	20100210 TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	72	72		
	20800150 TRENCH BACKFILL	CU YD	200	200		
	31101200 SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	1028	1028		
	35301100 HIGH-EARLY-STRENGTH PORTLAND CEMENT CONCRETE BASE COURSE 8"	SQ YD	97	97		
	35400300 PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 8"	SQ YD	470	470		
(1)	40600200 BITUMINOUS MATERIALS (PRIME COAT)	TON	0.9	0.9		
(1)	40600300 AGGREGATE (PRIME COAT)	TON	38	38		
(1)	40600625 LEVELING BINDER (MACHINE METHOD), N50	TON	571	571		
(1)	40600982 HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	567	567		
(1)	40600990 TEMPORARY RAMP	SQ YD	479	479		
(1)	40603335 HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	1296	1296		
	42300200 PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	87	87		
	42400100 PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	32107	32107		
	42400440* PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH, SPECIAL	SQ FT	480	480		
	42400800* DETECTABLE WARNINGS	SQ FT	152	152		
(1)	44000198* HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	16645	16645		
	44000200 DRIVEWAY PAVEMENT REMOVAL	SQ YD	103	103		
	44000300 CURB REMOVAL	FOOT	1623	1623		
	* SEE SPECIAL PROVISIONS					

(1) NON-PARTICIPATING ITEM FOR TRANSPORTATION ENHANCEMENT FUNDING

(2) SPECIALTY ITEMS

SUMMARY OF QUANTITIES
SHEET 1 OF 7