

MUNICIPALITY	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
QUINCY	06-00300-00-LS	ADAMS	69	16

CIRCUIT I - 240 VOLT	PVC CONDUIT 2" IN TRENCH	PVC CONDUIT 2" AUGERED	USE EXISTING CONDUIT	EL CABLE 4 WIRES #8 - 1C	ORNAMENTAL LIGHT POLE	150 WATT HPS LUMINAIRE	EL CABLE 5 WIRES #12 - 1C	CONCRETE FOUNDATION	JUNCTION BOX	TRENCH & BACKFILL
	FOOT	FOOT		FOOT	EACH	EACH	FOOT	FOOT	EACH	FOOT
NORTH SIDE OF MAINE STREET - 4TH TO 5TH										
PULL ELECTRIC CABLE FROM EXISTING LIGHTS EL4 AND EL5 TO PARK JUNCTION BOX										
PULL ELECTRIC CABLE FROM JOHN WOOD STATUE ACCENT LIGHTS TO PARK JUNCTION BOX										
INSTALL JUNCTION BOX 1 AND 2 ON EXISTING CONDUIT									2	
SPLICE ON EXISTING CIRCUIT AT PARK JUNCTION BOX										
PARK JUNCTION BOX TO JB 2			X	52						
JB 2				6						
JB 2 TO LIGHT 2	5			20						5
LIGHT 2				12	1	1	85	3		
JB 2 TO JB 1			X	244						
JB 1				6						
JB 1 TO LIGHT 1	5			20						5
LIGHT 1				12	1	1	85	3		
JB 1 TO PARK HANDHOLE			X	244						
PARK HANDHOLE				26						
SPLICE AT PARK HANDHOLE TO JB EL 4			X	36						
JB EL 4				6						
JB EL4 TO LIGHT EL 4			X	20						
LIGHT EL4				12						
SPLICE AT PARK HANDHOLE TO JB 5			X	400						
JB 5				6						
JB 5 TO LIGHT EL 5			X	20						
LIGHT EL5				12						
REINSTALL ELECTRIC CABLE FROM PARK JUNCTION BOX TO JOHN WOOD STATUE ACCENT LIGHTS										
CUT CIRCUIT TO 5TH STREET LIGHTS AT HH 2										
PULL ELECTRIC CABLE FROM HH 2 TO PARK JB										
INSTALL JUNCTION BOX 3, 4 AND 5 ON EXISTING CONDUIT									3	
SPLICE AT PARK JUNCTION BOX TO JB 3			X	220						
JB 3				6						
JB 3 TO LIGHT 3		14		56						
LIGHT 3				12	1	1	85	3		
JB 3 TO JB 4			X	252						
JB 4				6						
JB 4 TO LIGHT 4		14		56						
LIGHT 4				12	1	1	85	3		
JB 4 TO JB 5			X	208						
JB 5				6						
JB 5 TO LIGHT 5		14		56						
LIGHT 5				12	1	1	85	3		
REINSTALL ELECTRIC CABLE TO 5TH STREET FROM PARK JUNCTION BOX TO HH 2										
SPLICE BACK TO 5TH STREET LIGHT CIRCUIT										
TOTALS	10	42		2056	5	5	425	15	5	10

CIRCUIT II - 208 VOLT	PVC CONDUIT 2" IN TRENCH	PVC CONDUIT 2" AUGERED	USE EXISTING CONDUIT	EL CABLE 5 WIRES #6 - 1C	ORNAMENTAL LIGHT POLE	150 WATT HPS LUMINAIRE	EL CABLE 5 WIRES #12 - 1C	CONCRETE FOUNDATION	JUNCTION BOX	TRENCH & BACKFILL
	FOOT	FOOT		FOOT	EACH	EACH	FOOT	FOOT	EACH	FOOT
SOUTH SIDE OF MAINE STREET - 4TH TO 5TH										
SPLICE TO EXISTING CIRCUIT - EL 8 ON SERVICE B			X	375						
STUB END OF EXISTING CONDUIT TO JB 9	20			100					1	20
JB 9				7.5						
JB 9 TO LIGHT 9	5			25						5
LIGHT 9				15	1	1	85	3		
JB 9 TO JB 8	77			385						77
JB 8				7.5					1	
JB 8 TO LIGHT 8	5			25						5
LIGHT 8				15	1	1	85	3		
JB 8 TO JB 7	66			330						66
JB 7				7.5					1	
JB 7 TO LIGHT 7	5			25						5
LIGHT 7				15	1	1	85	3		
JB 7 TO JB 6	74			370						74
JB 6				7.5					1	
JB 6 TO LIGHT 6	5			25						5
LIGHT 6				15	1	1	85	3		
TOTALS	257			1750	4	4	340	12	4	257

SCHEDULE OF QUANTITIES  
SHEET 6 OF 15