

MUNICIPALITY	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
QUINCY	06-00300-00-LS	ADAMS	69	17

CIRCUIT III - 240 VOLT	PVC CONDUIT 2" IN TRENCH	PVC CONDUIT 2" AUGERED	USE EXISTING CONDUIT	EL CABLE 4 WIRES #8 - 1C	ORNAMENTAL LIGHT POLE	150 WATT HPS LUMINAIRE	EL CABLE 5 WIRES #12 - 1C	CONCRETE FOUNDATION	JUNCTION BOX	TRENCH & BACKFILL
NORTH SIDE OF MAINE STREET - 5TH TO 6TH	FOOT	FOOT		FOOT	EACH	EACH	FOOT	FOOT	EACH	FOOT
SERVICE BOX C TO LOT G HANDHOLE			X	80						
LOT G HANDHOLE TO HH 9			X	640						
HH 9				26						
SPLICE AT HH 9 - TO JB 20	27	30		184						27
JB 20				6					1	
JB 20 TO LIGHT 20	5			20	1	1	85	3		5
LIGHT 20				12						
JB 20 TO JB 19	66			264						66
JB 19				6					1	
JB 19 TO LIGHT 19	5			20						5
LIGHT 19				12						
JB 19 TO JB 18	59			236	1	1	85	3		59
JB 18				6					1	
JB 18 TO LIGHT 18	5			20						5
LIGHT 18				12	1	1	85	3		
JB 18 TO HH 10	24			96						24
HH 10				26						
HH 10 TO JB 17	46			184						46
JB 17				6					1	
JB 17 TO LIGHT 17	5			20						5
LIGHT 17				12	1	1	85	3		
JB 17 TO EXISTING CONDUIT WEST SIDE 6TH STR	12									12
PLACE JUNCTION BOX AT EXISTING CONDUIT									1	
SPLICE AT HH 9 - TO JB 21	14			56						14
JB 21				6					1	
JB 21 TO LIGHT 21	5			20						5
LIGHT 21				12	1	1	85	3		
JB 21 TO JB 22	67			268						67
JB 22				6					1	
JB 22 TO LIGHT 22	5			20						5
LIGHT 22				12	1	1	85	3		
JB 22 TO JB 23	70			280						70
JB 23				6					1	
JB 23 TO LIGHT 23	5			20						5
LIGHT 23				12	1	1	85	3		
JB 23 TO JB 24	52			208						52
JB 24				6					1	
JB 24 TO LIGHT 24	5			20						5
LIGHT 24				12	1	1	85	3		
TOTALS	477	30		2852	8	8	680	24	9	477

CIRCUIT IV - 240 VOLTS	PVC CONDUIT 2" IN TRENCH	PVC CONDUIT 2" AUGERED	USE EXISTING CONDUIT	EL CABLE 4 WIRES #8 - 1C	ORNAMENTAL LIGHT POLE	150 WATT HPS LUMINAIRE	EL CABLE 5 WIRES #12 - 1C	CONCRETE FOUNDATION	CONCRETE FOUNDATIONS (SPECIAL)	JUNCTION BOX
SOUTH SIDE OF MAINE STREET - 5TH TO 6TH	FOOT	FOOT		FOOT	EACH	EACH	FOOT	FOOT	EACH	EACH
SERVICE BOX C TO LOT G HANDHOLE			X	80						
LOT G HANDHOLE TO HH 9			X	640						
HH 9				26						
HH 9 TO HH 12			X	256						
HH 12				26						
SPLICE AT HH 12 - TO JB 12	43			172						
JB 12				6						1
JB 12 TO LIGHT 12	5			20	1	1	85	3		
LIGHT 12				12						
JB 12 TO JB 11	68			272						
JB 11				6						1
JB 11 TO LIGHT 11	5			20						
LIGHT 11				12	1	1	85	3		
JB 11 TO JB 10	69			276						
JB 10				6						1
JB 10 TO LIGHT 10	5			20						
LIGHT 10				12	1	1	85		1	
SPLICE AT HH12 - TO JB 13	21			84						
JB 13				6						1
JB 13 TO LIGHT 13	5			20						
LIGHT 13				12	1	1	85	3		
JB 13 TO JB 14	69			276						
JB 14				6						1
JB 14 TO LIGHT 14	5			20						
LIGHT 14				12	1	1	85	3		
JB 14 TO JB 15	61			244						
JB 15				6						1
JB 15 TO LIGHT 15	5			20						
LIGHT 15				12	1	1	85	3		
JB 15 TO HH 11	45			180						
HH 11				26						
HH 11 TO JB 16	15			60						
JB 16				6						1
JB 16 TO LIGHT 16	5			20						
LIGHT 16				12	1	1	85	3		
TOTALS	426			2884	7	7	595	18	1	7

SCHEDULE OF QUANTITIES
SHEET 7 OF 15