CONTRACT NO. 93447

| MUNICIPALITY | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| QUINCY | 06-00300-00-LS | ADAMS | 69 | 31 |

BC - BEGIN CURB
EC - END CURB

THIS PAGE: HDS 259 | LB 208 | PC 0.2 | APC 8 | HSR 3699 | ASB 94

MATCH LINE

VILORIA (601) — SR 2272 / S4 1278 / BP 619

VILORIA (607-611)

OMEGA TRUST (613)

MORRIS (615)

MORRIS (619)

METER PIT LID TO REMAIN

CDR 29 / CDP 26

WILLIAMS (625) — SR 2168 / S4 1351 / BP 621

FIRST BANK (635)

FIRST BANK (637) — SR 253 / S4 178 / BP 78

EX ROW

PROP TCE 12' WIDE

BENCHMARK
7TH AND MAINE
ELEV 604.70
HYDRANT NW CORNER
CHISLED "+"
ON SE BOLT

ST BONIFACE CHURCH (641) — SR 1811 / S4 1462 / BP 347

REPLACE CURBS @ EACH CORNER OF INTERSECTION

0 20 40 60 80 100 FEET

N

7TH STREET

GRIESBAUM (701) — SR 148 / S4 151

14.5' R TO FC

19.8' / 55.3' LT / 19.8'

CB 33 / CR 33

CR 25 / CB 25

CR 24

15' R TO FC

17.9' RT / 46.9' / 17.9'

EX ROW FREIBURG 700-702 — SR 221 / S4 223 / CB 24

33.00'

66.00'

+84.31 | +15.95 | +32.84 | +00.28 | +26.46 | +23.95 | +21.66 | +53.57 | +86.10 | +94.71

±2.5' | ±11.9' | ±11.83' | ±2.8'

EXISTING CURB TO REMAIN

DRIVE TO REMAIN

DRIVE TO REMAIN

EXISTING CURB TO REMAIN

MAINE STREET
FAUS RT 7807

PGT Sta 100+00.00

CB 69 / CBW8" 39 / CR 72

CB 100 / CBW8" 55 / CR 102

BC 602.33 / EC 602.88

BC 602.26 / EC 602.88

21 | 22 | 23 | 24 | 25+00 | 26

82.50' | 52' FC-FC | 52' FC-FC

17" | 10" | 19" | 11" | 17" | 14"

DOLLAR GENERAL (600)

DAVIS (606)

TOWN & COUNTRY BANK (610)

TAYLOR (614-618) — SR 3346 / S4 1979 / BP 976

EX ROW

NOTE:
350 EXTRA SQUARE FEET OF 4" SIDEWALK QUANTITY INCLUDED ON THIS PAGE FOR USE IN REOVING AND REPLACING VARIOUS BROKEN SLABS OF SIDEWALK MARKED TO REMAIN

+05.63 SPRINGFIELD CATHOLIC DIOCESE (620)

SCHLUETER (622)

REMOVE EXISTING STRUCTURE (CONCRETE LANDSCAPE PLANTER) 1 EACH

SEE PLAN & PROFILE SHEET 38 FOR PEDESTRIAN WALKWAY DETAILS

ABBOT (626)

RIDDERS (628)

RIDDERS (632) — SR 3014 / S4 1870 / BP 923

REMOVE EXISTING STRUCTURE (CONCRETE LANDSCAPE PLANTER) 1 EACH

NEEDHAM (634)

HOLTHAUS (636)

HOLTSCHLAG (638)

ERICSON (640)

NEEDHAM (642)

NEEDHAM (644)

FISK (646)

FISK (648) — SR 363 / S4 363 / CB 33

REFER TO SEWER CONSRUCTION DETAIL SHEET 38 FOR INLET WORK ON NW CORNER 7TH & MAINE

STA 21+00

STA 27+00

PLAN: SURVEYED | PLOTTED | FIELD CHECKED | ALL INFO. CHECKED | DRAWN | CADD FILE NAME | NOTE BOOK | NO. | BY | DATE

PROFILE: SURVEYED | PLOTTED | FIELD CHECKED | ALL NOTED | STRUCTURE NOTATNS CHKD | NOTE BOOK | NO. | BY | DATE

610 / 608 / 606 / 604 / 602 / 600 / 598 / 596 / 594

HOT-MIX ASPHALT SURFACE REMOVAL- 2 1/4 INCH AVE NEW 1 1/4" SURFACE AND 1" LEVELING BINDER

HOT-MIX ASPHALT SURFACE REMOVAL- 1 1/4 INCH AVE NEW 1 1/4" SURFACE

PROPOSED ℄ =
EXISTING ℄

LIMIT OF HOT-MIX ASPHALT SURFACE REMOVAL

EXISTING
PROPOSED

602.06 602.06 | 601.76 601.76 | 602.00 602.00 | 602.21 602.21 | 602.56 602.56 | 602.69 602.69 | 603.11 603.11 | 602.92 602.92 | 602.98 602.98 | 602.23 602.23 | 601.96 601.96 | 601.62 601.62 | 601.36 601.36

21+00 | 21+50 | 22+00 | 22+50 | 23+00 | 23+50 | 24+00 | 24+50 | 25+00 | 25+50 | 26+00 | 26+50 | 27+00

PLOT DATE = 8/7/2007
FILE NAME = plan&profile.dgn
PLOT SCALE = 20.0000 ' / IN.
USER NAME = default