FA-RTE SECTION COUNTY TOTAL SHEET NO 03-00026-90-PK MADISON 33 18

EXIST. CONC. E.J. (SEE PLAN) - \mathbb{R}^2_8 X12X28" W/ $8-\frac{3}{4}$ " ϕ A307 ANCHORS DRILL & INSTALL W/ EPOXY PER GEN. NOTES W/ MIN. $6\frac{3}{4}$ " EMBED. DRILL HOLE TO MISS EXIST. REINF. 8" PRECAST HOLLOW CORE SLAB BY PRECAST MANUF. (NOT IN PHASE 2B) REF. DETAIL 3.1C FOR BALANCE OF INFORMATION 2—TEFLON BRG. PAD — 3/32X5X111
(ETCHED 1 SIDE) COMPOSED OF
GLASS—FILLED VIROIN TFE RESIN,
TESTED PER ASTM D 1457 BRG.
PAD SHALL BE BONDED TO BACK—UP
STEEL IN SHOP USING AN EPOXY
SUITABLE FOR SERVICE CONDITIONS. PRECAST BEAM BY
PRECASET MANUF,
(SEE PLAN FOR SIZE
& LOCATION) 3"STIFF. PL (2-THUS) <u>3.2F</u> 3"=1′−0 3.2E 3"=1'-0

211 N. Broadway Suite 1900 St. Louis, MO 63102 (314) 241-8188 FAX (314) 241-0125

phase 2B Lewis and clark memorial tower Village of Hartford, illinois Hartford, illnois 62049

DETAILS ంర

SECTIONS

IBBUE DATE 03-JUNE-05

SHEET NO S3.2B

KENNEDY PROJECT NO KAI: 10-02048

SSE PROJECT NO: 02111 PHASE 2B