


PORTABLE CLOSED RUNWAY MARKER DETAIL AND NOTES

- 1. THE AIRPORT WILL PROVIDE PORTABLE LIGHTED CLOSURE MARKERS FOR THE CONTRACTOR'S USE.
- 2. THE CONTRACTOR WILL BE REQUIRED TO TOW AND SET UP THE MARKERS AT THE ENDS OF THE RUNWAY WHENEVER RUNWAY CLOSURES ARE
- 3. THE CONTRACTOR WILL BE REQUIRED TO PROVIDE REPLACEMENT BULBS, FUEL AND DAILY/PERIODIC MANTENANCE INSPECTIONS AS REQUIRED BY THE
- 4. THE AIRPORT WILL PERFORM PERIODIC MAINTENANCE, PROVIDE REPLACEMENT PARTS AND PERFORM REPAIRS AS REQUIRED TO KEEP THE EQUIPMENT OPERATIONAL.
- 5. THE COST OF SET-UP, FUELING AND REMOVAL OF THE MARKERS SHALL BE INCIDENTAL TO THE
- 6. MARKERS SHALL BE PLACED OVER EXISTING RUNWAY NUMERALS. HOWEVER, WHEN WORK IS NECESSARY FOR THAT AREA OR PAVEMENT IS OPEN TO TAXIING AIRCRAFT, THE MARKERS SHALL BE RELOCATED OFF THE PAVEMENT AS SHOWN ON THE DETAIL.




FLASHER BARRICADE DETAIL

N.T.S.

FLASHER BARRICADE NOTES

- FLASHERS TO BE BATTERY OPERATED. LENS TO BE RED AND BE ABLE TO ROTATE 90 DEGREES.
- 2. SANDBAGS TO BE PLACED ON EACH SUPPORT BRACE AS REQUIRED TO PREVENT DISPLACEMENT BY WIND, JET OR
- 3. NO SEPARATE PAYMENT WILL BE MADE FOR THIS ITEM. COSTS SHALL BE CONSIDERED INCIDENTAL TO THE PROJECT.
- 4. PLACE AT 20' INTERVALS.



CONSTRUCTION SETBACK LINE DETAIL

REVISIONS BY THIS BAR IS EQUAL TO 2" AT FULL SCALE (34X22). **ACTIVITY PLAN DETAILS** SPRINGFIELD AIRPORT AUTHORITY ABRAHAM LINCOLN CAPITAL AIRPORT SPRINGFIELD, ILLINOIS CONSTRUCTION RLV СМТ RIN CHECKED BY: RIN APPROVED BY: AUGUST 07, 2007 JOB No: 07035-02-00 IL. PROJ. NO. SPI-3711 AIP PROJ. NO. 3-17-0096-XX SHEET OF 31 SHEETS

CAOO4 K:\SpringfieldAp\0703502_SPI_TXY_F\Drow\Sheets
FILE: CONACTDETL.dwg UPDATE BY: Dave Allen PLOT DATE: B/3/2007 1:25 PM SPI_LOGO