


EROSION CONTROL FABRIC FENCE DETAIL


NOTES

- 1. WOVEN WIRE FENCE TO BE FASTENED SECURELY TO FENCE POSTS WITH WIRE TIES OR STAPLES.
- 2. FILTER CLOTH TO BE FASTENED SECURELY TO WOVEN WIRE FENCE WITH TIES SPACED EVERY 2'-0" AT TOP AND MID SECTION.
- 3. WHEN TWO SECTIONS OF FILTER CLOTH ADJOIN EACH OTHER THEY SHALL BE OVERLAPPED BY 6" MINIMUM AND FOLDED.
- 4. MAINTENANCE SHALL BE PERFORMED AS NEEDED AND MATERIAL REMOVED WHEN "BULGES" DEVELOP IN THE SILT FENCE. MAINTENANCE, WHICH INCLUDES THE REPLACEMENT OF DAMAGED FENCE SHALL BE CONSIDERED INCIDENTAL TO THE COST OF THE EROSION CONTROL FENCE.


EARTHWORK SUMMARY

STATION	EXCAVATE END AREA (S.F.)	EMBANK END AREA (S.F.)
0+75	220.18	0.00
1+00	92.15	31.96
1+50	56.06	0.76
2+00	66.40	0.11
2+50	78.49	0.00
3+00	76.24	0.00
3+50	71.12	0.31
4+00	62.67	12.97
4+50	65.18	19.81
5+00	65.65	24.29
5+50	77.29	11.11
6+00	99.29	0.10
6+50	196.33	11.18
6+99.55	533.81	0.00











DETAIL 3 - ANCHOR SLOT




DETAIL 5 - STAPLE DETAIL

NOTES

- STAPLES TO BE PLACED ALTERNATELY, IN COLUMNS APPROXIMATELY 2' APART AND IN ROWS APPROXIMATELY 3'
- 2. EROSION CONTROL MATERIAL SHALL BE PLACED LOOSELY OVER GROUND SURFACE. DO NOT STRETCH.
- ALL TERMINALS ENDS AND TRANSVERSE LAPS SHALL BE STAPLED AT APPROXIMATELY 12" INTERVALS.



INLET PROTECTION WITH FABRIC



INLET PROTECTION WITH STRAW BALES N.T.S.

CAOO4 K:\SpringfieldAp\0703502_SPI_TXY_F\Draw\Sheets FILE: ERODET.dwg UPDATE BY: Dove Allen
PLOT DATE: 8/3/2007 1:27 PM
SPI_LOGO

REVISIONS				
NUMBER	BY	DATE		
n	1	2		

THIS BAR IS EQUAL TO 2" AT FULL SCALE (34X22).



SPRINGFIELD AIRPORT AUTHORITY ABRAHAM LINCOLN CAPITAL AIRPORT SPRINGFIELD, ILLINOIS WIDEN TAXIWAY FOSION CONTROL DETAILS EARTHWORK SUMMARY ER &

CRAWFORD, I CONSULTING LICENSE NO. 18

RLV DRAWN BY: CMT CHECKED BY: RW APPROVED BY: RUN DATE: AUGUST 07, 2007 JOB No: 07035~02~00

IL. PROJ. NO. SPI-3711 AIP PROJ. NO. 3-17-0096-XX

SHEET 29 OF 31 SHEETS