-	/			TOTAL	SHEET	
	ROUTE	SECTION	COUNTY	SHEETS	NUMBER	
	VARIOUS	2012-042-I	COOK	20	4	

CONTRACT: 60V31

LOCATION	COMB. CONC. C & G R&R (LF)	HMA SURF R&R VARIABLE DEPTH (SQYD)	SALT TOLERANT SODDING (SQYD)	SIDEWALK 5" R&R (SQFT) 18" CARRIAGE/ COURTESY	SIDEWALK 5" R&R (SQFT) 5' PARALLEL	SIDEWALK 8" R&R (SQFT) 5' PARALLEL	DRIVEWAY 8" R&R (SQFT)	DETECTABLE WARNINGS (ADA RAMPS) (SQFT)	REMARKS
5931 West 59th Street	100.0	16.7	15.0	15.0	0.0	0.0	0.0	0.0	Replace 100 Feet of Broken Curb Along Mason Avenue Side of House
3810 West 60th Place	8.0	1.4	0.0	18.0	150.0	0.0	0.0	10.0	Install Depressed Curb For Handicapped Accessible Access, and Replace 6 Sidewalk Squares and 4 Courtesy Walk Squares
5838 West 63rd Place	0.0	0.0	0.0	0.0	200.0	0.0	840.0	0.0	Replace Alley In Concrete From 5822 to 5846 West 63rd Place, 2 Locations
4501 West 66th Place	0.0	0.0	0.0	9.0	600.0	0.0	0.0	0.0	Replace Entire Sidewalk On Front and Side of Home
3650 West 67th Place	0.0	0.0	0.0	0.0	225.0	0.0	0.0	0.0	9 Sidewalk Squares
3859 West 67th Place/3858 West 68th Street	10.0	1.7	0.0	4.5	100.0	150.0	700.0	20.0	Repair Alley Return/Apron In its Entirety With Concrete and ADA Ramps Behind These Two Listed Addresses That Share This Alley Return/Apron
3858 to 3854 West 68th Street	11.0	1.9	1.5	3.0	0.0	0.0	0.0	0.0	Replace 11 Feet of Broken Curb and Missing Gutter in Front of These Two Addresses
3901 West 68th Place/3900 West 69th Street	10.0	1.7	0.0	0.0	100.0	150.0	700.0	20.0	Repair Alley Return/Apron In its Entirety With Concrete and ADA Ramps Behind These Two Listed Addresses That Share This Alley Return/Apron
3816 West 68th Street	0.0	0.0	0.0	0.0	100.0	0.0	0.0	0.0	Replace 4 Sidewalk Squares
3834 West 68th Street	0.0	0.0	0.0	13.5	0.0	0.0	0.0	0.0	Replace 3 Sunken Carriage Walk Squares
3901 West 68th Street/3900 West 68th Place	10.0	1.7	0.0	0.0	100.0	150.0	700.0	20.0	Repair Alley Return/Apron In its Entirety With Concrete and ADA Ramps Behind These Two Listed Addresses That Share This Alley Return/Apron
3630 West 70th Street	30.0	5.0	3.4	15.0	0.0	0.0	0.0	0.0	Replace 30 Feet of Curb and Gutter In Front of Entire Length of Home
3634 West 70th Street	30.0	5.0	3.4	15.0	0.0	0.0	0.0	0.0	Replace 30 Feet of Curb and Gutter In Front of Entire Length of Home
3803 West Marquette Road/3800 West 67th Place	10.0	1.7	0.0	0.0	100.0	150.0	700.0	20.0	Repair Alley Return/Apron In its Entirety With Concrete and ADA Ramps Behind These Two Listed Addresses That Share This Alley Return/Apron
3859 West Marquette Road/3858 West 67th Place	10.0	1.7	0.0	0.0	100.0	150.0	700.0	20.0	Repair Alley Return/Apron In its Entirety With Concrete and ADA Ramps Behind These Two Listed Addresses That Share This Alley Return/Apron
3901 West Marquette Road/3900 West 67th Place	10.0	1.7	0.0	0.0	100.0	150.0	700.0	20.0	Repair Alley Return/Apron In its Entirety With Concrete and ADA Ramps Behind These Two Listed Addresses That Share This Alley Return/Apron
3757 West Marquette Road/6715 South Hamlin Avenue	10.0	1.7	0.0	0.0	100.0	150.0	700.0	20.0	Repair Alley Return/Apron In its Entirety With Concrete and ADA Ramps Behind These Two Listed Addresses That Share This Alley Return/Apron
4025 West Marquette Road/6715 South Komensky Avenue	10.0	1.7	0.0	0.0	100.0	150.0	700.0	20.0	Repair Alley Return/Apron In its Entirety With Concrete and ADA Ramps Behind These Two Listed Addresses That Share This Alley Return/Apron
6048 South Austin Avenue	0.0	0.0	0.0	0.0	25.0	0.0	0.0	0.0	Replace 1 Sidewalk Square
6052 South Austin Avenue	10.0	1.7	1.7	0.0	0.0	0.0	0.0	0.0	Repair Curb and Gutter In Front of This Address
6419 South Austin Avenue	30.0	5.0	1.7	30.0	0.0	0.0	0.0	0.0	Replace Courtesy Walk, and 30 Feet of Curb and Gutter in front of home. It is currently too high and too deep, and is causing a standing water issue.
6423 South Austin Avenue	0.0	0.0	0.0	0.0	50.0	0.0	0.0	0.0	Repair Caving-In Cement/Concrete In Front of This Address
7200 South Avers	7.0	1.2	1.2	0.0	0.0	0.0	0.0	0.0	Replace 7 Feet of Missing Gutter on Either Side of Adjacent Sewer Catch Basi on 72nd Street Side
SUB-TOTAL	306.0	51.5	27.9	123.0	2150.0	1200.0	6440.0	170.0	

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES