

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NUMBER
VARIOUS	2012-042-1	COOK	20	5

CONTRACT: 60V31

LOCATION	COMB. CONC. C & G R&R (LF)	HMA SURF R&R VARIABLE DEPTH (SQYD)	SALT TOLERANT SODDING (SQYD)	SIDEWALK 5" R&R (SQFT) 18" CARRIAGE/ COURTESY	SIDEWALK 5" R&R (SQFT) 5' PARALLEL	SIDEWALK 8" R&R (SQFT) 5' PARALLEL	DRIVEWAY 8" R&R (SQFT)	DETECTABLE WARNINGS (ADA RAMPS) (SQFT)	REMARKS
6412 South Karlov Avenue	0.0	0.0	0.0	36.0	150.0	0.0	0.0	0.0	Replace 6 Sidewalk Square, Courtesy Walk, and Carriage Walk
6558 South Keating Avenue	100.0	16.7	13.4	30.0	0.0	0.0	0.0	0.0	Replace 100 Feet of Broken, Cracked, and Low Curb and Gutter on the 66th Street of This Address - North Side of Street
6600 South Keating Avenue	100.0	16.7	13.4	30.0	0.0	0.0	0.0	0.0	Replace 100 Feet of Missing Curb and Gutter on the 66th Street of This Address - South Side of Street
6023 South Kenneth Avenue	12.0	2.0	0.4	15.0	150.0	0.0	0.0	0.0	replace 12 feet of curb and gutter
6559 South Kilbourn Avenue	20.0	3.4	0.0	0.0	50.0	0.0	30.0	0.0	Replace Side Driveway Apron & Adjacent Curb Around Perimeter of Driveway Apron Facing 66th Street
6058 South Kilpatrick Avenue	20.0	3.4	0.0	22.5	0.0	0.0	0.0	0.0	Replace Side Concrete Driveway Apron Facing 61st Street Side, Including Driveway Apron Curb and Gutter. There is currently a standing water issue here.
7759 South Kilpatrick Avenue	20.0	3.4	0.0	0.0	0.0	0.0	30.0	0.0	Replace Missing Curb and Gutter on 78th Street Side of Home Directly In Front of Driveway Apron
6058 South Kilpatrick Avenue/6059 South Keating Avenue	10.0	1.7	0.0	22.5	100.0	150.0	700.0	20.0	Repair Alley Return/Apron In its Entirety With Concrete and ADA Ramps Behind These Two Listed Addresses That Share This Alley Return/Apron
6459 South Knox Avenue	100.0	16.7	15.4	12.0	0.0	0.0	0.0	0.0	Replace 100 Feet of Curb and Gutter on the 65th Street of This Address, Between Knox Avenue and Train Tracks - North Side of Street
6500 South Knox Avenue	100.0	16.7	15.4	12.0	0.0	0.0	0.0	0.0	Replace 100 Feet of Curb and Gutter on the 65th Street of This Address - South Side of Street - Standing Water Issue Here.
6501 South Knox Avenue	100.0	16.7	15.4	12.0	0.0	0.0	0.0	0.0	Replace 100 Feet of Curb and Gutter on the 65th Street of This Address, Between Knox Avenue and Train Tracks - South Side of Street
6149 South Kostner Avenue	0.0	0.0	0.0	0.0	100.0	0.0	0.0	0.0	Replace 3 or 4 Sidewalk Squares
6340 South Kostner Avenue	0.0	0.0	0.0	0.0	150.0	0.0	0.0	0.0	Replace 6 Sidewalk Squares
6348 South La Crosse Avenue	0.0	0.0	0.0	0.0	25.0	0.0	0.0	10.0	Replace ADA Ramp on the SouthWest Corner of 6300 South La Crosse Avenue -
6349 South La Crosse Avenue	0.0	0.0	0.0	0.0	50.0	0.0	0.0	0.0	Replace 2 Sidewalk Squares
6351 South La Crosse Avenue	0.0	0.0	0.0	0.0	50.0	0.0	0.0	0.0	Replace Sidewalk Squares Impacted By The Sewer
6459 South Lamont Avenue	0.0	0.0	0.0	0.0	75.0	0.0	0.0	0.0	Replace 3 Raised Sidewalk Squares on 65th Street Side of House
6459 South Laporte Avenue/6458 South Lamont Avenue	10.0	1.7	0.0	0.0	100.0	150.0	700.0	20.0	Repair Alley Return/Apron In its Entirety With Concrete and ADA Ramps Behind These Two Listed Addresses That Share This Alley Return/Apron, Facing 65th Street
6751 South Lawndale Avenue	0.0	0.0	0.0	0.0	150.0	0.0	0.0	0.0	Replace 6 Cracked, Broken Sidewalk Squares
6000 South Major Avenue	20.0	3.4	0.0	0.0	0.0	0.0	30.0	0.0	Replace Side Concrete Driveway Apron Facing 60th Street Side
6025 South Mason Avenue	0.0	0.0	0.0	22.5	150.0	0.0	0.0	0.0	Replace 6 Sidewalk Squares, 2 Courtesy Walk Squares, and 3 Carriage Walk Squares
6001 South Massasoit Avenue	20.0	3.4	0.0	0.0	0.0	0.0	30.0	0.0	Replace Side Concrete Driveway Apron Facing 60th Street Side
6001 South Massasoit Avenue/6000 South Major Avenue	10.0	1.7	0.0	0.0	100.0	150.0	700.0	20.0	Repair Alley Return/Apron In its Entirety With Concrete and ADA Ramps Behind These Two Listed Addresses That Share This Alley Return/Apron
SUB-TOTAL	642.0	107.6	73.4	214.5	1400.0	450.0	2220.0	70.0	

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES