



NOTES:
1. APPROXIMATELY 100 RAISED REFLECTIVE PAVEMENT MARKERS ARE TO BE REMOVED EAST OF WEBER ROAD. THESE MARKERS WILL NOT BE REPLACED.

LEGEND

- BUTT JOINT
- EXISTING MANHOLE
- EXISTING CATCH BASIN
- COMBINATION B-6.24 CURB AND GUTTER REMOVAL AND REPLACEMENT
- HMA SIDEWALK REMOVAL & P.C. CONCRETE SIDEWALK REPLACEMENT
- P.C. CONCRETE SIDEWALK REMOVAL AND REPLACEMENT (5")
- PAVEMENT REMOVAL WITH CLASS D PATCH, 10"
- STRUCTURE TO BE ADJUSTED
- PAVEMENT REMOVAL WITH PCC PAVEMENT, 10" (JOINTED) REPLACEMENT
- DETECTOR LOOP TO BE REPLACED

SEE ENLARGED VIEW FOR DIMENSIONS

END IMPROVEMENTS STA 164+45

NO EASTBOUND TRAFFIC SHALL BE STAGED ON THE WESTBOUND LANES DURING PAVEMENT REPLACEMENT OPERATIONS.

FILE NAME = 11617-PLAN 01 - IDOT P05	USER NAME =	DESIGNED — JH	REVISED —	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	TAYLOR ROAD ROADWAY RESURFACING PAVEMENT PLAN		F.A.U. RTE 0286	SECTION 12-00059-00-RS	COUNTY WILL	TOTAL SHEETS 26	SHEET NO. 11	
	PLOT SCALE =	DRAWN — ACAD	REVISED —		SCALE:	SHEET NO. 11 OF 26 SHEETS	STA.	TO STA.	CONTRACT NO. 63727			
	PLOT DATE = 05-02-12	CHECKED — ACAD	REVISED —				FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT M-4003(021)					