

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0004 US 50 80% Fed 20% State		
20200100	EARTH EXCAVATION	CU YD	11021	11021		
20400800	FURNISHED EXCAVATION	CU YD	904	904		
20700220	POROUS GRANULAR EMBANKMENT	CU YD	12.9	12.9		
20800150	TRENCH BACKFILL	CU YD	121	121		
X 25000210	SEEDING, CLASS 2A	ACRE	5	5		
X 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	418	418		
X 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	418	418		
X 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	418	418		
X 25100115	MULCH, METHOD 2	ACRE	5	5		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1398	1398		
28000305	TEMPORARY DITCH CHECKS	FOOT	877	877		
28000500	INLET AND PIPE PROTECTION	EACH	7	7		
28100105	STONE RIPRAP, CLASS A3	SQ YD	24	24		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0004 US 50 80% Fed 20% State		
28200200	FILTER FABRIC	SQ YD	24	24		
30200650	PROCESSING MODIFIED SOIL 12"	SQ YD	5166	5166		
30200850	PROCESSING MODIFIED SOIL 16"	SQ YD	488	488		
30201050	PROCESSING MODIFIED SOIL 20"	SQ YD	1878	1878		
30201500	LIME	TON	73	73		
31101900	SUBBASE GRANULAR MATERIAL, TYPE C	TON	293	293		
35100700	AGGREGATE BASE COURSE, TYPE A 8"	SQ YD	973	973		
40200100	AGGREGATE SURFACE COURSE, TYPE A	TON	86	86		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	3	3		
40600300	AGGREGATE (PRIME COAT)	TON	10	10		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	78	78		
40600990	TEMPORARY RAMP	SQ YD	76	76		
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	3584	3584		

*X*SPECIALTY ITEM

FILE NAME *	USER NAME * bergnd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pvc\work\pavdot\bergnd\d8160887\d876d23\ahc-plan.dgn		DRAWN -	REVISED -			327	21-1-1, 27-1	CLINTON	96	3	
PLOT SCALE = 100.0000' / in.		CHECKED -	REVISED -			CONTRACT NO. 76D53					
PLOT DATE = 6/15/2012		DATE -	REVISED -			SCALE:	SHEET NO. 1 OF 4 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT