SIGN SCHEDULE

LOCATION EXISTING STATION	LOCATION EXISTING OFFSET	LOCATION PROPOSED STATION	LOCATION PROPOSED OFFSET*	IDENTIFIER	DESCRIPTION	SIGN SIZE EXISTING W	SIGN SIZE EXISTING H	SIGN SIZE PROPOSED W	SIGN SIZE PROPOSED H	REMOVE SIGN PANEL TYPE 1 SQ FT	REMOVE SIGN PANEL TYPE 2 SQFT	REMOVE SIGN PANEL ASSEMBLY TYPE A EACH	REMOVE SIGN PANEL ASSEMBLY TYPE B EACH	REMOVE GROUND MOUNTED SIGN SUPPORT EACH	RELOCATE SIGN PANEL TYPE 2 SQ FT	SIGN PANEL TYPE 1 SQ FT	SIGN PANEL TYPE 2 SQ FT	WOOD SIGN SUPPORT FT
US 50																		
698+98	28' RT			W1-7	LT/RT ARROW	60	30				12.5			1				
699+35	42' LT				SHATTUC RD	24	9					3		1				
					US 50	24	9											
700+95	26' RT			M1-4	US 50	24	24			4				1				
		701+67	18' LT	W10-1	RAILROAD			ROUND	36							7.1		18.5
		702+00	18' LT	R2-1	SPEED LIMIT			30	36							7.5		18.5
		703+50	18' LT	M1-4	US 50			36	36							9		17
		705+00	18' LT	W1-7	LT/RT ARROW			60	30								12.5	14.5
		706+50	18' RT	M1-4	US 50			36	36							9		16
		707+97	18' LT	R3-1100	LEFT TURN LANE			24	24							4		15
		708+00	18' RT	R2-1	SPEED LIMIT			30	36							7.5		16.5
702+97	25' LT	709+50	18' LT		LAB/SHATTUC	72	36	72	36		18			2	18			30
705+00	28' LT	711+50	18' LT		KASK COLL/COR CENTER	72	30	72	30		15			2	15			29
707+41	28' LT			W2-1	CROSSROAD	36	36						12.1	1				
					SHATTUC RD	30	15											
709+07	26' RT			W14-3	NO PASSING ZONE	59.3	48				19.8			1				
709+14	27' LT			W10-1	RAILROAD	36	ROUND						13.3	1				
				W8-1	BUMP	30	30											
EXISTING SHATTUC ROAD																		
90+05	20' RT			W3-1A	STOP AHEAD - GRAPHIC	36	36			9				1				
94+11	20' RT			W10-4	RR AHEAD RT	30	30			6.3				1				
98+25	19' LT			M1-5	CILTON CO RD 5	24	24					7.5		1				
					SHATTUC RD	24	3											
				R12-1	WEIGHT LIMIT 15 TONS	18	24											
99+43	22' RT			R1-1	STOP	36	36						13.5	1				
				R1-1100	CROSS TRAFFIC	36	18											
99+54	22' RT			R1-1	STOP	36	36						13.5	1				
				R1-1101	CROSS TRAFFIC	36	18											
PROPOSED SHATTUC ROAD																		
		97+67	16.5' RT	W3-1A	STOP AHEAD - GRAPHIC			36	36							9		16.5
		97+67	16.5' LT	W3-1A	STOP AHEAD - GRAPHIC			36	36							9		18
		100+92	16.5' RT	R1-1	STOP			36	36							9		18
TOTALS										19.3	65.3	10.5	52.4	15.0	33.0	71.1	12.5	227.5

*PROPOSED OFFSETS ARE FROM EDGE OF PAVEMENT TO CENTERLINE OF SIGN PANEL

FURNISHING & ERECTING RIGHT OF WAY MARKERS			FURNISHING & ERECTING RIGHT OF WAY MARKERS		
ROUTE	STATION	OFFSET	ROUTE	STATION	OFFSET
US 50	697+89.60	55.06' RT	Shattuc Rd. Proposed	81+50.00	40.59' RT
US 50	697+88.38	54.94' LT	Shattuc Rd. Proposed	81+50.00	39.41' LT
US 50	697+93.74	32.94' LT	Shattuc Rd. Proposed	82+50.00	50.61' RT
US 50	698+89.34	59.70' LT	Shattuc Rd. Proposed	82+50.00	50.00' LT
US 50	698+90.58	54.94' LT	Shattuc Rd. Proposed	83+29.43	50.00' LT
US 50	699+19.92	55.05' RT	Shattuc Rd. Proposed	84+92.97	61.07' RT
US 50	701+00.00	54.96' LT	Shattuc Rd. Proposed	85+88.28	66.83' RT
US 50	702+94.44	55.03' RT	Shattuc Rd. Proposed	87+77.00	50.00' LT
US 50	702+94.44	54.97' LT	Shattuc Rd. Proposed	90+19.35	154.48' RT
US 50	703+93.80	54.95' LT	Shattuc Rd. Proposed	90+22.38	50.00' RT
US 50	705+94.02	54.91' LT	Shattuc Rd. Proposed	92+25.03	50.00' LT
US 50	706+00.00	40.10' RT	Shattuc Rd. Proposed	92+25.03	50.00' RT
US 50	708+00.00	54.86 LT	Shattuc Rd. Proposed	94+01.03	50.00' RT
US 50	711+00.00	40.21' RT	Shattuc Rd. Proposed	94+01.03	50.00' LT
US 50	711+00.00	32.79' LT	Shattuc Rd. Proposed	97+15.00	50.00' LT
US 50	712+00.00	33.23' RT	Shattuc Rd. Proposed	97+15.00	50.00' RT
			Shattuc Rd. Proposed	100+28.93	50.00' LT
			Shattuc Rd. Proposed	100+28.93	50.00' RT
			Shattuc Rd. Proposed	100+49.75	50.00' RT
			Shattuc Rd. Proposed	100+59.29	50.00' LT
			Total Quantity		36

RIGHT OF WAY/PROPERTY CORNERS		
Shattuc Rd. Prop.	83+29.43	50.00' LT
Shattuc Rd. Prop.	90+22.72	50.00' RT
US 50	698+90.58	54.94' LT
US 50	698+89.34	59.70' LT
Total Quantity		4

SECTION CORNERS		
Sta	O/S	Location
698+92.88 (US 50)	14.45' LT	E 1/4 Corner Section 16, T2NR1W
Total Quantity		1

FILE NAME = #FILE#	USER NAME = bergnd	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE =	CHECKED -	REVISED -
	PLOT DATE =	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: NONE | SHEET NO. 4 OF 4 SHEETS | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
327	21-1-1, 27-1	CLINTON	96	13

CONTRACT NO. 76D53

ILLINOIS FED. AID PROJECT