## INDEX OF SHEETS

- COVER SHEET
- 2. INDEX OF SHEETS, HIGHWAY STANDARDS, GENERAL NOTES, COMMITMENTS
- 3 4, SUMMARY OF QUANTITIES
- 5. -7. TYPICAL SECTIONS
  - 8. SCHEDULE OF QUANTITIES WIDELOAD SIGNING
- 10. PLAN VIEW

9,

- 11. 12. STAGE 1 CONSTRUCTION
- 13.- 14. STAGE II CONSTRUCTION
- 15. 27. STRUCTURE PLANS
  - 28. DETAILS

## HIGHWAY STANDARDS

000001-06 001001-02

001006

701006-03 701011-02

701306-03

701311-03 701321-12

701326-04 701422-04 701901-02

704001-07 780001-03 781001-03

COMMITMENTS

NONE

## GENERAL NOTES

- 1. THE STANDARDS AND REVISION NUMBERS SHALL APPLY TO THIS PROJECT.
- 2. THE CONTRACTOR AND THE ENGINEER SHALL BE AWARE THAT NO SURVEY WAS PERFORMED FOR THIS PROJECT. THE STATIONING AND TOPOGRAPHY SHOWN IN THE PLANS WAS CREATED USING MICROFILM AND FIELD MEASUREMENTS. BOTH SHALL BE ASSUMED TO BE APPROXIMATE. THE CONTRACTOR SHALL VERIFY DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.
- 3. ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE BE GIVEN TO ALL UTILITIES BEFORE DIGGING. FIELD MARKING OF FACILITIES MAY BE OBTAINED BY CONTACTING JULLIE, OR FOR NON-MEMBERS, THE UTILITY COMPANY DIRECTLY, AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:
  - AMEREN ILLINOIS
  - AT&T ILLINOIS
  - CHARTER COMMUNICATIONS
  - . NORTHEAST CENTRAL COUNTY PUBLIC WATER DISTRICT

MEMBERS OF J.U.L.I.E. CALL TOLL FREE (800) 892-0123 OR 811 AND ARE INDICATED BY . NON-J.U.L.I.E. MEMBERS MUST BE NOTIFIED INDIVIDUALLY.

- 4. ALL TURF AREAS DISTURBED BY THE CONTRACTOR SHALL BE SEEDED WITH THE APPROPRIATE EROSION CONTROL AS DIRECTED BY THE ENGINEER AT THE CONTRACTOR'S EXPENSE.
- 5. THE PROPOSED PAVEMENT MARKING SHALL MATCH THE LOCATIONS OF THE EXISTING PAVEMENT MARKING, AS DIRECTED BY THE ENGINEER.
- 6. THE FOLLOWING MIXTURE REQUIREMENTS ARE APPLICABLE FOR THIS CONTRACT:

MIXTURE USE	SURFACE	WIDENING			
AC/PG	PG 64-22	PG 64-22			
RAP % (MAX)	SEE SPEC.	SEE SPEC.			
DESIGN AIR VOIDS	4.0% @ Ndes=70	4.0% @ Ndes=70			
MIX COMPOSITION					
(GRADATION MIXTURE)	IL 9.5	IL 19.0			
FRICTION AGG	MIXTURE "C"	MIXTURE "B"			

PLAN QUANTITIES FOR HOT-MIX ASPHALT SURFACE COURSE ITEMS ARE CALCULATED USING A UNIT WEIGHT

- 7. THE DEPARTMENT STRONGLY ENCOURAGES THE PRIME CONTRACTOR AND THEIR APPROVED SUB-CONTRACTORS TO HIRE MINORITY, WOMEN AND DISADVANTAGED INDIVIDUALS FROM ITS FEDERALLY FUNDED HIGHWAY CONSTRUCTION CAREERS TRAINING PROGRAM (HCCTP) TO HELP MEET WORKFORCE AND TRAINEE GOALS. THIS PROGRAM IS TRAINING MINORITIES, WOMEN AND DISADVANTAGED INDIVIDUALS IN HIGHWAY CONSTRUCTION-RELATED SKILLS, E.G., MATH FOR THE TRADES, JOB READINESS, TECHNICAL SKILLS COURSEWORK (CARPENTRY, CONCRETE FLATWORK, BLUEPRINT READING, SITE PLANS, SITE WORK, TOOLS USE, ETC.) AND OSHA 10 HOUR CERTIFICATION, TO PREPARE THEM FOR A CAREER IN THE HIGHWAY CONSTRUCTION TRADES, GRADUATES ARE WELL-TRAINED AND READY TO BECOME PRODUCTIVE ENTRY-LEVEL CONSTRUCTION WORKERS, CONTACT THE DISTRICT 8 EEO OFFICE AT 618-346-3360 AND/OR THE HCCTP COORDINATOR AT 618-874-6528 TO LEARN MORE ABOUT THE PROGRAM AND FOR ASSISTANCE IN MEETING WORKFORCE AND TRAINEE GOALS.
- 8. A QUANTITY OF 6061 FEET OF "TEMPORARY PAVEMENT MARKING LINE 6" WHITE HAS BEEN INCLUDED IN THE PLANS FOR PAINTING THE BOTTOM 6" OF THE TEMPORARY CONCRETE BARRIER.
- 9. ACCESS SHALL BE MAINTAINED TO ALL PROPERTIES UNLESS OTHERWISE NOTED IN THE PLANS.
- 10. THE CONTRACTOR SHALL RELOCATE MAILBOX 5776 WEST ON THE SAME SIDE OF THE STREET TO A TEMPORARY LOCATION NEAR MAILBOX 5729 AND RETURN IT TO ITS ORIGINAL LOCATION OUNCE CONSTRUCTION HAS BEEN COMPLETED. THIS WORK SHALL BE DONE ACCORDING TO ART. 107.20 OF THE STANDARD SPECIFICATIONS.

<u> </u>		· · · · · · · · · · · · · · · · · · ·	·									Į.
FILE NAME	*	USER NAME = #USER#	DESIGNED -	REVISEDA - 9- 13-12						CH	CECTION	TOTAL SHEET
#FILEL#	1		DRAWN -	REVISED -	STATE OF ILLINOIS	INDEX OF SHEETS, GENERAL NOTES, HIGHWAY STANDARDS, AND COMMITMENTS		RTE.	SECTION	COUNTY SHEETS NO.		
	in the second se	PLOT SCALE = #SCALE#	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION			<u> </u>	1-HB-1	MADISON 28 2		
L		PLOT SATE # * DATE*	DATE -	REVISED -	Services of their offices	SCALE: N/A	SHEET NO. 1 OF 1 SHEETS	TSTA	TO STA	l		CONTRACT NO. 76F62
		V	<del>'</del>	<del></del>	· · · · · · · · · · · · · · · · · · ·	1 00000000	1 DACCT HOL 1 OF I SHILLIS	JIA.	10 31A.	FED. ROAD DIST.	NO.   ILLINOIS FED.	A3D PROJECT