

Holes in the masonry for anchor bolts shall be drilled through the base plates to the diameter and depth shown or according to the manufacturer's recommendation after beams or girders have been erected and adjusted. Prior to setting the bolts, the holes shall be dry and all dust and loose particles shall be removed by the use of compressed air or vacuuming. The anchor bolts, furnished and installed and including the epoxy grout or capsules shall not be paid for separately but shall be included in the unit bid price for Furnishing and Erecting Structural Steel.

			CONTRA	ACT NO.	60B86
F.A.I. RTE.	SECTION	C	DUNTY	TOTAL SHEETS	SHEET NO.
55	2006-032 E	37	WILL	505	282
STA.		TO S	STA.		
FED. RO	AD DIST. NO. I	LLINOIS	FED. AI	D PROJECT	-

## GENERAL NOTES

	SHT. SC-23 OF 2 REVISIONS NAME	3 <b>8</b> 	ILLINOIS DEPARTMENT OF TRANSPORTATION FAI ROUTE 55 US 30 (PLATHEILD ROAD) TO LILY CACHE SLOUGH SB & NB I-55 OVER US RTE. 30, S.N. 099-0016 & 099-0017 STA. 587+80.82, SECTION 2006-032 BY WILL COUNTY ANCHOR BOLT DETAILS				
INC.			SCALE: DATE 07/05/	06		BY PA DBY MJK	
			TEN	ENGI ENGI	& ASSOCIATES, INC. NEERS/ARCHITECTS/PI AGO, ILLINOIS	ANNERS	